

US EPA RECORDS CENTER REGION 5



466896

**CONCEPTUAL WORK PLAN
ALTERNATE REMEDY**

**ACS NPL SITE
GRIFFITH, INDIANA**

Prepared For:

ACS RD/RA Group

Prepared By

**Montgomery Watson
2100 Corporate Drive
Addison, Illinois 60101**

August 1998



MONTGOMERY WATSON

EXECUTIVE SUMMARY

The ACS site is a 33-acre parcel of land, including a currently active chemical manufacturing plant located at 420 South Colfax Avenue in Griffith, in the northwest corner of Indiana. The Site began reclaiming spent solvent wastes in 1955, and continues to manufacture specialty chemicals. Based on the findings of an RI/FS and subsequent studies and groundwater sampling, three primary contaminant source areas have been identified at the Site: the On-Site Containment Area, the Still Bottoms Pond Area, and the Off-Site Containment Area. Identified contaminants of concern include volatile organic compounds ("VOCs") in the soil and groundwater and PCBs in the soil. This Site was placed on the National Priorities List in 1984 and a Record of Decision ("ROD") was issued on September 30, 1992. The ROD specified groundwater pump-and-treat, low temperature thermal treatment ("LTTT") of buried waste and contaminated soils, in-situ vapor extraction ("ISVE") of contaminated soils, drum removal from the On-Site Containment Area and groundwater monitoring for remedial action at the Site. This document outlines an alternate remedial action which replaces the LTTT with a more extensive containment and ISVE application which is equally protective, and more technically and cost effective than the LTTT.

Groundwater pump-and-treat and groundwater monitoring have already been implemented to some extent at the site. In addition, a polyethylene and bentonite slurry containment barrier was constructed around the Site source areas. One foot of clay cover has also been placed on the Off-Site Containment Area. These containment measures effectively isolate the source areas from further contaminating the groundwater. In response to the ROD requirement for LTTT, a materials handling and LTTT study were undertaken to determine the feasibility of LTTT at the Site. The results of the study determined that even though LTTT can be effective at treating organic compounds, implementing the technology at the ACS Site would be extremely difficult based on complications with buried debris, municipal waste, fugitive vapor loss, and potential for explosions during excavation and treatment. Therefore, an alternate to manage the organics at the Site needed to be developed.

The alternate remedy incorporates the groundwater pump-and-treat and ISVE requirements of the ROD, and will meet the general remedial objectives of the ROD. The alternate remedy approach includes the following components:

- Enhancement of the current containment systems in the Still Bottoms Pond and Off-Site Containment Areas by covering to reduce infiltration and prevent direct contact with contaminants.
- Mass removal of mobile VOC contaminants through the use of ISVE in the Still Bottoms Pond and Off-Site Containment Areas.
- Elimination of a primary potential source of contaminants by excavating drums from the On-Site Containment Area and disposing of the contents off-site.

- Removal of the PCB-impacted sediments in the wetlands area by excavating sediments and consolidating them on-site in a contained area.
- Continued operation of the groundwater pump and treat system.
- Enhanced bio-remediation and long term monitoring of the contaminated groundwater at the Site

Application of ISVE to remove VOC contaminants will be conducted first in the Off-Site Area, where there is sufficient vadose zone to implement ISVE. In addition, the water table will be lowered in this area while the ISVE system is running to expose additional contaminants to the ISVE and thereby increase the mass of VOCs removed. A phased approach to ISVE start-up will be implemented, so that the vapor treatment system for the ISVE system can be optimized and operated as efficiently as possible. Once the ISVE system is optimized with the lowered water table in the Off-Site Containment Area, the ISVE system will be applied to the second significant source area; the Still Bottoms Pond Area. The water table will also be lowered in this area to increase the effectiveness of the ISVE application. Again, a phased approach to start-up will be conducted to maximize the treatment system efficiency and optimize contaminant recovery.

Both the Still Bottoms Pond Area and the Off-Site Containment Area will be covered with an impervious material which will provide a surface seal for the ISVE system, reduce infiltration of rainwater and prevent direct contact with exposure to contaminants and vapors from those contaminants. The initial cover layers will be installed as part of the start-up of the ISVE systems. Once the ISVE systems are in place and have been optimized, the final layers of the covers will be installed.

The ISVE system will continue to be applied to the two contaminated soils areas, the Off-Site Containment Area and the Still Bottom Pond Area, until data indicates that the system is no longer removing significant masses of contaminants as demonstrated by reaching the asymptotic limit of the VOC recovery rate. Current estimates indicate that the systems will be applied for approximately 10 years, and pulsing or other operational modifications will be considered to maximize efficiency and minimize supplemental fuel use, reducing the total emissions from the off-gas treatment system(s).

Coordination of the remedial actions with the ongoing chemical plant operations will be required as long as the chemical plant continues to operate on-Site. The chemical plant currently uses the Still Bottoms Pond Area and several adjacent areas, which will be covered and treated with ISVE, for transport and some operations. The need to modify the remedial actions to accommodate continued operation of the plant may result in modified work schedules and costs.

The alternate remedy is a robust system, capable of complying with the ROD objectives for remedial action at the Site. The combination of continued groundwater pumping and treatment, covering for containment, ISVE for source reduction, and source removal in the On-Site Containment Area and wetlands, will adequately address the risks at the Site.

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
EXECUTIVE SUMMARY	I
1.0 INTRODUCTION.....	1
1.1 SITE LOCATION AND SURROUNDING AREA	1
1.2 SITE BACKGROUND	1
1.3 WASTE CHARACTERIZATION.....	3
1.3.1 Source Areas	4
1.4 CHEMICALS OF CONCERN	4
1.4.1 Volatile Organic Compounds.....	5
1.4.2 Polychlorinated Biphenyls	5
1.4.3 Inorganics	6
1.5 RISK ASSESSMENT	6
2.0 CONCEPTUAL REMEDIAL WORK PLAN	7
2.1 ROD REMEDY	7
2.2 ALTERNATE REMEDY	11
3.0 IN-SITU SOIL VAPOR EXTRACTION	13
3.1 AREAS TO BE TREATED WITH ISVE.....	14
3.2 ISVE MODELING.....	15
3.3 PRELIMINARY DESIGN CONSIDERATIONS	16
3.3.1 ISVE Effectiveness Around Buried Debris and Waste	16
3.3.2 Free Phase Product.....	16
3.3.3 Smearing	17
3.3.4 Short Circuiting	17
3.4 DESIGN	18
3.4.1 Extraction Wells and Piping.....	18
3.4.2 Vacuum Blower System.....	19
3.4.3 Condensate Removal System.....	19
3.5 EXTRACTED VAPOR TREATMENT SYSTEM	20
3.6 COMPLIANCE AND PERFORMANCE MONITORING.....	20
3.7 PHASED START-UP	21
3.7.1 Scenario 1 – Gradual Decline.....	23
3.7.2 Scenario 2 – Moderate Decline	23
3.7.3 Scenario 3 – Exponential Decline	24
3.8 LONG-TERM OPERATION AND SHUTDOWN CRITERIA.....	25
3.8.1 Stage 1 – Advective Transport Regime.....	25
3.8.2 Stage 2 – Diffusive Transport Regime.....	26

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
4.0 DEWATERING	28
4.1 ALTERNATES EVALUATION	28
4.2 SELECTED ALTERNATIVE	29
5.0 COVER AND COVER DESIGN	31
5.1 Cover Regulations	31
5.1.1 Methane Collection	32
5.1.2 Drainage Layer	32
5.2 ALTERNATIVES EVALUATION	32
5.3 PROPOSED COVERS	33
5.3.1 Still Bottoms Pond Area	33
5.3.2 Off-Site Containment Area	35
5.4 SURFACE WATER DRAINAGE CONTROL	35
5.5 COVER IMPLEMENTATION	35
6.0 DRUM REMOVAL IN THE ON-SITE CONTAINMENT AREA	36
6.1 DRUM REMOVAL WORK PLAN	36
7.0 OFF-SITE GROUNDWATER TREATMENT	37
7.1 DESCRIPTION OF UPPER AQUIFER CONTAMINATION	37
7.1.1 North Area	38
7.1.2 South Area	39
8.0 MISCELLANEOUS ACTIVITIES	40
8.1 REMOVAL AND CONSOLIDATION OF PCB-IMPACTED SEDIMENTS IN THE DRAINAGE SWALE	40
8.2 CONSOLIDATION OF MISCELLANEOUS DEBRIS	40
8.3 GROUNDWATER TREATMENT PLANT UPGRADE	41
8.3.1 Install a Second Air Stripper	41
8.3.2 Provide Outside Air Intakes for the Air Strippers	41
8.3.3 Install Filter Upstream of the GAC Cells	41
8.3.4 Phase Separator Installation	42
8.3.5 Coagulant Delivery System	42
8.3.6 Install a Final Biological Groundwater Treatment System	42
8.4 COORDINATION WITH THE ACS PLANT UTILITIES	43

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
9.0 PROPOSED PROJECT SEQUENCING.....	44
10.0 REFERENCES.....	45

LIST OF TABLES

	<u>Page</u>
Table 1 Technologies Evaluated During Feasibility Study.....	10
Table 2 HELP4 Results from Modeled Scenarios.....	34

LIST OF FIGURES

Figure 1	Proposed Remedial Components
Figure 2	Areas of Soils Impact
Figure 3	Still Bottoms Pond Area Cross Section
Figure 4	Off-Site Containment Area Cross Section
Figure 5	Off-Site Containment Area – ISVE System Phase Startup
Figure 6	Still Bottoms Pond Area – ISVE System Phased Startup
Figure 7	Typical Wellhead Detail
Figure 8	Conceptual Process Flow
Figure 9	Conceptual Cover Plan – Still Bottoms Pond Area
Figure 10	Conceptual Cover Plan – Off-Site Containment Area
Figure 11	Conceptual Cover Plan – Oxygen Release Compound Injection Area
Figure 12	ACS Facility Utilities and Site Preparation
Figure 13	ACS Conceptual Sequence – Remedial Action

LIST OF APPENDICES

Appendix A	VOC Mass Calculations
Appendix B	ISVE Modeling Results
Appendix C	Dewatering Calculations
Appendix D	HELP® Model Results

1.0 INTRODUCTION

This document presents the conceptual design for an alternate final remedy at the American Chemical Service (ACS) site. The ACS site is a 33-acre parcel of land, including an active chemical manufacturing plant located at 420 South Colfax Avenue in Griffith, in the northwest corner of Indiana. This Site was placed on the National Priorities List in 1984 and a Record of Decision (ROD) was issued on September 30, 1992. The ROD required treatability studies and indicated Low-Temperature Thermal Treatment (LTTT) would be used for treatment of buried waste in the Off-site Containment Area and for VOC contaminated soil unable to be treated by in-situ soil vapor extraction (ISVE). The results of the 1997 Material Handling and LTTT treatability studies (1,2) showed that LTTT treatment would not safely achieve the goals of the ROD. Therefore, at the request of U.S. EPA, an alternate final remedy has been developed.

1.1 SITE LOCATION AND SURROUNDING AREA

The Site is bordered on the east and northeast by Colfax Avenue as shown on Figure 1. An abandoned leg of the Chesapeake and Ohio Railway bisects the Site in a northwest-southeast direction, between the fenced ACS operating facility (north) and the fenced Off-Site Containment Area (south). ACS now owns these tracks and operates them strictly for holding and switching tank cars. The Site is bordered on the south by the Griffith Municipal Landfill (closed) and the abandoned Erie and Lackawanna Railway. On the north, the Site is bordered by the Grand Trunk Railroad and to the west by wetlands areas.

Approximately 33 acres are present within the Site, with the on-site area (ACS operating facility) covering 15 acres, and the Off-Site Containment Area and Kapica-Pazmey Area (at the southern end of the Site, where a former drum recycler was located) covering 13 acres. The wetlands to the west of the Site make up approximately 5 acres.

1.2 SITE BACKGROUND

The site began operations in 1955, with reclamation of spent solvent waste. The site accepted solvent mixtures containing alcohols, ketones, esters, chlorinateds, aromatics, aliphatics, and glycols which contained various residues. Other processes that have operated at the site since 1955 include specialty chemical manufacturing in small batches, burning of still bottoms and non-reclaimable materials in incinerators (1965-1970), epoxidation and bromination operations, and storage and blending of waste streams for ACS's secondary fuel program.

The approximate area of drum storage was a 250-foot by 450-foot parcel, located in the northern third of the fenced ACS facility. The drum storage area was visible in a 1970 aerial photograph. However, an aerial photograph from 1973 indicates that the area was

clear with no sign of drums on the ground surface. Approximately 400 drums containing sludge and semi-solids of unknown types were reportedly disposed of inside the plant (this area was named the "On-Site Containment Area")

From 1988 to 1992, a Remedial Investigation/Feasibility Study was conducted at the Site. In 1992, a ROD was executed which described the remedial action to be implemented on the site. The remedial action identified in the ROD is discussed in Section 2 of this Plan.

During the RI in the late 1980s, a test pit was excavated in the On-Site Containment Area, where drums were thought to be buried. Drums were found to be buried on their sides, stacked 3-high and closely packed together. Various liquids were observed in soil surrounding some of the drums, such as brownish water, and an oil-like liquid. In addition, a viscous blue liquid was observed leaking from several drums. The majority of the drums were noted to be dented and corroded, but largely intact. Construction activities conducted during installation of the Perimeter Groundwater Containment System (PGCS) and Barrier Wall Extraction System (BWES) verified the presence of buried drums stacked 3-high in the On-Site Containment Area. A geophysical investigation was subsequently conducted in February 1998 to determine the extent of the buried drums in the On-Site Containment Area. Based on past RI results, recent construction activities, and the 1998 geophysical investigation, two areas of buried drums were identified, and are shown on Figure 1.

The Still Bottoms Pond Area, located in the central portion of the ACS facility, served as a repository for still bottoms waste from the solvent recycling process. This area contained a pond and "treatment lagoon" where still bottoms were disposed. The pond and lagoon have since been filled in with drum carcasses, rubble, soil, and other debris. During the RI, many borings were advanced in this area, and the concentrations of contaminants in the area indicate that it is a significant source area on Site. Further description of the extent of contamination is included in Section 1.3.

The wetlands to the west of the ACS facility were investigated in 1996 to determine the extent of impact from facility operation on the wetlands. Analytical samples collected during this investigation indicated that certain localized sediments in the wetlands area were contaminated with polychlorinated biphenyls (PCBs). These PCBs likely were transported from the facility via surface water runoff from the facility which drained into the wetlands areas.

The Off-Site Area of the Site is located south of the ACS facility railroad tracks and encompasses the Off-Site Containment Area and the Kapica-Pazmey building area. A large portion of the Off-Site Area is essentially a continuation of the Town of Griffith landfill. During the RI, installation of soil borings indicated contaminated areas in the central and southern portions of the Off-Site Area. The barrier wall construction, because it required excavation of several hundred feet at the perimeter of the Off-Site Area, verified the landfilled nature of the area. During the Material Handling/LTTT Study, a portion of the central Off-Site Area was found to contain many deteriorated drum carcasses and parts. This area is also a significant source area on Site.

In February 1997, as part of the expedited interim remedial measures, a groundwater pump and treatment system was installed in the wetland area. The pumping system referred to as the Perimeter Groundwater Containment System (PGCS), provides containment for a groundwater plume in the northwest portion of the Site. In addition, a groundwater treatment system, including phase separation, UV/oxidation, precipitation, filtration, air stripping, and carbon adsorption, was constructed to treat groundwater from the PGCS.

In 1997, a continuous barrier wall was installed around the On-Site Containment Area, the ACS operating facility, the Off-Site Containment Area and the Kapica-Pazmey Area. The barrier wall encloses the known source areas at the Site. A groundwater extraction system inside the barrier wall, comprised of eight 100-foot long extraction trenches, was installed to maintain a hydraulic capture zone within the barrier wall, and is referred to as the Barrier Wall Extraction System (BWES). Groundwater from the BWES is also treated in the groundwater treatment system.

The PGCS has been operated since March of 1997, and the BWES was started-up in May 1997. Groundwater from these systems continues to be treated through the groundwater treatment system. Based on the performance data collected to date, these interim systems have successfully, isolated the source areas of the Site thus preventing further off-site groundwater contamination from occurring and providing active treatment of groundwater from within the barrier wall (BWES) and in the northeast portion outside the barrier wall (PGCS).

1.3 WASTE CHARACTERIZATION

The interim remedial measures cut off the groundwater migration pathways from the source areas and provide mass removal and treatment of contaminated groundwater. However, the soil contamination source areas have been contained but not directly treated date/. Therefore, to fully understand the conceptual design process, the source areas will be discussed here. The source areas, in general, are those areas that contain "buried waste," defined in the Statement of Work (SOW) section of the ROD as those areas of contamination with VOC concentrations greater than 10,000 mg/kg or PCBs concentrations greater than 10 mg/kg. In addition to the primary source areas, areas of "contaminated soil," defined in the SOW as concentrations in excess of clean-up goals but less than those defined as buried waste, exist near each of the source areas.

It is important to note that the SOW anticipated a remedial action involving LTTT and a residential end-use for determining the risks at the Site. However, based on results from the Materials Handling/LTTT study and the revised Baseline Risk Assessment (not yet approved by U.S. EPA), the remedial action is not expected to include LTTT. The risk calculations will be based on industrial end-use for the Site as stated by the Agency. Therefore, the clean-up goals will likely be modified from those listed in the current SOW.

To gain a better understanding of the primary source areas addressed by the conceptual design, each of the areas of concern are discussed below.

1.3.1 Source Areas

The primary identified source areas at the Site, presented on Figure 2, are:

1. The On-site Containment Area. According to the ROD, approximately 400 drums of unknown sludges and semi-solids were suspected to be buried in the On-site Containment Area. Subsequent geophysical surveys indicate that the On-Site Containment Area may contain between 1000 and 2500 drums.
2. The Still Bottoms Pond Area. This area includes the former Still Bottoms Pond, treatment lagoon #1, and adjacent contaminated areas of the ACS facility. The Still Bottoms Pond Area received still bottoms waste from the solvent recovery process. The pond and lagoon were drained and filled with crushed drums containing sludge materials, along with miscellaneous rubble and debris. A cross section, illustrating the contaminant concentrations by depth in the Still bottoms Pond, is shown on Figure 3.
3. Off-site Containment Area and Kapica-Pazmey Area. The ROD reported that the Off-Site Containment Area received wastes that included 20,000 to 30,000 punctured, crushed drums, general refuse, on-site incinerator ash, and a tank truck containing solidified waste paint for disposal. The Materials Handling/LTTT Study, October 1997, indicates that up to 50,000 drums, predominantly crushed and non-intact, could be buried within the Off-Site Containment Area. The area surrounding the Off-Site Containment Area, to the west and south is contiguous with the City of Griffith Landfill and contains landfilled wastes. A cross section through the Off-Site Containment Area, is shown on Figure 4. The Kapica-Pazmey property has impacted soil from direct disposal as a result of a drum washing area.

Contaminated groundwater has migrated off-site in the shallow aquifer. The areas of groundwater impact outside the barrier wall include an area to the north referred to as the North Area and an area to the south/southeast referred to as the South Area. Further discussion of these areas is presented in Section 7.

1.4 CHEMICALS OF CONCERN

The chemicals of concern which impact the groundwater at the Site are volatile organic compounds (VOCs) including chlorinated hydrocarbons and benzene, and some semi-volatile organic compounds (SVOCs). The interim expedited remedial measures implemented in 1996 and 1997 have contained much of the groundwater plume, and have isolated the sources of groundwater contamination from further migration. Chemicals of concern that are present in the soils and waste at the Site are primarily VOCs and PCBs, and these will be addressed in the conceptual design described herein.

1.4.1 Volatile Organic Compounds

To determine the areal and vertical extent of total VOC contamination, analytical results from soil samples collected during the RI and subsequent investigations were used to plot the areas shown on Figure 2. Boundaries of the VOC contamination were defined by evaluation of the sample concentrations and the sample locations. A concentration of 10,000 ppm was used to define the outer boundaries of buried waste, as defined in the ROD. Iso-concentration lines were also defined at 1,000 ppm and 100 ppm (shown on Figures 3 and 4). The majority of the VOC contamination lies within the On-Site Containment Area (associated with the drum burial), the Still Bottoms Pond Area (as a result of the solvent recovery waste disposal), and the Off-Site Containment Area (associated with the punctured drum and waste disposal).

Once the areal and vertical extents of contamination were established, the total VOC mass in each source area was estimated for use in the ISVE models and to determine at which depth a majority of the mass is located. The mass was calculated from the average VOC concentration of the soil samples within the boundary of a given area. Where concentrations were reported as ND (not detected), the concentration of the contaminant was set equal to the detection limit, to produce conservative results. The actual mass however, is unknown because the calculation is based on soil boring data. Review of the boring data shows that the soil sample concentrations vary in that there are samples of high concentration next to samples of lower concentrations. This variability indicates that there are localized areas of VOCs within areas of relatively unimpacted soil; typical of areas with buried drums, sludges and debris. Because of the variability, an accurate estimate of mass is not possible.

Details of the calculation are provided in Appendix A.

1.4.2 Polychlorinated Biphenyls

The source areas for PCBs are generally limited to the Still Bottoms Pond Area, the Off-Site Containment Area, and the Kapica-Pazmey Area (Figure 1). The areal and vertical extents of PCBs were determined based on the RI soil sample analytical data. The PCBs present in the Still-Bottoms Pond Area are at or near the surface and based on the revised Risk Assessment, pose an unacceptable risk to the future workers at the Site. There were also some detections of PCBs south of the Still Bottoms Pond Area, but these detections were generally at depths of between 15 and 20 feet. These PCBs do not pose an unacceptable risk because of their burial depth. As mentioned in Section 1.2, PCBs were also detected in the sediments in the wetlands west of the Site, probably due to the off-site transport of PCB-laden sediment via storm water runoff from the Site.

PCBs were also detected in the Off-Site Area, although the detections of PCBs in this area were more random than in the Still-Bottoms Pond Area, as might be expected in a landfilled area. Because of the nature of waste placement in this area, the PCB contamination is likely not contiguous throughout the area.

1.4.3 Inorganics

The primary areas of inorganic contamination on Site contain lead concentrations in excess of 500 ppm and are located in the Still Bottoms Pond Area, the Off-Site Containment Area, and the Kapica-Pazmey area. Detected lead concentrations in the Still Bottoms Pond Area were detected in excess of 500 ppm in two test pits and one soil boring. This area lies within the PCB-contaminated area, and will be covered. Concentrations of lead in excess of 500 ppm were detected between 3 and 10 feet in the Kapica-Pazmey area and between 10 and 15 feet in the Off-Site Containment Area, both of which will be covered. A single test pit excavated in the On-Site Containment Area contained lead in excess of 500 ppm.

1.5 RISK ASSESSMENT

The findings of the risk assessment, once approved by U.S. EPA, will be summarized here.

2.0 CONCEPTUAL REMEDIAL WORK PLAN

According to the ROD, under current-use scenarios, the primary risk of exposure from the site contamination would be through:

1. Incidental ingestion, inhalation of vapors and dermal contact with contaminated groundwater
2. Inhalation of vapors from subsurface releases and fugitive dust from surface contaminants
3. Ingestion and dermal contact of contaminated soil, and
4. Ingestion and dermal contact with contaminated media in the wetlands, surface water and sediment in the site's drainage ditches.

For future-use scenarios, risk from exposure could occur from ingestion, dermal contact and inhalation from the contamination in the groundwater, soil, vapor emissions, and surface water.

The risk scenarios are based on a residential property use at a 10^{-6} Target Cancer Risk and a Hazard Quotient less than 1. Remediation levels were established based on these risks and presented in the SOW. Based on the revised Baseline Risk Assessment, the residential use scenario for the Site is not appropriate, because of the industrial zoning on the property and the landfilled nature of the Off-Site Area. Treatment of the contamination at the Site to address a residential risk level would not provide benefits to the community, given that a removal action would have a much greater short-term risk without the long term benefit of significant additional risk reduction. (See Exhibit 1 Report on Short-term risk attached hereto). Therefore the original ROD remediation levels and the remedy itself need to be modified to reflect the industrial use scenario.

2.1 ROD REMEDY

The following major remedial action components were established in the original ROD:

1. Groundwater pumping and treatment to "dewater the site" and contain the groundwater plume;
2. Excavation and off-site incineration of the 400 drums in the On-Site Containment Area;
3. Excavation of buried waste for LTTT;

4. In-situ soil vapor extraction (ISVE) pilot study of buried wastes in the On-site Area;
5. ISVE of contaminated soils;
6. Continued evaluation and monitoring of wetlands, and if necessary, remediation;
7. Long term groundwater monitoring;
8. Fencing the Site;
9. Implementation of deed and access restrictions and deed notices; and
10. Private well sampling with possible wells closures or groundwater uses advisories.

Several of these actions have already been completed or implemented at the site:

1. Groundwater pump and treat system
6. Evaluation and monitoring of the wetlands
7. Groundwater monitoring program
8. Fencing the Site
9. Implementing deed and access restrictions and deed notices, and
10. Private well sampling program

In addition, a containment barrier wall was constructed around the Site source areas. The barrier wall contains the Site source areas and the contaminated groundwater beneath the site. One foot of clay cover has also been placed on the Off-Site Area. Other actions will be implemented as part of the proposed conceptual remedy:

2. On-Site Containment Area drum removal and off-site disposal
6. Excavation of PCB contaminated sediments in the wetlands for on-site consolidation
- 4., 5. In-situ soil vapor extraction

The alternate remedy is required because of the results of the 1997 Material Handling/LTTT Treatability Study, which was conducted to evaluate the technology as a remedy. The results of the study showed that even though LTTT can be effective at treating organic compounds, implementing the technology at the ACS Site would be impractical based on the following findings:

- A severe explosion hazard would exist from the excavation, handling and treatment of VOC-contaminated material. This is especially the case in the treatment system off-gas unit, where high concentrations of organic vapors could build, due to heating the soil to be treated.
- Approximately half of the contaminated material in the Off-site Containment Area contained municipal waste that was covered or commingled with soil. The amount of municipal waste was estimated to be 30 to 60 percent by weight. Since municipal waste is not amenable to LTTT, it would have to be managed separately, cleaned of the chemicals of concern, and disposed off-site. Steam cleaning, as required by the ROD, is not practical on municipal waste. Therefore, other management options for the waste would have to be investigated.
- Approximately 65 percent of the VOCs were lost as fugitive emissions during sample preparation for the treatability study, which implies that VOCs similarly will be lost as fugitive emissions during full-scale handling and blending operations. This situation would be inconsistent with controlling vapor emissions during excavation and would require an extensive engineered system in an attempt to minimize the short-term risk to the Site workers.

The LTTT study concluded that it would be necessary to develop an alternate remedy to manage the organics.. Many separate treatment technologies were evaluated in the 1992 Feasibility Study (3). Table 1 presents a screening matrix for the technologies evaluated, and shows that various technologies were screened out based on effectiveness, implementability, cost, or other criteria. As indicated in Table 1, there are a number of technologies that remain following the screening process, and the alternate remedy incorporates all of them.

Because of the Industrial/Commercial nature of the Site property, a final remedy that consists of removing principal threat by source reduction, process waste treatment and containment should be acceptable under the NCP. Therefore, the following alternate remedy has been developed for the Site.

Table 1: Technologies Evaluated During Feasibility Study

Technology	Media	Reasons for Screening Out Technology					
		Not Protective	Regulations Prohibit	Not Reducing TMV	Questionable Effectiveness	Cost Prohibitive	Difficult to Implement
Ex-Situ Bio Treatment	G						
Chem. Precip.	G						
UV/OX	G						
Air Stripping	G						
Ex-Situ Steam Stripping	G					X	X
GAC Adsorption	G						
Ion Exchange	G					X	
POTW Treatment	G		X				
In-Situ Steam Stripping	G BW SS						X X X
In-Situ Bio Treatment	G BW SS				X X		X X
Ex-Situ Bioreactor / Landfarming	BW SS	X			X	X X	X X
Off-Site Incineration	BW SS	X				X	X
On-Site Incineration	BW SS		X X				
Off-Site LTTT	BW SS	X				X X	X X
On-Site LTTT	BW SS					X X	X X
In-Situ Vitrification	BW SS	X			X X	X X	X X
Ex-Situ SVE	BW SS	X X				X X	X X
In-Situ SVE	BW SS						
Ex-Situ Solvent Extraction	SS				X	X	X
In-Situ Fixation	SS				X		
In-Situ Radio Frequency	SS				X		X

G = Groundwater

BW = Buried Waste

SS = Soil and Sediment

2.2 ALTERNATE REMEDY

The remedial action objectives established in the ROD for the Site are:

1. Minimize exposure to contaminated soil, groundwater, buried drums/liquid wastes/sludges or other substances which would result in a risk greater than the acceptable risk range identified in the ROD;
2. Restore groundwater to applicable state and federal requirements;
3. Reduce migration of contaminants off-site through water, soil or other media, and
4. Reduce the potential for erosion and possible migration of contaminants via site surface water and sediments.

To achieve these objectives, under the Alternate Remedy, the items listed in the ROD remedy would be implemented, except for LTTT of the contaminated wastes and soils. The risks posed by the contaminants at the Site will be addressed as follows:

1. Incidental ingestion, inhalation of vapors and dermal contact with contaminated groundwater will be prevented through containing the groundwater with the existing barrier wall, covering the Site, containment of groundwater plume, and groundwater pumping and treatment to remove contaminants.
2. Inhalation of vapors from subsurface releases and fugitive dust from surface contaminants will be prevented by covering the source areas and treating subsurface contaminants with ISVE.
3. Ingestion and dermal contact with contaminated soil will be prevented by covering the Site source areas.
4. Ingestion and dermal contact with contaminated media in the wetlands, surface water and sediment in the site's drainage ditches will be prevented by covering the source areas and excavating the contaminated sediments in the wetlands.

The Alternate Remedy has the following elements: 1) source (mass) reduction, 2) treatment of process wastes, and 3) containment of wastes. These elements will serve to eliminate contaminant migration from source areas and reduce potential human exposure to acceptable levels. The proposed Alternate Remedy consists of:

- ISVE in the Still Bottoms Pond Area (*source reduction and prevention of vapor migration*),
- ISVE in the areas of VOC impact in the Off-Site Containment Area (*source reduction and prevention of vapor migration*),

- Treatment of extracted vapor (*vapor control*),

Installation of an engineered cover over the areas containing buried waste (*containment and prevention of direct contact with impacted soil and vapors*).

In addition, the expedited remedial actions that currently contain the source areas and groundwater, including the PGCS, BWES, and barrier wall, will continue to operate as part of the proposed alternate conceptual remedy. The following items will be conducted or continued in accordance with the ROD:

- Excavation and consolidation inside the barrier wall of the PCB contaminated sediments from the wetland area,
- Removal and off-site disposal of the intact drums in On-site Containment Area,
- Continued groundwater pumping from the PGCS and BWES and treatment through the groundwater treatment plant in accordance with the performance standard verification plan (PSVP) for the groundwater treatment system,
- Long term groundwater monitoring, in accordance with the Agency-approved groundwater monitoring program, and
- Private well sampling, in accordance with the Agency-approved groundwater monitoring program.

The proposed Remedial Components are shown on Figure 1. The remainder of this document presents descriptions of the individual components for the proposed alternate conceptual remedy.

3.0 IN-SITU SOIL VAPOR EXTRACTION

In-situ soil vapor extraction (ISVE) technology is a physical mechanism designed to remove VOC compounds from contaminated subsurface media. ISVE is operated by applying a vacuum-induced air flow through the subsurface, to remove the vapors in the pore space. The initial mass removal is through advective flow regime, in which the vapors present in the pore space of the soil are removed. Once the initial soil vapors are removed, ISVE is limited by the rate at which VOCs, absorbed on the soil particles, trapped in the pore space as liquid, and dissolved in the pore water, partition (volatilize and diffuse) into the pore space. This is referred to as diffusive flow regime.

Because the barrier wall already contains the source areas at the Site, the main objective of ISVE at the ACS Site is mass reduction in these source areas by extracting mobile VOC contaminants from below the ground surface. The source's mass reduction will be from preferential air and water flow pathways, where contaminants, if their physical and chemical characteristics are such that they are mobile, will migrate. Certain compounds such as VOCs have characteristics that make them mobile. Other compounds, such as semi-VOCs, have characteristics that typically make them less mobile or immobile. Mobile-characteristic contaminants, which are not within these preferential flow pathways, will not likely migrate because they are trapped within the soil/debris/drum matrix. If they do migrate, they will migrate to preferential pathway and will be removed through the ISVE (if in vapor form or product form) or groundwater extraction system (if dissolved in water or in product form). Either way, the mobile contaminants are still within the containment area. Immobile contaminants in the containment area are not a priority because they will not mobilize from the source areas through the preferential flow pathways and are therefore contained.

Applying ISVE to the source areas will decrease the mobile mass of contaminants so that they cannot migrate to groundwater within the barrier wall. This reduction, in conjunction with the barrier wall and groundwater pump and treat system, will further reduce the potential for off-site migration. In addition, ISVE will reduce the opportunity for vapor contact through the ground surface by reducing the vapors in the subsurface and minimize the VOC loading in the treatment plant by removing VOCs before they dissolve into the groundwater. This remedial component is consistent with the objectives of the final remedy for the ACS Site, as defined in the ROD, to address principle threat by reducing the risk of exposure to contaminated vapors and reducing the potential migration of mobile contaminants to the groundwater.

3.1 AREAS TO BE TREATED WITH ISVE

As discussed in Section 1.3, the areas containing high VOC concentrations are found in four primary areas:

- On-site Containment Area
- Still Bottoms Pond Area
- Off-site Containment Area
- Kapica-Pazmey Area

In the On-Site Containment Area, the elevated levels of VOCs are coincident with the buried drums. These drums, based on test pitting during the RI and observation during the recent construction in this area, are generally intact and are stacked on their sides, three high. Although the number of drums is likely higher than the ROD estimate, drums within the defined On-Site Containment Area can be removed in accordance with the ROD. The intact drums will be sent off-site for incineration or disposal, depending on the contents, in accordance with all local, state, and federal regulations. Section 6 discusses the drum removal in greater detail.

For the other three areas of elevated VOC contamination, the percentage of total VOC mass present was determined (see Section 1.3 and Appendix A). The percentages of total VOC mass by area are as follows:

Area	Distribution of Estimated VOC Mass within Containment Area	Percentage of Area Soil Mass that is Impacted with VOCs
Still Bottoms Pond	65%	1.6%
Off-Site Containment	32%	1.1%
Kapica-Pazmey	3%	0.3%

As shown in the above table, the mass of VOC-contaminated soils within the Kapica-Pazmey Area before the barrier wall was installed represented only 3% of the total VOC contaminant mass within the soil. Because a portion of this VOC-impacted area was along the barrier wall alignment, some of the mass was removed during installation of the barrier wall. Therefore the mass in the Kapica-Pazmey area now represents less than 3% of the total VOC mass within the barrier wall and only 0.3% of the Kapica-Pazmey soil mass is impacted. ISVE will not be implemented as part of the conceptual remedy for the Kapica-Pazmey Area.

No.

3.2 ISVE MODELING

Following determination of the contaminant mass present in each area, the Still Bottoms Pond Area and the Off-Site Containment Areas were modeled for application of ISVE. The purpose of the ISVE modeling was: 1) to determine if ISVE was a feasible remedy, and 2) to develop preliminary design criteria. Two screening models, which are recommended by the EPA, were used.

The screening models are Hyperventilate® and BioSVE®. Both models use simple mass transfer and partitioning equations such as the ideal gas law. These models estimate mass removal under "ideal" conditions, which predict fairly accurate mass removal at initial startup of the ISVE system, during advective flow. The mass removal during diffusive flow is not predictable from the models, as the mass removals will decrease over time. However, understanding this, the models are a useful tool to estimate the feasibility of ISVE for application at a site. The models also provide preliminary estimates of mass removal, desired removal rates, achievable flowrates, and other preliminary design parameters.

The two models were used to answer two different questions regarding the conceptual design of the ISVE system. Hyperventilate answers questions related to the ISVE system design. For instance, What radius of influence (ROI) can be expected? How many wells does the system require? What flow rate is needed per well? What are the initial vapor concentrations? BioSVE then answers the question: How much removal can be expected with the system?

The initial model used, Hyperventilate®, was used to estimate feasible flow rates, initial vapor concentrations, and desired and feasible mass removal rates. Then, once these variables were estimated, the output from Hyperventilate® was used in the second model, BioSVE®, to estimate a rate of removal over the operational life of the ISVE system, based on individual contaminants that make up the estimated mass of VOCs. The input parameters and output of the models and a discussion of how the parameters are defined are provided in Appendix B. A summary of the input and output parameters is presented on Table 1 in Appendix B. The conceptual design of the ISVE system for the ACS NPL Site was developed from the results of the modeling effort.

The model outputs typically represent ideal and initial conditions such as those that will likely be observed within the first few weeks of start-up. The model output values represent maximum design criteria under ideal conditions therefore, the models were used to only address the feasibility of ISVE as part of the alternate remedy. Under actual operating conditions, especially during steady state removal or the diffusive flow regime, concentrations and flowrates are expected to be significantly reduced. For example, the mass removal rates are expected to decrease within the first several months as the accumulated vapor that is accessible to the vacuum is extracted. Often, ISVE systems are designed based on the model's ideal and start-up conditions, which leads to an over-designed system that allows for no flexibility as vapor concentrations decline. Also, in

many cases once the vapor has declined, the operation is assumed to be completed. The system for this site has been designed to address the decline in vapor rates to prevent an oversized, inflexible system and a logical approach to develop shut-off criteria to address rebound effects is discussed further in Section 3.7 Phased Start-up.

3.3 PRELIMINARY DESIGN CONSIDERATIONS

Preliminary design of the ISVE system included consideration of the challenges previously identified in meetings and conversations with U.S. EPA and IDEM personnel. These challenges included uncertainties regarding effectiveness of ISVE around buried debris and garbage in heterogeneous landfills, free product recovery, and "short circuiting" of air flow. Specific design features related to each of these issues are summarized in the following paragraphs.

3.3.1 ISVE Effectiveness Around Buried Debris and Waste

The subsurface at the Site includes buried debris, municipal waste, and other objects that introduce pockets of air into the subsurface due to imperfect packing of soil. These pockets would represent channels for preferential flow in the subsurface and could potentially dominate the vapor flow pattern induced by the applied vacuum in the ISVE system. For this reason, the ISVE system has not been designed to induce uniform vapor flow through the subsurface, but rather to prioritize recovery of the contaminants in certain areas depending on the potential for those contaminant areas to impact groundwater and soil within the barrier wall in the future. This natural prioritization of contaminant recovery (or preferential recovery) will first remove the contaminants that have the greatest potential for future migration.

Preferential recovery occurs because contaminants are recovered first from the zones of highest vapor flow during ISVE, which is also expected to be the zone of highest contaminant distribution. The concentration of contaminants is likely greatest in the voids caused by heterogeneities, such as collapsed drums and garbage, because these zones offer the least resistance to gravity-driven migration. These are the same zones in which preferential flow will occur during ISVE. Therefore, preferential flow in these zones during ISVE will actually optimize initial recovery of contaminants and will provide early removal of contaminants from these pockets of highest concentration. The ISVE system will include valves on individual wells, allowing each well to be used either as a vacuum extraction point or as a passive air vent to influence the pathways as necessary.

3.3.2 Free Phase Product

Free phase product is a priority for removal from the Site because free phase product has the highest potential to impact soil or groundwater in the future. Although small amounts of free phase product have been observed at the Site during previous investigations, there do not appear to be large volumes of free phase product at the Site. A sheen has been detected in selected wells, but measurable thicknesses of free product have not been detected in any well. The presence of a sheen in selected wells suggests that free product, where present, exists only at low volumes that are immobilized in soil above the water

table. Highly concentrated areas of free phase product do not appear to be present because such areas would likely cause significant downward migration of free product that would be detectable as measurable thicknesses in groundwater monitoring wells.

Since free product only exists at low volumes where it is found on Site, ISVE is an appropriate technology to maximize recovery. ISVE provides recovery of volatilized constituents via a vacuum-induced vapor flow through the vadose zone between the ground surface and water table and through the dewatered zone. ISVE uses the same above ground equipment and recovery mechanisms as bioslurping, which is often mentioned specifically as a free product recovery technology. As ISVE is operated, vapor will preferentially flow through the zones with the greatest proportion of void spaces, which may be caused by debris or garbage. These zones of preferential flow are likely to also be the greatest areas of accumulation of free product since free product will similarly migrate according to lines of least resistance. Therefore, the volatile compounds at the Site are expected to volatilize relatively quickly into the flowing vapor stream and recovery of free product will be natooptimized.

3.3.3 Smearing

If free phase product is present in the soils floating atop the water table, the potential exists for "smearing" this product across the soil matrix. Smearing occurs when a pool of free phase product is mobilized through the soil and leaves residual product in its path. This "smear zone" will greatly increase the surface area of free phase product, that will be contacted by vapor recovered via the ISVE system. During vapor extraction, free phase product is recovered by direct diffusion into the vapor. Since diffusion is proportional to the surface area of contact between vapor and the contaminants, increasing the surface area will directly increase the rate of recovery of the contaminants. Therefore, by "smearing" this product, if present, across the soil matrix (thereby increasing the surface area of the contaminants), the effectiveness of the ISVE system on these contaminants will be increased.

3.3.4 Short Circuiting

Short circuiting occurs when a source of atmospheric air is introduced to the subsurface in which the ISVE system is operating and causes this air to be preferentially extracted instead of the contaminated soil vapors. Short circuiting is a concern at any site for which ISVE is considered because short circuiting can causes preferential flow of uncontaminated air through the system, and thereby reducing the achievable radius of influence. The most common cause of short circuiting is direct flow of air from above ground into the extraction well because the ground surface is not sealed. This potential for short circuiting will be minimized at the site because the entire ground surface over the ISVE system will be sealed with an engineered cover at a minimum. The ISVE system, moreover, is designed to address a small amount of short circuiting given that individual wells can be adjusted to reduce or increase flow and vacuum or opened to introduce air into the system at preferential points, thereby redirecting the preferential flow paths that the atmospheric air follows.

3.4 DESIGN

The conceptual ISVE design takes into account the concerns with ISVE in waste, short circuiting and free product, as well as the results of the modeling and other institutional knowledge about the Site and ISVE. The major components of the ISVE system consist of:

- Extraction wells and piping
- Vacuum blower system
- Condensate removal system
- Extracted vapor treatment system

3.4.1 Extraction Wells and Piping

The extraction wells will be installed so that the screened portion of the well is within the source area. The screens will be deep enough to avoid short circuiting of atmospheric air through the ground surface. The well diameters will be four inches, which is typical of ISVE systems. Smaller diameter wells might lead to higher vacuums and subsequent mounding of groundwater and larger wells typically do not significantly increase treatment efficiency.

The ROI for the individual ISVE wells has been estimated to be 30 feet, based on hydraulic conductivity of undisturbed soil from data obtained during the RI. The 60-foot spacing is a conservative estimate that coincides with ISVE systems in similar geologic settings. Conservative spacing may be greater, especially given the void space through debris and the results of modeling described previously. For example, the actual ROI may be greater in the Off-Site Containment Area where varying amounts of debris are present in the subsurface. Montgomery Watson calculated that 46 extraction wells are needed in the Still Bottoms Area and 30 wells are needed in the Off-site Containment Area based on the areal extent of impacted soil. To provide adequate coverage, the wells will be placed so that there is overlap of the ROI. Within the Still Bottoms Area, the ISVE well locations may need to be field-adjusted to avoid site structures and avoid interfering with the ACS facility operations. Conceptual layouts of the Off-Site Containment Area and Still Bottoms Pond Area ISVE well fields are presented on Figures 5 and 6, respectively.

The well heads will be below grade in shallow utility vaults, but accessible for vacuum and water level measurements and vapor sample collection, if needed. Each well head will consist of a removable cover, throttling valve, sample and monitoring port, and lateral conveyance line. Ports will be installed on the lateral line to measure vacuum and collect vapor samples. A typical well design is shown on Figure 7.

The conveyance piping plan will involve laying pipe on the existing grade or slightly below grade, to minimize trenching and the handling of contaminated materials necessitated by trenching. The initial and permanent covers will be placed over the pipes to protect from traffic and weather damage. Because the cover thickness will be less than 4 feet, the pipes will be insulated at low points, where condensate may accumulate to provide additional freeze protection. The conveyance piping of the ACS ISVE System will be designed so that series of wells in the well field are joined to a common header. Wells located within

specific areas will be connected as a section to a header with lateral lines. The header pipes will be connected to one common header at the blower. The header sections will have valves at the common header pipe to perform fine vacuum and flow adjustment. Each individual well will have a valve at the well head for coarse vacuum and flow adjustment and to allow air venting during system operation. The piping configuration is presented in Figure 6.

The Off-Site Containment Area will have five well sections in the well field. The well sections will correspond to specific areas within the Off-site Containment Area, but because of the topography of the site, the header placement for each well section will be located through the center of the area to minimize the need for trenching. The Off-Site Containment Area is mounded, with the highest elevation near the center of the impacted area. The headers are designed to slope outward towards the edge of the impacted area (and toe of the cover) to reduce condensate accumulation in the headers.

3.4.2 Vacuum Blower System

The ISVE blower system will be housed in a small building on or near the well field. The system blowers will be sized based on the estimated flowrate and vacuum requirements. It is anticipated a centrifugal blower will be used. Process controls will be minimal. There will be safety controls to shut-off the blower if it overheats or becomes flooded with water. Included with the major equipment components will be flow meters, blower silencer, vacuum and pressure gauges and valves. The basic equipment components are presented in Figure 8, Conceptual Process Flow.

3.4.3 Condensate Removal System

Initially, condensate will be generated in the ISVE system because the soil vapor will likely be saturated or nearly saturated with groundwater vapor. As the Site is dewatered and the subsurface moisture is removed, the water saturation of the vapor will drop, however, some condensate will still be generated. The condensate will be minimized through operation of the system and to minimize accumulation. Operating the system at low vacuums will minimize the condensate, which can be reduced further, either in the field or collected and removed at the blower inlet. Condensate can be removed in the field by sloping the conveyance piping toward the wells, installing filter fabric in the wells, driplegs in the well field or a combination of these or other components.

At the blower, the system will include a "knockout" tank with a demister. Condensate removed from the system will be treated in the groundwater treatment system. A condensate transfer pump will pump the condensate to a storage tank or the groundwater influent equalization tank in the Groundwater Treatment Plant. An alarm level will shut the ISVE system down to prevent water from flooding the blower.

} ?
why?
will
contain
VOCs.

3.5 EXTRACTED VAPOR TREATMENT SYSTEM

It is anticipated that, initially, the vapors extracted from the system will require treatment prior to being released to the atmosphere. Initial vapor mass flowrates from the wells during start-up are estimated to be greater than the allowable air emission of VOCs. The initial vapor will likely be treated with either a thermal or catalytic oxidizer. Because of the chlorinated compounds in the inlet vapor stream, a scrubber will be required to remove hydrochloric acid that is generated during oxidation of chlorinated compounds.

all
the
time

Typically, this initial vapor treatment is required until vapor removal rates decrease after the initial pore vapor has been removed. At that point, the vapor concentrations in the ISVE system will be lower than concentrations at start-up and will be limited by the contaminant diffusion rates. For the ACS Site's ISVE system, the mass removal rates at start-up estimated for a single well will likely exceed the treatment capacity of the oxidizer, therefore it is anticipated that only a few wells in each area will be operated at start-up until the rates decline. Vapor treatment with regard to start-up and initial extracted vapor treatment are discussed further in Section 3.7 Phased Start-up.

A less aggressive vapor treatment system will be used after the vapor concentration decreases below a point at which it is no longer cost effective to treat the extracted vapors with an oxidizer. Depending on the vapor composition, vapor phase carbon may be a viable option. A condenser or chiller/dryer may be considered in conjunction with the carbon, to reduce the carbon usage. At some point, when the vapor concentration and mass discharge drops below the regulatory requirement, direct discharge may be possible. Criteria for these modifications will be detailed in the Final Design. An air permit or notification will be required because of the initial concentrations. The permit will specify the applicable regulatory requirements.

No.

3.6 COMPLIANCE AND PERFORMANCE MONITORING

Compliance monitoring will consist of monitoring to comply with air emission regulations.

Performance monitoring will be conducted to evaluate and optimize the ISVE system. Performance monitoring will consist of sampling and analyzing the inlet and outlet vapor of the extracted vapor treatment system and the incoming combined vapor from the well field, and measuring vacuums, flowrates, and temperatures. Mass removal rates will be calculated and evaluated to assess the system performance and mass reduction over time. Vapors from the wells or well sections will be sampled and analyzed and water levels will be measured periodically.

3.7 PHASED START-UP

ISVE will be implemented first at the Off-Site Containment Area because the vadose zone is sufficiently thick at this location to allow effective operation before dewatering is completed. Therefore, ISVE can be implemented in this area before the water elevation is dropped to the target long-term level by the dewatering effort. After the water elevation in Off-Site Containment Area is dropped to the target level, the dewatering effort for the Still Bottoms Pond Area will be implemented. An ISVE system will not be installed at the Still-Bottoms Pond Area until dewatering has sufficiently lowered the water level, because the shallow depth of groundwater in this area would limit the system effectiveness.

Start-up of the ISVE systems at both the Off-Site Containment Area and Still-Bottoms Pond Area will be conducted in phases because of the uncertainties regarding subsurface conditions and nature of the ISVE mass transfer process. All the wells and piping will be installed as shown on the design drawings and the phases will be conducted using the full-scale well field. The overall concept of the phased start-up is to initially start operation with a subset of extraction wells, observe performance over an initial period, and use the initial results to adjust the design of the full-scale mechanical and vapor treatment system. This will allow flexibility to adjust system operation and design of subsequent phases to optimize overall operation when operating conditions reach steady state or the diffusive regime. It will also provide a better understanding of local conditions around each well. Specific features that will be provided by the phased implementation schedule include the following:

- Effective initial operation for uncertain site conditions.
- Capability to change operating configurations to deal with differences in localized conditions.
- Flexibility to modify system operation as conditions change over time (i.e., from advective to diffusive removal).
- Avoidance of treatment capacity exceedances.
- Optimization of energy efficiency by avoiding oversizing the system based on initial conditions and minimize pollution due to unnecessary burning of supplemental fuel.) right

The phased start-up will be conducted in lieu of a small-scale pilot study. Information obtained from this start-up sequencing will be more comprehensive than a small-scale pilot test, because it will be utilizing the full-scale well configuration, will have a longer duration, and will cover a wider area. It will also be more cost-effective because the equipment sizing will be based on long-term operation during diffusive extraction, instead of short-term start-operation.

It is anticipated that the start-up will be operated in three phases:

- 1) day one to month six "pilot phase"
- 2) month 6 to month 12, "design and installation phase"
- 3) month 12 to month 18 "optimization phase."

After start-up, long-term operation and maintenance will begin.


The first phase of ISVE in the Off-Site Containment Area will involve applying a vacuum to approximately eight wells, at the locations shown on Figure 7. These wells have been selected to provide a distribution throughout the designated areal extent of contamination. Initially, the applied vacuum will be provided by a blower capable of providing up to 500 scfm flow at a maximum vacuum of 60 inches H₂O. It is expected that the actual applied vacuum will be significantly less, to limit preferential flow as much as possible. A 500 cfm thermal oxidizer with heat exchanger will be initially used to provide extracted vapor treatment with a maximum destruction capacity of 1,700 pounds per day. This 500 cfm system is referred to as a "pilot system".

Because of the initial high vapor concentrations, it is likely that early operation will be limited by the destruction capacity of the thermal oxidizer. It is estimated that the initial achievable removal rate from each may be as high as 1,000 to 2,970 pounds per day. Therefore, all eight wells may not be operated simultaneously during pilot phase operation. The wells will be alternated initially to evaluate differences in characteristics from each well.

Once the characteristics are determined, wells with low and high VOC vapor concentrations can be operated simultaneously to prevent exceeding the treatment capacity of the thermal oxidizer, while maximizing its volumetric capacity. The number of wells operating at any one time will be gradually increased to maintain maximum destruction of hydrocarbons in the thermal oxidizer. The "pilot phase" of ISVE will be operated for up to six months.

VOC concentrations in the extracted soil vapor will decline over time because of the nature of the soil vapor extraction process and the mass transfer phenomenon. The decline may be approximated by one of the three characteristic patterns shown in the figure below.

CHARACTERISTIC PATTERNS OF VAPOR CONCENTRATION DECLINE



Concentrations may drop gradually in a nearly straight line as shown in Scenario 1, moderately as shown in Scenario 2, or exponentially and sharply as shown in Scenario 3. The design of the full-size system and phased integration of additional extraction wells will be dependent on the actual characteristic decline in concentrations that are observed during the pilot phase. The implementation schedule for the next two phases is explained for each of the different scenarios in the following paragraphs.

3.7.1 Scenario 1 – Gradual Decline

Under Scenario 1, concentrations will decline gradually and the trend of concentrations over the initial six months will approximate a straight line. This scenario represents a condition in which the extracted vapor is from a significant source such as a trapped pool of free phase product in void spaces. Typically, vapor concentrations for this scenario would remain relatively high and initial operation of the system would be limited by the destruction capacity of the thermal oxidizer. Depending on the vapor treatment capacity limit, it is possible that a subset of the eight extraction wells shown on Figure 7 would be utilized for the first six months. Following the pilot phase, a larger system will be designed, procured, and installed during the design and installation phase (month 6 through month 12). During this time, additional wells will continue to be brought on-line, if additional destruction capacity is available in the vapor treatment unit. The larger system will be started up at month 12 and used in conjunction with the initial 500 cfm system for the next 6 month phase (optimization phase). During this time, the overall system will continue to be optimized and the initial system will be modified to treat the measured flow.

3.7.2 Scenario 2 – Moderate Decline

Under Scenario 2, concentrations would decline moderately and after six months, might be as low as 50% of the initial values. In this scenario, accessible subsurface contamination

would be removed at a proportionally high rate, but the rate would reach an asymptotic limit. The decline in concentrations over six months is expected to be sufficient enough that all eight initial wells could be operated simultaneously by the end of the pilot phase (six months). While the full-size system is designed and installed during months 6 through 12, additional wells would be brought on-line, as needed, to maintain maximum destruction capacity in the thermal oxidizer. The final system would be started up at month 12 and used in conjunction with the initial 500 cfm system. As concentrations continue to decrease, the overall system would be optimized and the 500 cfm system would be modified to treat the increased flow.

3.7.3 Scenario 3 - Exponential Decline


Under Scenario 3, concentrations would decline exponentially so the concentration at the end of month six would be significantly lower than the first day of operation. This pattern would suggest that the accessible zones of high concentrations were relatively small and were quickly removed. An asymptotic level would be reached relatively quickly representing long-term removal of VOCs from the subsurface. If an asymptotic level is attained within the first six months, the design and installation of the full-size system would be expedited and completed by month 12. As the full-scale system is designed and installed, additional wells would be added, as appropriate, to maximize operation of the extraction and treatment system. It is possible that destruction of hydrocarbons for this scenario would be limited by the flow-through capacity (retention time) of the oxidizer and not the destruction capacity. In this case, the full-scale system could incorporate a catalyst that would be more cost-effective for lower concentrations. For this scenario, the full-scale system would be implemented as soon as it was ready for operation. It is anticipated that the system would be on-line and optimized before 18 months had elapsed from initial start-up.

Regardless of the characteristic decline scenario of VOC concentrations, the full-size system would be started up at the latest, by month 12 and would be optimized and fully operational by month 18. After month 18, the system would be operated according to a long-term operation and maintenance schedule that provides required servicing of equipment, change-outs, and periodic adjustments. The locations of the 30 proposed extraction wells and configuration of the full-size extraction system are shown on Figure 5. This system will provide complete coverage of the estimated extent of VOC concentrations greater than 100 mg/L. At the end of 18 months (maximum), extraction and treatment of soil vapor from the Off-Site Containment Area would be conducted using one system.

The ISVE system for the Still Bottoms Pond Area will be implemented in phases similar to the Off-Site Containment Area, after the first ISVE system is fully operational. The first phase will use up to 10 wells as shown in Figure 6. This pattern of extraction wells would provide information on achievable recovery rates from across the impacted area, as well as other design parameters. The initial system will be operated for up to six months, a full-size system will be designed from month 6 to 12, and the full-size system will be implemented and optimized from month 12 to 18. The full-size system is expected to require approximately 46 extraction wells, as shown on Figure 6, which will provide recovery of VOCs above concentrations of 100 mg/L. where - initial soil levels?

3.8 LONG-TERM OPERATION AND SHUTDOWN CRITERIA

The ISVE systems will be operated until the primary remedial objective is satisfied, which is removal of mobile volume of VOCs from the two source areas with the greatest potential to impact soil and groundwater in the future. The two systems will be operated in different modes to maximize efficiency of recovery for the two characteristic contaminant transport regimes. These transport regimes are advective recovery and diffusive recovery. A summary of the transport regimes and graph of characteristic concentrations during each regime is provided in the figure below.



Long-term operation and shutdown criteria have been developed based on the physical processes of contaminant recovery that are part of the operation of an ISVE system. The ultimate performance of the ISVE system is difficult to predict because of the uncertainty and variability of the subsurface conditions. Consequently, the numerical parameters for shutdown will be difficult to define. However, the dominant recovery mechanisms, advective transport (Stage 1) and diffusive transport (Stage 2), are understood and shutdown criteria are typically developed based on knowledge of these mechanisms. Shutdown criteria will be defined for the two stages of recovery.

3.8.1 Stage 1 – Advective Transport Regime

During this stage, the ISVE system will operate continuously and will be optimized to maintain the highest level of vapor concentrations possible. The constituents removed will include contaminants in the most permeable zones and contaminants that have the greatest potential to migrate from the source area due to their mobility. The advective recovery of contaminants will be characterized by high initial recovery rates, which will decline over time as the most mobile contaminants are recovered and contaminants accessible for advective flow are depleted. While advective transport is significant, the achievable recovery of contamination will be dependent on the total vapor flow rate that can be sustained. Thus, continuously operating the ISVE system to maximize efficiency is critical to optimizing contaminant recovery during advective flow.

During the first mode of recovery, the advective recovery regime, the ISVE systems will be continuously operated during advective recovery until the VOC concentrations reach an asymptotic level. The asymptotic level will be determined by periodically recording the VOC concentration in recovered vapor and identifying when the change in concentration over time has become negligible. Mathematically, the asymptotic level will be reached if the slope of concentration change versus time is nearly zero as defined by equation (1):

$$-5 \% < \text{slope} < 0 \quad (1)$$

The slope of concentration change over time will be obtained by plotting the trend of VOC concentration over time, curve-fitting the data, and identifying the slope of the curve midway between the two most recent data points. If the slope is determined to be asymptotic, the ISVE system will be temporarily turned off and cyclical operation will commence in accordance with the criteria for diffusive recovery.

Continuous operation (Stage 1) will be concluded once advective recovery of contamination becomes negligible. The ISVE system will be operated for a period of time to allow optimization of the equipment and full development of the vacuum field across the entire area of concern. After this period of operation, the magnitude of advective recovery will be determined by monitoring the recovery rate of contamination and identifying the time at which the recovery rate has reached an asymptotic level. The system would be shutdown after a relatively-steady rate of recovery is observed; at such time, the ISVE system would be operated in a cyclical mode (Stage 2), with the duration of the advective stage depending on the level of soil vapor concentrations and the quantity and mobility of contaminants.

3.8.2 Stage 2 – Diffusive Transport Regime

During this stage, vapor concentrations and mass removal are limited by diffusion rates. Diffusive transport will remain relatively constant as ISVE operation continues, because diffusive recovery of contaminants will involve the slow diffusion from less accessible areas. The rate of diffusion will be dependent on the concentration gradient between the permeable zones accessed by soil vapor extraction and pockets of contamination in less accessible areas. Therefore, the key to maintaining recovery during the diffusive stage will be to maintain sufficient operation of the ISVE system such that concentrations in the vapor flow remain relatively low, providing a concentration gradient between the less accessible areas and more permeable zones. The ISVE system will be operated cyclically during the diffusive stage. The cycle frequency will maintain a consistent concentration gradient while decreasing the total volume of vapor that requires treatment, optimize the efficiency of vapor treatment by maintaining the concentrations in vapor recovered during times of, and minimize short-circuiting that develops during continuous ISVE operation.

To optimize the mass reduction, the system will be operated in cycles by alternately operating well sections to allow vapor equilibrium in the soil gas to be achieved at the wells that are shut off. The timing of the ISVE system on/off cycles will be determined by monitoring the concentration in recovered vapor. The purpose of the cycles will be to start the system when vapor concentrations are several orders of magnitude higher than at the

time of the last shut-off period. The first off-cycle will last for three months, and then the system will be operated until asymptotic concentrations are attained in accordance with equation (1) again. Once asymptotic levels are attained, the system will again be turned off. The duration of each off-cycle will be the same as the previous off-cycle, unless the preceding period of operation was less than half the off cycle, in which case the off-cycle will be doubled. In summary, each on-cycle will last until asymptotic levels are attained and each off-cycle will last the same or double the previous off-cycle, depending on the length of the preceding on-cycle. The frequency of cycles will be systematically adjusted throughout operation to maximize the efficiency of mass removal.

No. Pulsing of the ISVE system will be stopped when operating cycles are less than 10 percent the duration of off cycles. Pulsing the system until short periods of operation are attained will provide recovery of significant contamination that has diffused from low permeability zones. Once these short periods of operations are reached, the ISVE system will no longer be technically or cost effective and shutdown will be appropriate. Therefore, this criteria dictates ultimate shutdown once the ISVE effectiveness has declined.

At the time of final shut-down, the groundwater will be allowed to recharge to the barrier wall maintenance level. The ISVE extraction wells will be opened and allowed to vent to atmosphere as a passive system.

SUDCs + DNAPL not addressed.

air injection necessary

4.0 DEWATERING

In accordance with the SOW in the ROD, one remedial component is to contain and treat the groundwater plume. The barrier wall contains the plume near the source areas and the existing groundwater pumping system removes impacted groundwater contained within the wall to treat that water and maintain the water levels within the barrier wall.

Lowering the water table will expose portions of the soil contamination that is currently below the water table. Once the zone of contamination is exposed, the ISVE system will withdraw contaminated vapors from the subsurface for treatment. Exposing the soil will increase the effectiveness of ISVE in both the Still Bottoms Pond Area and the Off-Site Containment Area by exposing the areas with the largest volumes of contaminants. Therefore, a critical component of the final remedy will be the dewatering program for the Site.

The water table in the Off-Site Containment Area, in the proposed ISVE system location, is currently approximately 8 to 10 feet below the ground surface (bgs). This vadose zone (area between the water table and the ground surface) thickness is sufficient to begin ISVE in this area. However, a majority of the contaminant mass in this area extends to a depth of 15 to 17 feet bgs. Therefore, to expose the largest areas of contaminant mass and to optimize the performance of the ISVE system, the water table in the Off-Site Containment Area will be drawn down to 15 to 17 feet bgs.

not low enough?
Because of the high water table in the Still Bottoms Pond Area (3-5' bgs), this area will require dewatering prior to implementation of ISVE. This area will be dewatered to a depth of approximately 8 to 10 feet bgs, exposing the areas with the largest mass of contaminants for extraction through the ISVE system.

The areas of contamination that will remain below the water table are relatively small compared to the areas that will be treated with ISVE. These areas are also contained within the barrier wall and if the contaminants in these areas dissolve in the groundwater, they will be removed by the groundwater extraction system and treated in the water treatment plant.

4.1 ALTERNATES EVALUATION

Preliminary evaluations were conducted in order to determine the most effective method of dewatering the Site, given the capacity limitations of the existing extraction trenches (the barrier wall extraction system - BWES) and the groundwater treatment system. Several different options were evaluated:

1. Use of the existing BWES trenches to dewater the Site.
2. Use of the existing BWES trenches to dewater and installation of a separation barrier between the Off-Site Containment Area and the ACS facility.

3. Use of the existing BWES trenches, installation of a separation barrier, and installation of a series of well points around the Still Bottoms Pond Area to locally dewater this area.
4. Use of the existing BWES trenches, installation of a separation barrier, installation of well points, and installation of sheet piling around the Still Bottoms Pond Area to locally dewater this area.

To evaluate these options, the storm water infiltration through various parts of the Site was calculated and converted to a flow rate into the dewatering system. The effective pumping rate out of the dewatering system was then calculated as the actual pumping rate minus the infiltration rate. Several different covering and cover scenarios were assumed during evaluation of infiltration rates through the ACS operating facility and the Off-Site Area. For each option, a design pumping rate and an elapsed time to dewater were calculated. Criteria for evaluating effectiveness include the pumping capacity of the trenches, the volume and treatment capacity limitations of the groundwater pump and treatment system and the time required to lower the water table in relation to implementation of the ISVE systems. The results of the evaluation indicated that Option 2 was the most cost effective. Details of the evaluation are included in Appendix C.

} need
to
increase
vol./
capacity

4.2 SELECTED ALTERNATIVE

Option 2, installation of a separation barrier and use of the existing trenches to dewater both Off-Site and On-Site Areas, was determined to be most cost effective, because the option prevents exceeding the capacity of the trenches and treatment system while minimizing the time required to implement remediation. Therefore, the Alternate Remedy includes installing a separation barrier wall just south of the existing railroad tracks, at the south edge of the ACS operating facility. Because the ISVE system will begin in the Off-Site Containment Area, this area will be dewatered first, allowing optimization of the ISVE system to extract vapors from the majority of the contaminated area. The existing trenches in the Off-Site Area will pump at 25 gpm (5 gpm from each trench) to dewater the Off-Site Area. Following installation of the separation barrier (slurry wall), the Off-Site Area will be surrounded by a barrier wall on the east, south and west sides, a clay layer below, a one-foot cover on top, and the separation barrier on the north. Therefore, the infiltration into this area is expected to be less than 5 gpm. Once the area is dewatered (which should take approximately 7 to 8 months), extraction from the trenches can be "throttled back" to produce a flow rate just equal to the infiltration rate. Matching the infiltration rate will keep the water table lowered to expose the majority of the VOC mass while the ISVE is in operation and to keep the water level below the barrier wall after the ISVE system is shut-down.

↓
which is?

Not
good
enough.

Following the water table lowering in the Off-Site Area, the Still Bottoms Pond Area water table will be lowered. Because the Off-Site Area will require only 5 gpm to maintain the lowered water table, the remaining pumping capacity will be used in the three BWES trenches in the ACS facility. Additional pumps will be installed in these three trenches, to boost their extraction capacity, and they will be operated at approximately 35 gpm (10-12 gpm per trench) to dewater the On-Site Area. Based on our evaluation, lowering the water table in this area should take approximately six to seven months. Prior to dropping the water table in the Still Bottoms Pond Area, the existing Fire Pond will be filled, the ACS Site will be regraded to more effectively drain storm water, and the Still Bottoms Pond Area will be covered to reduce infiltration. (See Figure 9).

As a contingency, if the trenches in the ACS facility are not able to dewater the Still Bottoms Pond Area effectively, well points would be installed near the Still Bottoms Pond Area to locally dewater this area. However, because the treatment capacity of the groundwater treatment system is limited, and the water extracted from well points very near the contaminant source are likely to be highly contaminated, this alternative will be avoided, if possible. If unavoidable, it may be necessary to add temporary treatment capacity to the groundwater treatment system to deal with the additional flow and contaminant loading.]

Will be

5.0 COVER AND COVER DESIGN

As discussed in Section 2.2, the proposed alternate remedy includes covering the areas of the Site containing buried waste, as defined in the SOW. The Still Bottoms Pond Area and the Off-Site Area (including the Off-Site Containment Area, the area contiguous to the City of Griffith landfill, and the Kapica-Pazmey Area) are the two areas of the Site that will be covered. Both of these areas contain concentrations of VOCs and PCBs in the defined as buried waste which must be addressed as part of the Site remedial action. In addition, the Kapica-Pazmey section of the Off-Site Area contains elevated concentrations of lead in the soil. The main objectives of covering these areas are:

1. Eliminate potential direct contact with VOC- and PCB-contaminated soils (and lead-contaminated soils in the Kapica-Pazmey Area);
2. Eliminate potential worker contact with VOC-contaminated groundwater;
3. Reduce the potential for contaminant migration to groundwater by reducing infiltration to these areas; and
4. Provide a surface seal for the ISVE system, to minimize potential short-circuiting and maximize the capture of VOC vapors.

In addition, covering these areas will reduce the storm water infiltration into the area inside the barrier wall, thereby reducing the amount of groundwater to be treated by the groundwater treatment plant.

5.1 COVER REGULATIONS

Because covering was not a part of the original ROD, the requirements for covering at the ACS Site are not outlined in the SOW. Therefore, several regulatory references were used in the evaluation of various alternatives for the cover (4, 5). An evaluation of conventional and alternative designs was conducted to determine an appropriate covering remedy design. Both Federal (U.S. EPA Subtitle D) and Indiana Department of Environmental Management (IDEM - Municipal and Hazardous Waste Landfills) regulations were used to provide potential design criteria for the evaluation. These regulations are particular to solid and hazardous waste landfills, and therefore are not applicable to the ACS Site. However, they are relevant and may be appropriate for the final cover selection. IDEM was contacted directly to discuss the relevant and appropriate requirements, and recommended 329 IAC 10-22-7 and deferred to U.S. EPA requirements to be used as guidance for the cover design. This guidance requires the equivalent of a model RCRA cover (composite cover with methane vent layer, drainage layer, frost protection layer, topsoil and vegetation) that is 60 inches thick. However, the methane vent layer and drainage layer are unnecessary at the ACS Site, as explained in the following sections.

5.1.1 Methane Collection

Because of the landfilled nature of the Off-Site Containment Area, methane generation in this area could be a concern following the installation of an engineered cover. However, because the ISVE system in this area will extract and treat the vapors from within this area, the need for a methane collection or vent system is eliminated. For long-term venting, following the shut-down of the ISVE system, the ISVE wells will be modified to serve as passive vent points.

Methane generation is not anticipated at the Still Bottom Ponds Area, but is possible if there is anaerobic biodegradation occurring in the subsurface soil. As with the Off-Site Containment Area, the methane, if generated, will be removed through the ISVE wells either under an active or passive operation.

5.1.2 Drainage Layer

Although a requirement of the model cover referenced in the 329 IAC and U.S. EPA Guidance, drainage layers for the covers at the ACS Site are unnecessary. Because of the low slopes associated with the covered areas (1% in the Still Bottoms Pond and 1-8% in the Off-Site Area), a drainage layer would not effectively collect significant volumes of water. This is supported by the HELP analyses included in Appendix D.

Furthermore, because the ACS Site is an operating facility with truck and equipment traffic, process and water pipes, storage areas, existing above ground tank, existing buildings and other structures the profile of the cover must be minimized, especially on the Still Bottoms Pond Area. Therefore, alternatives to the model cover are being evaluated.

5.2 ALTERNATIVES EVALUATION

Various cover configurations are being evaluated for regulatory acceptance, effectiveness in the infiltration reduction, integration with the ISVE system, costs (qualitatively at this point), and coordination with the ACS operating facility ongoing production activities. For example, the cover to be placed on the Still Bottoms Pond Area must:

- Significantly reduce the storm water infiltration through this area,
- Comply with relevant and appropriate regulatory requirements,
- Provide an adequate surface seal for the ISVE system, and
- Be cost effective

Further, if possible, the cover should:

- Minimize disruption to the ACS operating areas, and allow access to operational areas within the ACS facility

The first part of evaluating the types of covers that are acceptable is to determine the effectiveness of reducing infiltration. Infiltration through the covers was evaluated by using the Hydrologic Evaluation of Landfill Performance (HELP4) Model (7). The model is a two-dimensional iterative hydrological model of water movement across, into, through, and out of impacted soils and landfills.

The HELP4 model was used to compare the performance of eight standard and alternative cover designs. Weather data utilized for the evaluation were generated by the HELP model as default values for Chicago, Illinois, and were constant for all modeled alternatives. Variables for the modeling input included cover design layer-characteristics such as soil and geosynthetic layer types and thickness. Table 2 summarizes the modeled output results from selected cover and cover alternative design scenarios. Appendix D contains the complete model input and output.

5.3 PROPOSED COVERS

Based on the HELP model results, discussions with IDEM, consideration of potentially relevant and appropriate requirements and coordination with the ACS operating facility, the following covers are proposed.

5.3.1 Still Bottoms Pond Area

The alternatives for covering the Still Bottoms Pond Area considered two scenarios: a cover for operating site area and a cover for non-operating site area. The cover for a non-operating site area was evaluated for the Off-Site Containment Area and will not be further evaluated here. The cover for the operating site were focused to two types, following the initial evaluation:

1. A composite cover with gravel cover, incorporating asphalt access roads.
2. An asphalt cover with composite low-permeability zone and wearing surface.

The area to be covered in the Still Bottoms Pond Area is shown on Figure 9, along with sections of the covers. The actual final cover profile is still being evaluated and will depend on the operating requirements worked out with ACS Inc. For example, because of the insurance stipulations of the ACS facility, vegetation is not permitted within the ACS facility, therefore, neither of the two alternatives for the operating areas includes any form of vegetative cover.

→ so evapotranspiration is out.

Either alternative would consist of covering the Still Bottoms Pond with 12 inches of compacted clay, covered by geotextile, and six inches of gravel/slag as the initial layers of the final. These initial layers will be constructed as an interim cover prior to lowering the water table and installation of the ISVE system to reduce infiltration while dewatering. The final profile of the cover is still being evaluated and may depend on operating needs of the ACS plant.

Table 2. HELP4 Results for Modeled Scenarios
ACS NPL Site

Trial Cover Design Number and Description	Average Annual Totals			Peak Daily Values	
	inches	cubic feet	percent	inches	cubic feet
Offsite Cap Design					
Cap 1 - Standard RCRA Model Cap	(6"OL, 18"ML, 12"SP, FML, 24"CL)				
Precipitation	34.15	647,013	100	4.64	87,921
Runoff	2.86	62,407	8.39	2.06	44,851
Evapotranspiration	25.47	554,649	74.58	--	--
Percolation Through Cover	0.00021	4.65	0.00062	0.00046	10.11
Lateral Drainage Collected	5.8	126,345	16.99	0.03	651
Cap 2 - Alternative Cap	(6"OL, 18"ML, Geosynthetic, FML, GCL, 12"CL)				
Precipitation	34.15	647,013	100	4.64	87,921
Runoff	5.17	112,633	15.15	2.27	49,451
Evapotranspiration	28.97	630,898	84.83	--	--
Percolation Through Cover	0.0038	83.08	0.011	0.00022	4.71
Cap 3 - Alternative Cap	(6"OL, 12"ML, 0.2" FML, 12"CL)				
Precipitation	34.15	743,693	100	4.64	101,059
Runoff	5.17	112,659	15.15	2.27	49,439
Evapotranspiration	28.97	630,903	84.8	--	--
Percolation Through Cover	0.0034	73.6	0.0099	0.00026	5.68
Offsite Cover Design					
Offsite cover - Cover Area Limiting Rainfall Infiltration	(6" OL, 12"CL)				
Precipitation	34.15	867,642	100	4.64	117,902
Runoff	7.761	197,206	22.73	3.53	89,879
Evapotranspiration	25.07	636,995	73.42	--	--
Percolation Through Cover	1.32	33,441	3.85	0.01	259

5.3.2 Off-Site Containment Area

Several cover alternatives for non-operating areas, such as the Off-Site Containment Area were evaluated and narrowed to a single alternative. The cover will be placed only over those areas where there is buried waste as defined in the ROD and over areas of Griffith Landfill that extend off the Site. Twelve inches of compacted clay (much of which has already been placed) will be installed as an interim cover during initial operation of the ISVE system. Following initial start-up, a FML would be installed over the clay, to provide the primary low-permeability layer. A 12-inch root zone would be installed over the FML layer, and finally a six-inch topsoil layer would be installed and seeded to provide vegetative cover.

Outside of the covered Off-Site Containment Area, infiltration will be minimized possibly with a cover installed over this area. The cover would consist of 18 inches of compacted clay, covered with six inches of topsoil and vegetated. The areas and typical sections for the covered and uncovered areas, based on the information provided herein, are shown on Figure 10.

5.4 SURFACE WATER DRAINAGE CONTROL

The surrounding Off-Site and On-Site areas will be graded to improve storm water run-off and prevent storm water run-on. The drainage ditches and swales will be lined with appropriate erosion control measures, such as straw matting, silt fencing, hay bales, riprap, where necessary. The areas that currently pond water on the ACS facility will be regraded to drain into the existing storm sewer system, or off-site to the north or west wetlands. The drainage patterns for both the On-Site Area, and the Off-Site Area, are shown on Figures 9 and 10.

5.5 COVER IMPLEMENTATION

The first layer of the final covers will be placed as a temporary cover on the Still Bottoms Pond Area and the Off-Site Containment Area, and will consist of 12 inches of compacted clay, to provide a surface seal during the ISVE Start-Up. The 12 inches of clay will serve as a temporary cover for the ISVE areas, and will allow adjustments to be made in the ISVE systems (piping modifications, repairs, valve or port additions, etc.) during initial start-up of the ISVE systems. In this manner, damage to the final cover due to these potential adjustments will be avoided. Following initial ISVE system start-up, the final cover can then be constructed atop the initial 12-inch clay layer, taking care to incorporate the ISVE wells into the final cover surface. Because the Off-Site Area currently has approximately 12 inches of compacted clay in place, the placement of the first layer of the cover will be relatively simple, to consist of minor regrading and recompaction. In the Still Bottoms Pond Area, the existing gravel/slag base will be scraped up to a depth of approximately 12 inches, the ISVE system will be installed, and 12 inches of clay will be placed and compacted. The gravel/slag will then be reused to construct access roads on top of the 12-inch clay layer.

no freeze/thaw protection

6.0 DRUM REMOVAL IN THE ON-SITE CONTAINMENT AREA

The On-Site Containment Area contains buried drums that were identified using historical aerial photographs, geophysical investigations, and test pitting. In addition, during installation of a water line from the ACS facility to the groundwater treatment plant, several buried drums were noted in the side wall of the excavation. The drums discovered during test pitting and installation of the water line appear to have been stacked three high, and are generally intact. They are buried from 1 to 2 feet deep, and extend to approximately 8 to 10 feet below the ground surface. These areas are shown on Figure 2.

Based on the geophysical investigation conducted in 1991, during the remedial investigation of the Site, one particular area of the On-Site Containment Area was identified as containing a group of relatively intact drums. Based on the apparent areal extent and subsequent test pitting to determine the depth of the drums, this area was estimated to contain up to 1000 drums. The geophysical investigation conducted in 1998, which identified two more areas of probable buried drums, resulted in a revised estimate of up to approximately 2,500 buried drums, based on total areal extent and the assumption that the drums are stacked 3 high in the subsurface. It has not been confirmed that these areas do contain drums, but these areas will be investigated to confirm and delineate the extent of buried drums and to determine the drums' integrity prior to excavation.

6.1 DRUM REMOVAL WORK PLAN

The proposed drum removal in the defined areas would be conducted in accordance with the June 1997 Drum Removal Work Plan, submitted at the request of U.S. EPA and incorporated herein by reference. The objective of the drum removal is to excavate and dispose of drums in the On-Site Containment Area. The areas to be excavated would be based upon the geophysical investigations and would be staked in the field after confirming and delineating the location of drums prior to excavation.

In general, the drums within the areas defined by the geophysics will be excavated and staged in a lined, bermed area near the excavation. Air monitoring will be implemented to ensure a safe working environment, and work will begin in Level B personal protective equipment. Each drum will be fingerprinted to determine the waste characteristics, and then drums will be segregated into similar and compatible waste streams. Composite samples of each waste stream will be collected and analyzed to obtain disposal authorization. Following receipt of the analytical data from the waste streams, a waste evaluation report will be submitted to U.S. EPA, with recommendations on disposal alternatives for the drums. Upon U.S. EPA approval, the drums will be sent off-site for incineration, following applicable manifesting and transportation regulations. Drums that are not intact would be bulked for shipment. Drums not accepted at an off-site disposal facility would be buried in the existing Fire Pond (part of the Still Bottoms Pond Area), within the area to be covered and treated with ISVE. Contaminated soils that are excavated during the drum removal would also be placed in this area to be treated with ISVE.

7.0 OFF-SITE GROUNDWATER TREATMENT

Two areas of upper aquifer groundwater contamination have been delineated at the ACS Site. The shallow groundwater plume extending approximately 700 feet north from the ACS facility has been termed the North Area and a plume extending approximately 2,000 feet to the east-southeast has been termed the South Area. Localized contamination has been documented in the lower aquifer near monitoring well MW-9. This contamination appears to be a direct result of leakage along the well casing at monitoring well MW-9 and does not appear to be part of a wide spread release into the lower aquifer. The well has been abandoned and replaced with MW-9R, future monitoring will be used evaluate whether or not the source of lower aquifer impact has been eliminated.

The outer line on Figure 1, marks the approximate extent of contamination in the upper aquifer at the site. These areas were formed when groundwater contaminants migrated away from the source areas, after ACS began operations in 1955. The installation of the barrier wall in 1997 cut off further migration of contaminants from the source areas to the groundwater in the North and South Areas. However, these two areas of groundwater contamination remain outside the barrier wall. The primary contaminants in the groundwater are benzene and chloroethane.

7.1 DESCRIPTION OF UPPER AQUIFER CONTAMINATION

The North and South Areas of Groundwater contamination coincide with the historical groundwater flow paths outward from the ACS facility. The North Area of groundwater contamination results from groundwater flow from the source areas inside the ACS facility toward the north and west. The South Area of contamination results from the groundwater flow path from the Off-Site Containment Area and Kapica-Pazmey Area to the south, southeast.

Currently, a natural attenuation study is being conducted in both the North and South Areas to evaluate the capacity of naturally occurring process, in the soil and groundwater to attenuate the contaminants within the plume. Periodic monitoring is being conducted at wells within each affected area and at the edges of each area to document any trends or constants in the groundwater quality and contaminant concentration. The results will be further evaluated by the application of modeling to assess the relative contributions of microbes in the soils, reductive dechlorination, volatilization, and dilution. The natural attenuation study was started during the third quarter of 1997, after the barrier wall was closed, cutting off the original source of the groundwater contamination from further migration to the affected areas.

7.1.1 North Area

Historically, groundwater in the North Area started inside the ACS facility and flowed to the west and north, where it discharged to surface water. To the west, the groundwater discharged into the wetlands within 200 to 500 feet of the ACS facility. Samples collected 800 feet directly west of the ACS facility (MW 46), have showed only trace levels of benzene, indicating the end of the area of contamination. To the north, groundwater discharged to the drainage ditch 400 to 600 feet northwest of the facility. Samples collected north of the ACS facility (from monitoring wells MW 48 and MW 49), have consistently contained elevated levels of benzene (up to approximately 9.5 ppm) and chloroethane (up to 1 ppm). Monitoring wells located further to the north show that the area of contamination ends in that direction (MW37, MW38, and MW39) 9.50 ppm

The PGCS, shown on Figure 1, was installed specifically to halt the further off-site migration of contaminants to the north and west. Sampling indicates that the PGCS has been successful in capturing the contamination to the west of the ACS facility. However, monitoring results at MW48 and MW49 suggest that an area with benzene concentrations of up to 10 ppm that is beyond the hydraulic influence of the PGCS extraction system, and therefore, it represents a potential on-going "source" of contamination.

It is unlikely that natural attenuation will reduce the benzene concentrations to below MCLs within the next ten years, so active remediation of the source in this area is proposed in the Alternate Remedy. The remediation method proposed for this source is enhanced in-situ bioremediation through the addition of oxygen in the contaminant are using products such as Oxygen Release Compound (ORC®). ORC® is a formulation of magnesium peroxide that slowly releases (over 6 to 12 months) molecular oxygen when hydrated. The released oxygen enhances the naturally-occurring attenuation process in the zone of contamination. The oxygen introduced into the groundwater by ORC® promotes microbial growth and maximizes the ability of aerobic microbes to degrade the contaminants.

The remedial plan includes the treatment of an upper aquifer area, 100 by 100 feet, with a saturated thickness of 10 feet as shown on Figure 11. The theoretical ORC® requirement is based on the stoichiometric requirement of 3 oxygen molecules for every carbon molecule, and an oxygen content of 1 pound for every 10 pounds of ORC®. Calculations, based on a contaminant level of 9 ppm, indicate that approximately 150 pounds of contaminants exists in the plume area. Therefore, approximately 4,500 pounds of ORC® will be required to enhance the natural degradation of the benzene and chloroethane contained in the current source of the North Area.

The ORC® will be injected across the upper aquifer by geoprobe. The geoprobe will be used to punch vertical holes across the upper aquifer in an 100 by 100 foot array with ten foot spacing. The geoprobe will inject approximately 45 pounds of ORC® into each of 100 holes punched across the saturated thickness of the upper aquifer. Monitoring will continue at the monitoring wells in the vicinity and the results will be used in conjunction with the Natural Attenuation Investigation to evaluate the effectiveness of bio-attenuation, enhance by ORC®.

benzene = food for aerobic decomp. of chlorinateds

Not
useful
w/ chlor.
+

7.1.2 South Area

An area of benzene and chloroethane contamination also extends approximately 2000 feet beyond the barrier wall towards the south-southeast in the upper aquifer. The historical monitoring data indicate contaminant concentrations are generally below 1 ppm in this area. Sampling results from monitoring wells MW41, MW42, MW43, MW44, and MW47, show that the extent of the contaminated areas has been defined (Figure 1). A portion of this plume area is located in what is essentially a low-lying wetlands area, which is conducive to the microbial activity integral to natural attenuation. Immediate active remediation is not planned for the South Area. It is also the subject of the natural attenuation study which will continue until the third quarter of 1999.

Decreases have already been noted in the benzene and chloroethane concentrations inside the South Area of contamination. On the basis of the monitoring data and estimates of natural attenuation based on the expected half-life for benzene in the upper aquifer, Montgomery Watson calculates that the benzene concentrations will be below the MCL of 5 ppb within ten years. By the end of 1999, the Natural Attenuation Study will have been completed and active remediation by ORC® will have been conducted in the North Area for one year. If the results of the Natural Attenuation study and concurrent monitoring indicate that benzene concentrations may not reach the MCLs within ten years, the experience gained from the ORC® application in the North Area will be applied to the South Area in developing an active remediation plan.

Not
seen
enough.

8.0 MISCELLANEOUS ACTIVITIES

Several miscellaneous activities will be conducted as part of the final remedy for the Site. The following paragraphs briefly describe these miscellaneous activities:

- Removal and Consolidation of PCB-Impacted Sediments from a drainage swale in the Wetlands
- Consolidation of Miscellaneous Debris
- Upgrades to the Groundwater Treatment System
- Coordination with the ACS Plant Utilities

8.1 REMOVAL AND CONSOLIDATION OF PCB-IMPACTED SEDIMENTS IN THE DRAINAGE SWALE

The wetlands area to the west of the ACS facility, where the surface drainage runs away from the Site, has been found to contain PCBs in the sediments. The PCB contamination appears to be limited to the upper foot of sediment in this area, as defined in the Phase II Wetlands Investigation Report, February 1997 and shown on Figure 1. As part of the final remedy, this area will be excavated to a depth of approximately 1 foot, and transported to the Fire Pond, where it will be graded in the area to be covered. The total volume of the PCB-impacted soils to be excavated is approximately 850 cubic yards, based on the areal extent and a 1-foot depth. Sediment samples will be collected from the floor and the sides of the excavation, to confirm that PCB concentrations greater than 1 ppm have been removed. The wetlands area excavation will be backfilled with hydric soils, and reseeded with native wetlands vegetation.

No cat tails allowed.

8.2 CONSOLIDATION OF MISCELLANEOUS DEBRIS

Prior to installation of the cover or ISVE systems in the Still Bottoms Pond Area, the Fire Pond will need to be filled. If uncontaminated soils ("clean fill") from an off-site source were used to fill the Fire Pond, they would necessarily be placed in an area which is known to contain hazardous materials, thus rendering the "clean fill" contaminated. Instead, the placement of materials from several excavated areas on Site will be consolidated in the Fire Pond, to be covered and treated by ISVE. These materials include:

- the investigate-derived materials (soil cuttings) now contained in drums.
- Contaminated soil, debris, non-intact drums or drums from the drum removal activities in the On-Site Containment Area, that are not accepted at an off-site disposal facility.
- The PCB-impacted soils excavated from the wetlands area

- The soil from the spoils piles (VOC- and PCB-contaminated waste and soil) from the barrier wall installation that currently lie in the Off-Site Area.

The placement of these materials in the Fire Pond will eliminate the need to fill the Fire Pond with uncontaminated soil. By placing Site-derived materials into the Fire Pond, further contamination of "clean" materials will be avoided, and the materials which are placed in the Fire Pond will be conveniently located for covering and ISVE treatment.

8.3 GROUNDWATER TREATMENT PLANT UPGRADE

Montgomery Watson currently operates the groundwater treatment plant at the American Chemical Service NPL site in Griffith, Indiana. Groundwater is pumped from two sources: the Perimeter Groundwater Containment System (PGCS) and the Barrier Wall Extraction System (BWES). This treatment plant was designed to treat primarily groundwater from PGCS. However, in the recent past, with increased activated carbon cells, groundwater from the BWES has also been treated in this treatment plant. The groundwater characteristics from the two sources continually change. In order to continue treating the groundwater and not compromise the treatment efficiency, Montgomery Watson has identified specific upgrades/modifications that are necessary for this treatment plant. The following sections discuss the key upgrades/modifications that Montgomery Watson recommends be executed.

8.3.1 Install a Second Air Stripper

The concentrations of VOCs in the groundwater from the BWES source have increased. Currently, the existing groundwater treatment plant has a shallow tray air stripper to remove the VOCs. Because of the high VOC loading on the air stripper, a significant portion of the VOCs reside in the wastewater downstream of the air stripper and get adsorbed onto the activated carbon resulting in increased carbon replacement costs. In order to reduce the costs incurred in replacing activated carbon, Montgomery Watson proposes installing a second shallow tray air stripper in series with the existing air stripper.

8.3.2 Provide Outside Air Intakes for the Air Strippers

At the present time, air for the existing air stripper is drawn from inside the groundwater treatment plant building. Installation of a second air stripper will result in increased air intake for the air strippers from inside the building. The air inside the building is heated to a temperature of 70 degrees F during the winter. Continually drawing heated air for air stripping will result in increased utility consumption costs to maintain a heated environment inside the building. Montgomery Watson proposes that air intakes for the blowers be extended to outside the building. This should reduce the utility consumption costs.

*thermal
oxidizer
will have
heat.*

8.3.3 Install Filter Upstream of the GAC Cells

Despite installing a clarifier and a sand filter prior to the activated carbon cells, there has been evidence of carbon fouling by particulate matter. Montgomery Watson installed a

pilot cartridge filtration system upstream of the carbons and found considerable build up of particulate matter on the filter cartridges. Montgomery Watson believes that particulate matter smaller than 10 microns (μ) will escape collection in the sand filter and plug the carbon cells. Periodic backflushing of the carbon and early replacement of the spent carbon results in increased operating costs for the treatment plant. Installing a proper filtration system upstream of the carbon cells will lower the risk of carbon plugging and hence reduce such operating costs.

8.3.4 Phase Separator Installation

The concentrations of organic compounds in the BWES groundwater are high, and the groundwater that is extracted during dewatering may contain some free phase product. The existing separator at the groundwater treatment system can handle up to 35 gpm. However, during dewatering, this flow will likely be increased. Lack of phase separation will result in overwhelming specific treatment units such as the UV-Oxidation unit and the activated carbon cells. Therefore, more capacity is needed in the phase separator step of the treatment process. Hence, Montgomery Watson proposes installing a second phase separator to separate the free phase product from the groundwater.

8.3.5 Coagulant Delivery System

Montgomery Watson proposes to install a permanent coagulant feed system to the clarifier in the existing treatment plant. At the present time, Montgomery Watson uses a polymer in conjunction with a coagulant to achieve maximum solids removal in the clarifier. The coagulant addition system currently in place is a temporary arrangement. Montgomery Watson plans to properly engineer a permanent coagulant addition system and install it at the groundwater treatment plant.

8.3.6 Install a Final Biological Groundwater Treatment System

The existing ACS NPL Site groundwater treatment plant was designed to treat a maximum influent COD of 55 mg/L. The COD of the BWES groundwater has exceeded 1,000 mg/L, on occasion, and could reach higher levels in the future. The organic pollutants and COD are currently reduced in the UV-Oxidation system and the granular activated carbon columns. These two systems are not capable of adequately reducing the COD if the influent COD is in the range of 1,500 mg/L and therefore upgrades are required to treat additional BWES groundwater on a continuous basis.

Montgomery Watson currently is installing a biological treatment system pilot study consisting of 3 Fract tanks to provide activated sludge reactors and a sludge clarifier, and two blowers to aerate the system. To select the best approach and design for the long-term biological treatment at the Site, specific process information is necessary such as treatment efficiency, COD reduction, etc. Montgomery Watson proposes to operate the pilot system for four months while this process information is generated. Once the data from the interim biological treatment system is obtained, Montgomery Watson proposes that a full-scale permanent groundwater treatment system be designed and installed.

8.4 COORDINATION WITH THE ACS PLANT UTILITIES

A number of above ground and under ground utilities exist in the Still Bottoms Pond Area, inside of the ISVE system footprint. Because this area will be covered as part of the final remedy, intrusive activities within this area must be restricted. Therefore, the utilities within this area will need to be relocated or abandoned and structure will need to be removed or relocated. The measures to be implemented in the Still Bottoms Pond Area to allow ISVE system installation and covering are provided on Figure 12.

The former tank farm, concrete foundations and slabs, utilities and other operating and non-operating facilities within the area to be covered and treated with ISVE will need to be addressed prior to construction. Coordination with the ACS Facility to determine operating requirements, if necessary in this area, will be conducted. To provide the operating ACS facility with access through the ISVE system area, an asphalt-paved access road may be installed through the ISVE system well field at the approximate location where the existing truck access road is located. The overhead pipe rack could be placed directly along side this road, and access to this area could then be allowed. Vehicle access to the remaining ISVE system area would be restricted.

9.0 PROPOSED PROJECT SEQUENCING

Because of the complexity of the project, and the interaction of the various components, a project sequence that illustrates the approximate time frames for each of the remedial components has been developed. The attached flowchart illustrates the dependence of certain components on others. For instance, the ISVE system in the Still-Bottoms Pond Area cannot be implemented before the dewatering in this area is complete; the covering of the Still Bottoms Pond Area cannot be started before the Fire Pond is filled; the Fire Pond cannot be filled before the PCB-contaminated sediments are excavated from the wetlands, etc.

10.0 REFERENCES

1. Pretreatment/Materials Handling Study Report, American Chemical Service (ACS) Site, Focus Environmental, Inc., October 1997
2. Thermal Treatability Study Report, American Chemical Service (ACS) Site, Focus Environmental Inc., December 1997
3. Final Report Feasibility Study, ACS NPL Site, Griffith, Indiana, Warzyn, Inc., June 1992.
4. The July 1989 RCRA Technical Guidance Document: Final Covers on Hazardous Waste Landfills and Surface Impoundments (PB89-233480)
5. RCRA covers and final covers for municipal solid waste landfills are described in 40 CFR 264 Subpart G and 329 Indiana Administrative Code (IAC) 10-22-7
6. EPA document 600/R-93/028 Decision-Support Software for Soil Vapor Extraction Technology Application: Hyperventilate
7. Hydrologic Evaluation of Landfill Performance Version 3.07 (HELP4), U.S. Army Corps of Engineers Waterways Experiment Station, United States Environmental Protection Agency Municipal Environmental Research Laboratory
8. ORC Applications Software Version 2.0, Regenesi

TLH/BPG/TAB/tab/dlp/emp/TLH/tlh
J:\1252\042\final remedy\conceptual_workplan.doc
1252042.260101






FIGURE 1

PROPOSED REMEDIAL COMPONENTS

CONCEPTUAL DESIGN
AMERICAN CHEMICAL SERVICE, INC.
NPL SITE
GRIFFITH, INDIANA

Drawing Number
1252042
260101

MONTGOMERY WATSON



Developed By TLH Drawn By DKP

Approved By TAB Date 8/6/98

Reference J-1252/042/MWOWS/CONCEPTUAL PLAN/PRO_REM_CON.dwg

Revisions


This document has been developed for a specific application and may not be used without the written approval of Montgomery Watson.

QUALITY CONTROL

Graphic Standards
Lead Professional

Technical Review
Project Manager

Management Review
Other



LEGEND



PERIMETER GROUND WATER CONTAINMENT SYSTEM



AREAS WITH TOTAL VOCs > 10,000ppm



AREAS WITH TOTAL PCBs > 10ppm



AREAS WITH TOTAL PCBs > 10ppm
> 8FT BELOW GROUND SURFACE




AREAS WITH LEAD > 500 ppm



AREAS OF BURIED DRUMS - AS DEFINED
BY GEOPHYSICAL SURVEYS



APPROXIMATE EXTENT OF SITE CONTIGUOUS
WITH CITY OF GRIFFITH LANDFILL



SCALE IN FEET

FIGURE 2

AREAS OF SOILS IMPACT

AMERICAN CHEMICAL SERVICE, INC.
NPL SITE
GRIFFITH, INDIANA

Drawing Number
1252042
260101 **2**

**MONTGOMERY
WATSON**



Developed By TLH
Approved By TAB
Reference J-1252/042/MWOWS/CONCEPTUAL PLAN/AREAS_SL_IMP.dwg

Drawn By DKP
Date 8/6/98
Revisions



LEGEND


ISO-CONCENTRATIONS IN ppm

EXISTING GROUNDWATER LEVEL

FUTURE GROUNDWATER LEVEL

NOTE

DASHED ISO-CONCENTRATION LINE INDICATES AREA IS EXAGGERATED, BASED ON A SINGLE SAMPLE



HORIZONTAL SCALE IN FEET

0 80

VERTICAL SCALE EXAGGERATED 16:1

FIGURE 4

This document has been developed for a specific application and may not be used without the written approval of Montgomery Watson.

QUALITY CONTROL
Graphic Standards
Lead Professional

Technical Review
Project Manager

Management Review
Other




FIGURE 5

OFF-SITE CONTAINMENT AREA - ISVE SYSTEM PHASE STARTUP

SVE SYSTEM
AMERICAN CHEMICAL SERVICE, INC.
NPL SITE
GRIFFITH, INDIANA

Drawing Number
1252042
260101

5

MONTGOMERY
WATSON










Developed By TLH
Approved By TAB
Reference J-1252/042/NWDWGS/CONCEPTUAL PLAN/PHAS_STRT_OFF_SIT.dwg
Revisions
Drawn By DKP
Date 8/6/98

This document has been developed for a specific application and may not be used without the written approval of Montgomery Watson.

QUALITY CONTROL	Graphic Standards Lead Professional	Technical Review Project Manager	Management Review Other
-----------------	--	-------------------------------------	----------------------------

LEGEND:

-  SVE WELL (TOTAL OF 46)
30' RADIUS OF INFLUENCE
(60' DIA. TOTAL)
-  BURIED ISVE PIPING
-  BLOWER SHED
-  PROPOSED ROADWAY THROUGH
ISVE WELL FIELD
-  ISVE WELL OPERATED FOR
INITIAL START-UP
-  ISO-CONCENTRATION LINE
-  BARRIER WALL

NOTES:

1. PIPING WILL BE PLACED ON GRADE AND COVERED.
2. WELLS AND PIPING LOCATION WILL BE ADJUSTED AS NEEDED IN THE FIELD.





FIGURE 6


STILL BOTTOMS POND AREA - ISVE SYSTEM PHASED STARTUP

SVE SYSTEM
AMERICAN CHEMICAL SERVICE, INC.
NPL SITE
GRIFFITH, INDIANA

Drawing Number
1252042
260101

**MONTGOMERY
WATSON**

Developed By	TLH	Drawn By	DKP
Approved By	TAB	Date	8/6/98
Reference	J:/1252/042/MWDGSG/CONCEPTUAL PLAN/PHAS_STRT_STL_BOT.dwg		
Revisions			




TYPICAL WELL HEAD - STILL BOTTOMS AREA

LEGEND

- ③ SAMPLING PORT
- ⊙ VACUUM
- ⊗ VALVE
- ▽ FUTURE GROUNDWATER ELEVATION
- ▴ EXISTING GROUNDWATER ELEVATION

NOTE

NTS NOT TO SCALE



TYPICAL WELL HEAD - OFF-SITE AREA




FIGURE 7

TYPICAL WELL HEAD DETAIL

AMERICAN CHEMICAL SERVICE, INC.
NPL SITE
GRIFFITH, INDIANA

Drawing Number
1252042
260101

MONTGOMERY WATSON




Developed By TLH Drawn By DKP

Approved By TAB Date 8/6/98

Reference J:/1252/042/MWDGWS/CONCEPTUAL PLAN/Well_HEAD.dwg


Revisions









LEGEND


(V)	VACUUM GAUGE	(Symbol: Ball Valve)	BALL VALVE
(T)	TEMPERATURE GAUGE	(Symbol: Pressure Relief Valve)	PRESSURE RELIEF VALVE
(P)	PRESSURE GAUGE	(Symbol: Vacuum Relief Valve)	VACUUM RELIEF VALVE
(S)	SAMPLING PORT	(Symbol: Check Valve)	CHECK VALVE
(F)	FLOW METER		

FIGURE 8



LEGEND:

-  LIMITS OF ENGINEERED COVER
-  BARRIER WALL
-  ENGINEERED COVER SURFACE ELEVATIONS
-  INDICATES SURFACE WATER DISCHARGE FLOW DIRECTION
-  ACCESS ROADS
-  BWES TRENCH



PROPOSED ENGINEERED COVER FOR NON-OPERATING SITE

NOTES:

1. ENGINEERED COVER FOR OPERATING SITE WILL BE EVALUATED DURING PRELIMINARY DESIGN, AND WILL BE BASED ON ACS FACILITIES OPERATING REQUIREMENTS
2. THE FOLLOWING DESIGN OBJECTIVES WILL BE USED FOR THE ENGINEERED COVER FOR OPERATING SITE:
 1. LIMIT FILTRATION
 2. ELIMINATE DIRECT CONTACT WITH CONTAMINATES
 3. PROVIDE SURFACE SEAL FOR ISVE SYSTEM
 4. ALLOW ACCESS FOR ACS OPERATING AS NECESSARY

CONCEPTUAL CAP PLAN - STILL BOTTOMS POND AREA

AMERICAN CHEMICAL SERVICE, INC.
NPL SITE
GRIFFITH, INDIANA

Drawing Number
1252042
260101

9

MONTGOMERY WATSON



Developed By BPG Drawn By DKP

Approved By TAB Date 8/6/98

Reference J:/1252/042/NWDGWS/CONCEPTUAL PLAN/X-SEC-POND.dwg
Revisions

FIGURE 9

This document has been developed for a specific application and may not be used without the written approval of Montgomery Watson.

QUALITY CONTROL

Graphic Standards
Lead Professional

Technical Review
Project Manager

Management Review
Other

LEGEND:



AREA TO LIMIT RAINFALL INFILTRATION



LIMITS OF ENGINEERED COVER



TRENCH




PROPOSED SEPARATION BARRIER



BARRIER WALL




INDICATES SURFACE WATER DISCHARGE FLOW DIRECTION




ENGINEERED COVER SURFACE ELEVATIONS



RAINFALL INFILTRATION OUTSIDE OF ENGINEERED COVER WILL BE LIMITED BY GRADING AND VEGETATION



PROPOSED ENGINEERED COVER FOR NON-OPERATING SITE



INTERIM COVER LIMITING RAINFALL INFILTRATION




FIGURE 10

CONCEPTUAL CAP PLAN - OFF-SITE CONTAINMENT AREA

AMERICAN CHEMICAL SERVICE, INC.
NPL SITE
GRIFFITH, INDIANA

Drawing Number
1252042
260101

10

MONTGOMERY
WATSON



Developed By BPG

Drawn By DKP

Approved By TAB

Date

8/6/98

Reference J:/1252/042/MWDGWS/CONCEPTUAL PLAN/X-SEC-OFFSITE.dwg

Revisions





FIGURE 11




LEGEND:

- UTILITY POLE
- LIGHT POLE
- FIRE HYDRANT
- POST OR OBJECT
- SMALL SIGN
- SIGN POST
- GUARD RAIL
- GUARD FENCE
- CONCRETE DIVIDER
- FENCE
- RETAINING WALL
- TREE LINE
- WATER
- 6" TILE SEWER LINE
- 12" TILE SEWER LINE MAIN
- 12" IRON RUNOFF CATCH BASIN LINE
- 2" PVC WATER LINE AND 1/2" CABLE ELECTRIC (WELL SERVICE)
- 3/4" PVC WATER LINE
- 6" PVC SEWER LINE - WATER TREATMENT EFFLUENT
- 4" IRON NATURAL GAS LINE
- TELEPHONE CABLE
- 2" IRON NATURAL GAS LINE
- 2" ELECTRICAL CONDUIT (4 TOTAL)
- 3" PVC WATER RECIRCULATION LINE (2 TOTAL)
- 2" PVC AUXILIARY WATER LINE
- 6" IRON CONTAMINANT LINE - (TO SEPARATOR)
- 2" IRON STEAM LINE
- 1" IRON NITROGEN LINE
- 3" STAINLESS STEEL DOUBLE WALL TRANS LINE
- 12" PVC STORMWATER RUNOFF LINE
- 1" ELECTRICAL CONDUIT LINE TO FORMALDEHYDE SYSTEM
- 30" IRON FIRE PUMP SUCTION
- 6" IRON STORMWATER RUNOFF LINE
- 12" IRON CONTAMINANT LINE
- 4" IRON SEWER LINE - WATER TREATMENT EFFLUENT
- 1 1/2" ELECTRICAL CONDUIT
- 2" ELECTRICAL CONDUIT
- 1" ELECTRICAL CONDUIT TO COOLING TOWER SYSTEM
- 3/4" ELECTRICAL CONDUIT TO COOLING TOWER SYSTEM
- 2" ELECTRICAL CONDUIT
- 2" IRON NATURAL GAS LINE
- 1" PVC WATER LINE TO CHANGE BUILDING
- 2" FLEX CONDENSATE HOSE (ON SINK TRACK TIES)
- 4" TILE SEWER LINE
- 2" IRON WATER LINE FROM WELL TO PUMP HOUSE
- 1" ELECTRICAL CONDUIT - MAIN GATE
- 10" GALVANIZED STORMWATER RUNOFF LINE (MONITORING STATION)
- 12" GALVANIZED/PVC STORMWATER RUNOFF LINE
- 10" GALVANIZED STORMWATER RUNOFF LINE

NOTE:

- 1. DRAWING INDICATES APPROXIMATE LOCATION OF UNDERGROUND UTILITY LINES. FIELD VERIFICATION IS REQUIRED.



ACS FACILITY UTILITIES AND SITE PREPARATION

Drawing Number
1252042
260101
12
MONTGOMERY
WATSON

AMERICAN CHEMICAL SERVICE, INC.
NPL SITE
GRIFFITH, INDIANA


Developed By TAB
Approved By
Reference J/1252042/MWDWGS/NORTH_SOUTH_CAPSTILL_BOTTOM.cdr

Drawn By DKP
Date 8/6/98

Revisions

FIGURE 12

FIGURE 13: ACS Conceptual Sequence - Remedial Action




Project: 7_98_simple
Date: 8/13/98
7_98_simple

GW = Groundwater
ACS = American Chemical Service
GWTP = Groundwater Treatment Plant Upgrade
ORC = Oxygen Release Compound
ISVE = In-Situ Vapor Extraction
SBPA = Still Bottoms Pond Area
O&M = Operation & Maintenance

Task [Bar] Split [Dotted Line] Progress [Bar] Milestone [Diamond] Summary [Bar]





Appendix A - Contaminant Mass Calculations

Contents:

1. Calculation Explanation

2. Tables :

Table Number	Description
1a	Average Mass - Still Bottoms
1b	Average Mass - Off-Site
1c	Average Mass - K-P
2a	Still Bottoms Total VOCs
2b	Off-Site Area Total VOCs
2c	K-P Area Total VOCs
3	Percentage of VOCs in Each Area

3. Surfer Plots:

Plot Number	Description
1	Total VOC Concentrations - 0-3 ft.
2	Total VOC Concentrations - 3-5 ft.
3	Total VOC Concentrations - 5-10 ft.
4	Total VOC Concentrations - 10-15 ft.
5	Total VOC Concentrations - 15-20 ft.

4. Cross Sections

- 1 Off-Site Containment Area
- 2 Still Bottoms Pond Area
- 3 K-P Area

Mass Calculation for ACS NPL Site

Calculation of Areal extent:

- Soil sample results from the Remedial Investigation and soils samples collected since were compiled into one database. The data was sorted into the three main areas:

<u>Contaminant Area</u>	<u>Coordinates</u>
- Still Bottoms	(N6686 to N7166, E5268 to E5695)
- Off-Site Contaminant Area	(N5986 to N6343, E5083 to E5413)
- Kapica-Pazmey	(N5710 to N5915, E5023 to E5412)

- The soil sample results were plotted by Surfer and maps were generated by the following depth intervals:

- Still Bottoms:	0-3 feet, 3-5 feet, 5-10 feet, 10-15 feet, 15-20 feet, and 20-25 feet (not provided).
- Off-Site Contaminant Area:	0-5 feet, 5-10 feet, 10-15 feet, 15-20 feet, 20-25 feet (not provided), and 25-30 feet (not provided).
- Kapica-Pazmey:	0-5 feet, 5-10 feet, 10-15 feet, 15-20 feet, and 20-25 feet (not provided).

- A "dashed boundary" line was drawn on the attached surfer plots to indicate the areal extent of contamination. The areal extent was defined by soil sample results that were greater than 100 ppm. For example, sample results at locations next to each other had to be all less than 100 ppm to be outside the boundary. Conversely, if a sample with a concentration less than 100 ppm was surrounded by other samples with results greater than 100 ppm, the lower concentration sample location was included within the boundary.
- The volume of an area was calculated by assuming an approximate areal extent and multiplying by the depth of soil impacts. For example, in the Still Bottoms, the approximate size of the area is 450 feet diameter. The area is calculated as 159,043 square feet. The depth of the soil impacts are 25 feet, therefore the volume of impacted soil is 3,976,078 cubic feet. The volumes for the Still Bottoms area, Off-site area and Kapica-Pazmey are presented on Tables 1a, 1b, and 1c, respectively.

- Review of the soil borings within each depth interval shows that there are data gaps. For instance, soil samples may have been collected at a location in the 0-5 foot interval and in the 0-15 foot interval, but not in the 5-10 foot interval. It was reasonably assumed that if a contaminant was found at the upper and lower sample interval, the contaminant would be likely in the middle interval. Therefore, the volume was calculated by assuming the areal extent or "boundary" was consistent at each interval.

Calculation of Contaminant Mass

- The concentration of total volatile organic compounds (VOCs) for each sample was calculated by adding the concentration of individual contaminants and detection limits where applicable. For instance, some samples had elevated contaminant concentrations, causing detection limits for other individual contaminants to be raised by the laboratory and reported as non-detects. To be conservative, the concentrations of the non-detected compounds were set equal to the elevated detection limits in these samples.
- The average concentration within an interval was calculated by adding the total VOC concentrations of each sample within an area and depth interval and then dividing the sum by the total number of samples used for the summation. For example, in the sample interval of 0-3 feet in the Still Bottoms area, there where 6 locations were samples were collected; SB-091, SB-092, SB-093, SB-094, TP-05 and TP-07 (see Table 2a). The average for those six samples is 20,410 ppm. (See Table 1a). A list of the borings used for calculating the average concentration for the Still Bottoms, Off-site area and Kapica-Pazmey's intervals are presented in Tables 2a, 2b, and 2c, respectively and the averages are provided in Tables 1a, 1b, and 1c, respectively.
- The average concentration in each area is presented graphically by depth interval on the attached plan view surfer plots and the cross-sections.
- The average VOC mass was then calculated by multiplying the volume of the soil in each interval by the average concentration within that interval. A bulk soil density of sand at 100 lbs/cu. ft. was used. For example, in the interval of 0-3 feet for the Still Bottoms, the volume is 477,129 cubic feet and the average concentration is 20,410 ppm. The mass for that 3 foot thick interval is 973,803 pounds. (See Table 1a.) The mass for the Still Bottoms area, Off-site area and Kapica-Pazmey are presented on Tables 1a, 1b, and 1c, respectively.

The total mass was determined by summing the average mass of each interval.

- The area which would be affected by SVE is the area above the water table. This area is assumed to be 3 to 5 feet below the current water table which is assumed to be achieved with the future dewatering plan. The future water table levels are anticipated to be:

- Still Bottoms 10 feet below ground surface
- Off-Site Contaminant Area 15 feet below ground surface

Therefore, the average mass where SVE would be applied is the sum of the mass above the future water table. For example, the average mass for the Still Bottoms would be 3,624,123 pounds. The average mass for the Still Bottoms area and the Off-site area that would be treated with SVE, are provided in Tables 1a and 1b, respectively.

Note that since the VOC mass of the Kapica-Pazmey area is approximately 3% of the total VOC mass and only 0.3% of the total soil mass within the Kapica-Pazmey, SVE is not considered a remedy for this area (See Table 3).

TLH/TAB/dlp/emp/PVJ
\\chi1_server\jobs\1252\042\260101\Mass Calculation.doc
1252042.260101

Table 1a Average Mass Still Bottoms

z	Average (ppm)	Volume (cu. ft)	Average Mass (lbs)
3	20,410	477,129	973,803
5	6,425	318,086	204,378
10	30,758	795,216	2,445,941
15	5,592	795,216	444,684
20	335	795,216	26,666
25	154	795,216	12,230
Total Average	10,331	3,976,078	4,107,703
Avg. @ 10 Feet	22,787		

	Volume	Mass
Depth to 10 feet	1,590,431	3,624,123
Percent of total mass in Still Bottoms @ or Above 10 Feet.		88.2%

Table 1b Average Mass Off-Site

z	Average (ppm)	Volume (cu. ft.)	Average Mass (lbs)
5	1,324	414,788	54,910
10	1,018	414,788	42,214
15	35,330	414,788	1,465,453
20	6,659	414,788	276,187
25	229	414,788	9,484
30	174	414,788	7,231
Total Average	7,455.54	2,488,728	1,855,480
Avg. @ 15 Feet	12,557		

	Volume	Mass
Depth to 15 feet	1,244,364	1,562,577
Percent of total mass in Off-Site @ or Above 15 Feet.		84.2%

Table 1c Average Mass Kapica-Pazmey

z	Average (ppm)	Volume (cu. ft.)	Average Mass (lbs)
5	4,452	385,000	171,406
10	1,062	385,000	40,880
15	2	385,000	66
25	0.31	385,000	12
Total Average	1,103	1,540,000	212,363
Avg. @ 15 Feet	1,839		

	Volume	Mass
Depth to 15 feet	1,155,000	212,352
Percent of total mass in Off-Site @ or Above 15 Feet.		99.99%

Note: SB-030 was not included in the estimation of average mass because the area was excavated for the barrier wall and surrounding samples at the depth interval had low concentrations

Table 2a Still Bottoms Total VOC

LOCATION	EAST	NORTH	SUM VOCs	Depth top	Depth bottom	z
SB-091	5280.09	6889.12	128.07	3	3	3
SB-092	5367.35	6780.47	16487.4	3	3	3
SB-093	5499.68	6685.66	8417	3	3	3
SB-094	5661.57	6753.61	1996.3	3	3	3
TP-05	5496.76	6955.22	48040	3	3	3
TP-07	5545.19	6813.93	47389	3	3	3
TP-06	5558.39	6761.24	30490	4	4	5
SB-073	5429.86	6834.07	894.8	5	5	5
SB-074	5449.01	6877.5	43.28	5	5	5
SB-091	5280.09	6889.12	577.3	5	5	5
SB-092	5367.35	6780.47	12.566	5	5	5
SB-093	5499.68	6685.66	9704	5	5	5
SB-094	5661.57	6753.61	3254.8	5	5	5
SB-016	5468.79	6948.32	7310	6	6	10
SB-118	5620.5	6721.5	73250	6	8	10
SB-119	5567.4	6708.8	22968	6	8	10
SB-017	5534.22	6747.9	8685	6.5	6.5	10
SB-018	5575.58	6822.4	8097	7	7	10
SB-020	5322.66	6942.54	76.495	7	7	10
SB-021	5553.73	6950.64	0.443	7	7	10
SB-110	5660.5	6751.9	259260	7	9	10
SB-069	5545.1	6726.27	21446	8	8	10
SB-070	5582.86	6719.7	7663.3	8	8	10
SB-071	5620.11	6813.77	2086.2	8	8	10
SB-072	5599.25	6873.15	37.76	8	8	10
TP-04	5426.56	6889.23	2594.8	8	8	10
TP-03	5402.4	6826.16	17140	9	9	10
SB-014	5429.87	6817.52	75.66	11	11	15
SB-021	5553.73	6950.64	39.635	12	12	15
SB-022	5550.34	6780.1	8842.12	12	12	15
SB-023	5556.59	6698.85	82.505	12	12	15
SB-015	5462.63	6865.45	7180	13	13	15
SB-075	5486.98	6937.64	17332	15	15	15
SB-073	5429.86	6834.07	94.2	19	19	20
SB-074	5449.01	6877.5	576.46	19	19	20
SB-070	5582.86	6719.7	30.5	20.5	20.5	25
SB-071	5620.11	6813.77	61.23	20.5	20.5	25
SB-072	5599.25	6873.15	509	20.5	20.5	25
SB-069	5545.1	6726.27	14.466	21.5	21.5	25


Table 2b Off-Site Total VOC

LOCATION	EAST	NORTH	SUM VOCs	Depth top	Depth bottom	Z
SA-01	5220	5720	81.806	0.5	1.5	5
SA-02	5300	5770	1764.875	0.5	1.5	5
SB-081	5268.26	6343.38	0.4962	4	4	5
SB-082	5413.34	6280.41	5.1024	4.5	4.5	5
SB-004	5221.47	6099.18	4766.8	5	5	5
SB-079	5183.88	6101.94	0.5614	6	6	10
SB-080	5126.02	6209.15	0.4667	6	6	10
SB-081	5268.26	6343.38	0.7165	6	6	10
SB-082	5413.34	6280.41	1.255	6.5	6.5	10
SB-083	5394.79	6030.23	0.4102	6.5	6.5	10
SB-079	5183.88	6101.94	0.4643	8	8	10
SB-080	5126.02	6209.15	0.4838	8	8	10
SB-036	5299.96	5986.36	87.78	10	10	10
SB-037	5237.15	6051.48	419.45	10	10	10
SB-038	5261.78	6275.34	5107	10	10	10
SB-039	5173	6207.38	5576.5	10	10	10
SB-083	5394.79	6030.23	198.8	10.5	10.5	15
SB-025R	5395.52	6182.29	2659.5	11	11	15
SB-026R	5289.38	6151.73	59665	11	11	15
SB-027R	5343.42	6068.63	4116.25	11	11	15
SB-006	5325.93	6119.44	18133	11.5	11.5	15
SB-003	5242.55	6229.09	3322.9	12	12	15
SB-024R	5318.2	6267.85	34820.05	12	12	15
SB-005	5282.44	6039.4	3301.07	14	14	15
SB-007	5366.43	6229.86	222730	14	14	15
SB-006	5325.93	6119.44	4355	15	15	15
SB-003	5242.55	6229.09	33741.25	17	17	20
SB-005	5282.44	6039.4	62.27	17	17	20
SB-037	5237.15	6051.48	5069.5	17	17	20
SB-039	5173	6207.38	492.62	17	17	20
SB-004A	5212.68	6083.44	446.45	19	19	20
SB-007	5366.43	6229.86	13135	19	19	20
SB-003	5242.55	6229.09	60.28	20	20	20
SB-038	5261.78	6275.34	260.8	20	20	20
SB-024R	5318.2	6267.85	634.92	21	21	25
SB-025R	5395.52	6182.29	13.302	21	21	25
SB-026R	5289.38	6151.73	33.61	21	21	25
SB-027R	5343.42	6068.63	62.67	21	21	25
SB-037	5237.15	6051.48	13.836	23.5	23.5	25
SB-038	5261.78	6275.34	771.23	23.5	23.5	25
SB-039	5173	6207.38	43.04	23.5	23.5	25
SB-027RR	5346.91	6078.06	256.66	24	24	25
SB-024R	5318.2	6267.85	96.55	26	26	30
SB-026R	5289.38	6151.73	425.97	26	26	30
SB-025R	5395.52	6182.29	0.458	29	29	30

Table 2c K-P Total Vocs

LOCATION	EAST	NORTH	SUM VOCs	Depth top	Depth bottom	z
SB-001	5273.16	5710.15	31.83	3	3	5
TP-01	5225	5750	60770	3.5	3.5	5
SB-043	5365.56	5728.5	0.229	4.5	4.5	5
SB-044	5352.84	5793.67	6140	4.5	4.5	5
SB-045	5289.43	5738.93	31.14	4.5	4.5	5
SB-046	5279.87	5801.45	197.241	4.5	4.5	5
SB-047	5205.95	5814.14	213.969	4.5	4.5	5
SB-048	5235.04	5720.95	216.54	4.5	4.5	5
SB-049	5160.75	5726.03	0.268	4.5	4.5	5
SB-050	5145.95	5821.15	0.658	4.5	4.5	5
SB-051	5094.15	5721.8	3316	4.5	4.5	5
SB-052	5076.06	5832.98	1.215	4.5	4.5	5
SB-053	5005.94	5823.79	0.299	4.5	4.5	5
SB-054	5022.58	5723.33	0.906	4.5	4.5	5
SB-084	5305.16	5867	312.8	5	5	5
SB-085	5411.88	5793.81	0.4038	5	5	5
SB-002	5322.28	5808.58	904.7	5.5	5.5	10
SB-041	5016.05	5796.61	0.256	5.5	5.5	10
TP-01	5225	5750	0.322	6	6	10
SB-087	5317.73	5771.86	0.4724	7	7	10
SB-088	5138.92	5717.77	144.874	7.5	7.5	10
SB-028	5146.05	5901.21	5529.2	8	8	10
SB-029	5204.43	5831.57	588.98	8	8	10
SB-002	5322.28	5808.58	0.334	8.5	8.5	10
SB-001	5273.16	5710.15	0.31	9	9	10
SB-030	5096.61	5745.08	664500	10	10	10
SB-040	5072.57	5914.79	3448.8	10	10	10
SB-088	5138.92	5717.77	0.555	10.5	10.5	15
SB-087	5317.73	5771.86	2.857	11	11	15
SB-041	5016.05	5796.61	0.31	23.5	23.5	25

Total VOC Concentrations (with nds)



LEGEND



APPROXIMATE LIMIT OF DETECTED
TOTAL VOCs

APPROXIMATE LIMIT OF DETECTED
TOTAL VOCs

Total Volatile Organics (ppm)

Sample Depth
5-10 Feet


10,000
1,000
100

5000 5500 6000


TVOC-10.dwg


APPROXIMATE LIMIT OF DETECTED
TOTAL VOCs

Total VOC Concentrations (with nds)



Total VOC Concentrations (with nds)






Off-Site Area Section - Looking South




MONTGOMERY WATSON
Chicago, Illinois

American Chemical Services NPL Site
Griffith, IN

OFF-SITE CONTAINMENT AREA
SECTION 1





K-P Area Section - Looking South




MONTGOMERY WATSON
Chicago, Illinois

American Chemical Services NPL Site
Griffith, IN

K-P AREA
SECTION 3

Table 3
Mass of Total VOC Contamination by Area

	Areal Extent, acres	Contaminant Concentration, ppm	Mass of Total VOCs, lbs	
		Average	Average	% of Total
Still Bottoms Area	3.7	13,745	3,700,000	65%
Off-Site Area	1.9	10,890	1,807,740	32%
K-P Area	0.7	2,560	197,120	3%
			<hr/> <hr/> 5,704,860	



Appendix B - ISVE Modeling Results

Contents:

1. Modeling Explanation

2. Slides:

Slide Number	Description
1	Summary of Modeling Effort
2	Hyperventilate Modeling Inputs
3	Hyperventilate Modeling Outputs
4	Modeling Sensitivity Analysis
5	Conceptual ISVE Schematic
6	BioSVE Modeling - Percent Removed Over Time - Still Bottoms Pond Area
7	BioSVE Modeling - Percent Removed Over Time - Off-Site Containment Area

3. Off-Site Containment Area Modeling Results

Hyperventilate Screen Output

BioSVE Output @ 1.75 Darcy's

@ 5.2 Darcy's

@ 10 Darcy's

4. Still Bottoms Pond Area Modeling Results

Hyperventilate Screen Output

BioSVE Output @ 1.75 Darcy's

@ 5.2 Darcy's

@ 10 Darcy's

Modeling for ISVE ACS NPL Site

Modeling

- Two screening models, acceptable to the EPA, were used: Hyperventilate and BioSVE. These models only answer the question: "Is SVE feasible?" The equations upon which the models are based are simplistic and provide "ideal" mass removal (Johnson et. al and Johnson et. al). Because the models are simple, neither model predicts accurate mass removal after initial startup. (See Slide 1).
- Hyperventilate provides a check for the conceptual design, gives achievable vapor flows based on the soil type and permeability, and desired mass removal for a given time frame.
- The input parameters (See Slide 2) used for the Hyperventilate modeling effort were:
 - Soil permeability (based on site hydraulic conductivity, the soil's air permeability is 1.75 to 10 darcys)
 - Radius of influence (30 feet is typical and conservative for sand according to the hyperventilate manual)
 - Screen interval (5 feet in Still Bottoms, 10 feet in Off-site based on the proposed dewatering plan)
 - Well size (4 inch diameter - typical according to hyperventilate manual)
 - Remediation time (10 - 15 years considered reasonable)
- Hyperventilate outputs for both the Still Bottoms and Off-site are presented on Slide 3.
- A sensitivity analysis of the Hyperventilate model is presented on Slide 4. The information is based on the user manual and several model runs with differing inputs.
- A typical schematic for an SVE system is presented on Slide 5. The system generally consists of extraction wells or trenches, conveyance piping, a condensate tank, a blower and stack. Typically, off-gas treatment is required at the stack. (See Slide 5).
- BioSVE provided a time rate of removal, which will determine if and how much of the mass can be removed in the time interval of 10 to 15 years based on the individual contaminants that make up the total mass of VOCs. (See Slide 1).

- The input parameters for BioSVE were calculated in Hyperventilate. The limitations of the model include an upper bound on the total mass of contaminant that can be modeled. Therefore, the total VOC mass was divided by the number of wells anticipated for each area (from Hyperventilate) and BioSVE was modeled using the mass per well. The modeled output (percent mass removal), although it was determined based on the mass from one well, would apply to the entire site. The input parameters were:
 - Mass per well (total mass divided by number of wells)
 - Flowrate (from Hyperventilate - varies by area and permeability)
 - Time frame (15 years)
 - Area (total area divided by number of wells)
 - All other outputs were model defaults
- The output of BioSVE model is presented as a percentage of initial mass (See Slides 6 and 7).

REFERENCES

Johnson, P.C., C.C. Stanley, M.W. Kemblowski, D. Byers and J.D. Colthart, 1990. A Practical Approach to the Design Operation, and Monitoring of In-Situ Soil-Venting Systems, GWMR Spring 1990.

Johnson, P.C., M.W. Kemblowski, and J.D. Colthart, 1990. Quantitative Analysis for the Cleanup of Hydrocarbon - Contaminated Soil by In-Situ Soil Venting, Groundwater Vol. 28 No. 3 May June 1990.

TLH/blp/emp/TAB/PJV
 \\chil_server\jobs\1252\042\260101\SVE Modeling.doc
 1252042.260101

Summary of Modeling Effort

Two Models used as Screening Tools - Hyperventilate and Venting (BioSVE) - Both referenced by U.S. EPA

- Idealized models, predict maximum amounts, and don't account for subsurface dry-out and “crusting”

- Hyperventilate -

- Can the mass be SVE'd effectively?
- Will the Soil allow Adequate Flow?
 - Provides a check for conceptual design, gives required flow and achievable flows, but not time rate of removal.

- Venting (BioSVE) -

- How easily are contaminants released?
- Over what time frame will contaminants be released?
 - Uses achievable flows from Hyperventilate, gives time rate of removal

Hyperventilate Modeling Inputs

- Permeability, darcys 1.75 to 5.2 to 10 (silty sand to sand/debris to debris)
- ROI 30 ft (60 ft. well spacing)
- Screen Interval 5 ft (Still Btms), 10 ft (Off-Site)
- Vacuum 60" (Still Btms), 120" (Off-Site)
- Well Size 8" borehole, 4" pipe
- Remediation Time 10 - 15 yrs
- Depth of Water Table 8 - 10 ft (Still Bottoms)
12-15 ft (Off-Site)


Hyperventilate Model Outputs

- Required Rate of Removal 490 to 990 lb/day
- Achievable Rate of Removal 320 to 2970 lb/day
- Number of Wells Req'd 56 (Still Bottoms)
29 (Off-Site)
- Initial Vapor Conc. (ppm) 400 - 600 ppm
- Efficiency 70 - 85%


Modeling Sensitivity Analysis

- Permeability 1 to 1 Effect
- Well Radius 16% increase in flow for doubling size
- ROI 16% decrease in flow for doubling size
- Screen Length 1 to 1 Effect
- Vacuum 1 to 1 Effect below 120 in vacuum
- Time Inversely proportional to desired removal rate


Conceptual ISVE Schematic



BioSVE Modeling - Percent Removed Over Time



BioSVE Modeling - Percent Removed Over Time



Flowrate Estimation:

- ☐ Medium Sand
- ☐ Fine Sand
- ☐ Silty Sand
- ☐ Clayey Silts

☒ Input Your Own Permeability Range

Permeability Range (darcy)

1.75 to 5.2

Well Radius

2 in

Radius of Influence

30 ft

Interval Thickness*

10 ft

--> Calculate Flowrate Ranges <--

thickness of screened interval, or permeable zone (whichever is smaller).

- 1) Choose Soil Type, or
Optional - Enter your own permeability values (darcy)
- 2) Enter Well Radius (in)
- 3) Enter Radius of Influence (ft) & Interval Thickness*
- 4) Optional - Enter your own well vacuum (406" = max)
- 5) Click button to calculate Predicted Flowrate Ranges

Predicted Flowrate Ranges

Well Vacuum P_w (in H_2O)	Flowrate (SCFM) (single well)	
5	0.93	to 2.76
10	1.84	to 5.48
20	3.64	to 10.83
40	7.10	to 21.11
60	10.38	to 30.84
120	19.11	to 56.77
108	17.49	to 51.98

4

OFF SITE

About Soils (& Unit Conversions)

8

Info about Calculation

Flowrate Estimation:

- ☐ Medium Sand
- ☐ Fine Sand
- ☐ Silty Sand
- ☐ Clayey Silts
- ☒ Input Your Own Permeability Range

Permeability Range (darcy)

1.75 to 10

Well Radius in
 Radius of Influence ft
 Interval Thickness* ft

--> Calculate Flowrate Ranges <--

*thickness of screened interval, or permeable zone (whichever is smaller).

- 1) Choose Soil Type, or
Optional - Enter your own permeability values (darcy)
- 2) Enter Well Radius (in)
- 3) Enter Radius of Influence (ft) & Interval Thickness*
- 4) Optional - Enter your own well vacuum (406" = max)
- 5) Click button to calculate Predicted Flowrate Ranges

Predicted Flowrate Ranges

Well Vacuum P_w (in H_2O)	Flowrate (SCFM) (single well)
5	0.93 to 5.30
10	1.84 to 10.54
20	3.64 to 20.82
40	7.10 to 40.59
60	10.38 to 59.31
120	19.11 to 109.17
108	17.49 to 99.95

About Soils (& Unit Conversions)

8

Info about Calculation

Vapor Concentration Estimation - Calculation

1 Type in Temperature (C) (hit <return>)

20

Click to Enter Composition of Contaminant

☒ Enter Distribution

2 or

☐ "Fresh" Gasoline

Choose one of the Default Distributions

☐ "Weathered" Gasoline

3 Click to View Distributions, (optional)

View Distributions

4 Click to Perform Calculations

☒ Perform Calculations

Results:

Sum of Mass Fractions

1.01900

Calc. Vapor Pressure

0.12642

atm

Calc. Vapor Concentration

409.59751

mg/l

How Do I Measure a Distribution?

← 10 →

About Calculation

Print Card

Maximum Removal Rate

Estimates

Select your unit preference below

☒ [lb/d]

☐ [kg/d]

Note:

These are "maximum removal rates", and should only be used as screening estimates to determine venting is even feasible at a given site. Continue on to the next card to assess if these rates are acceptable...

Temperature (C)
Soil Type
Soil Permeability Range (darcy)
Well Radius (in)
Radius of Influence (ft)
Contaminant Type
Permeable Zone Thickness (ft)

20	
User Defined	
1.75	to 5.2
2	
30	
User Defined	
10	

P _w - Well Vacuum (in H ₂ O)	Flowrate Estimates [SCFM] (single well)		Max. Removal Rate Estimates [lb/d] (single well)	
5	0.93	to	2.76	34.72 to 103.04
10	1.84	to	5.48	69.56 to 207.16
20	3.64	to	10.83	141.16 to 419.99
40	7.10	to	21.11	290.35 to 863.29
60	10.38	to	30.84	448.97 to 1333.92
120	19.11	to	56.77	999.49 to 2969.17
108	17.49	to	51.98	878.02 to 2609.46

Maximum Removal Rate

Estimates

Select your unit preference below

☒ [lb/d]

☐ [kg/d]

Note:

These are "maximum removal rates", and should only be used as screening estimates to determine venting is even feasible at a given site. Continue on to the next card to assess if these rates are acceptable...

Temperature (C)
Soil Type
Soil Permeability Range (darcy)
Well Radius (in)
Radius of Influence (ft)
Contaminant Type
Permeable Zone Thickness (ft)

20	
User Defined	
1.75	to 5.2
2	
30	
User Defined	
10	

P _w - Well Vacuum (in H ₂ O)	Flowrate Estimates [SCFM] (single well)		Max. Removal Rate Estimates [lb/d] (single well)	
5	0.93	to	2.76	34.72 to 103.04
10	1.84	to	5.48	69.56 to 207.16
20	3.64	to	10.83	141.16 to 419.99
40	7.10	to	21.11	290.35 to 863.29
60	10.38	to	30.84	448.97 to 1333.92
120	19.11	to	56.77	999.49 to 2969.17
108	17.49	to	51.98	878.02 to 2609.46

Is Soil Venting Appropriate?

At this point, you compare the maximum possible removal rate with your desired removal rate.

If the maximum removal rate does not exceed your desired removal rate, then soil venting is not likely to meet your needs, and you should consider another treatment technology, or make your needs more realistic.

In the next cards, we will refine the removal rate estimates, in order to decide if venting can achieve your objectives.

- ① Enter Estimated Spill Mass ☐ kg ☒ lb
- ② Enter Desired Remediation Time days
- ③

Single Vertical Well Results

Desired Removal Rate:	<input type="text" value="493.150"/>	[lb/d]
Gauge Vacuum (in H ₂ O):	<input type="text" value="120"/>	[in H ₂ O]
Min Flowrate @ 120in H ₂ O	<input type="text" value="19.11"/>	[SCFM]
Max Flowrate @ 120in H ₂ O	<input type="text" value="56.77"/>	[SCFM]
Max. Est. Removal Rate:		
(lower estimate) - per well	<input type="text" value="999.49"/>	[lb/d]
(upper estimate) - per well	<input type="text" value="2969.17"/>	[lb/d]

① → Import Data ←

FIRST PRESSTHE IMPORT DATA
BOTTOM!

These are the results for the contaminant
type that you have specified. All of this

Saturated Vapor
Concentration at time=0

.4096E+03

[mg/L]

Min Volume to Remove
>90% of Initial Residual

12.95

[L-air/g-resi
dual]

Temperature (°C):

20

Contaminant Type:

User Defined

Qt/M(0) L-air/ g-residual	Vapor Conc. [% Initial]	Residual Level [% Initial]	BP #1 Residual [% total]	BP #2 Residual [% total]	BP #3 Residual [% total]	BP #4 Residual [% total]	BP #5 Residual [% total]
8.69	11.93	28.10	.00	.00	1.07	7.51	91.41
9.71	11.50	23.10	.00	.00	.38	6.31	93.31
10.77	11.25	18.10	.00	.00	.05	5.22	94.73
11.86	11.16	13.10	.00	.00	.00	4.24	95.76
12.95	11.17	8.10	.00	.00	.00	3.25	96.75
14.05	11.21	3.10	.00	.00	.00	1.27	98.73
14.08	11.21	2.94	.00	.00	.00	1.25	98.75
14.11	11.21	2.80	.00	.00	.00	1.22	98.78

17

Print Card

Is Venting Appropriate?

This is a complete summary of the data and results. Based upon these numbers, a "minimum number of wells" has been calculated, which should give you some indication of how appropriate venting is for your application. Note that this is the number of wells if circumstances are ideal which they rarely are.

The next card discusses some of the conditions that may limit the effectiveness

Temperature (°C):

20

Contaminant Type:

User Defined

Soil Type:

User Defined

Well Radius (m):

2

Est. Radius of Influence (ft):

30

Permeable Zone Thickness (ft):

10

Flowrate per Well (120" Vac) (SCFM)

19.11

Flowrate per Well (120" Vac) (SCFM)

56.77

Min. Vol. of Air (L/g-residual):

12.95

Estimated Spill Mass:

1800000

lb

Desired Remediation Time (days):


3650

0.88


Minimum # of Wells Based
on Your Input Parameters

2.61

18




ACS OFF SITE



1.75 darcy

ACS OFF SITE



Ascoff.out

```
+ + + + +  
+  
+ BiosVE For Window  
+  
+ SOIL VACUUM EXTRACTION CHEMICAL EQUILIBRIUM MODEL  
+ BASED ON JOHNSON ET AL. (1990) GROUND WATER  
+  
+  
+  
+  
+  
+  
+ COPYRIGHT 1995  
+ ASHOK KATYAL, Ph.D.  
+ DRAPER ADEN ENVIRONMENTAL MODELING  
+ BLACKSBURG, VA 24060, U.S.A.  
+  
+ + + + +
```

TITLE: ACS OFF SITE

— — — — —

```

air flow rate      (liters/day)      = .7788E+06
total mass of contaminant (g)        = .2916E+08
maximum simulation time (days)       = .5475E+04
starting time step (days)           = .5000E+00
maximum time step (days)            = .5000E+01
time increment factor                 = .1020E+01
printout time interval (days)       = .3650E+03
volumetric water content (fraction)   = .1500E+00
bulk density (g/cm^3)                = .1700E+01
foc                                   = .5000E-02
contaminated soil vol. (m^3)         = .6380E+02
temperature (C)                      = .2000E+02
intercept in free prod. recov. eqn. = .1500E+01
exponent in free prod. recov. eqn.  = .2000E-01
bio efficiency (fraction)             = .2000E-01
residual oil mass (kg)               = .2915E+04
venting efficiency (fraction)         = .7100E-01

```

SPECIES	VAP PRES atm	BOILING POINT deg C	SOL LIMIT ppm	KOW g/g
benzene	.1000E+00	.8000E+02	.1780E+04	.1350E+03
toluene	.2900E-01	.1110E+03	.5150E+03	.4900E+03

	Ascoff.out			
p-xylene	.8600E-02	.1380E+03	.1980E+03	.1413E+04
111-trichloroethane	.1620E-01	.7410E+02	.1500E+04	.3160E+03
1122-tetrachloroethane	.7000E-02	.1462E+03	.2900E+04	.2450E+03
112-trichloroethane	.4000E-01	.1138E+03	.4500E+04	.2950E+03
11-dichoroethane	.2400E+00	.5750E+02	.5500E+04	.6170E+02
11-dichoroethene	.7900E+00	.3700E+02	.2250E+04	.6920E+02
methylenechloride	.4760E+00	.9370E+02	.2000E+04	.2000E+02
tetrachloroethene	.2400E-02	.1210E+03	.1500E+03	.3980E+03
trichloroethene	.7600E-01	.8720E+02	.1100E+04	.2400E+03
vinylacetate	.1500E+00	.7200E+02	.2000E+04	.5000E+00
vinylchloride	.3500E+01	.1340E+02	.2670E+04	.2400E+02
Ethylbenzene	.9200E-01	.1362E+03	.1520E+03	.1410E+04
MASS FRACTION SUM	1.000000			

SPECIES	MOL WEIGHT g/mol	HENRY COEFF DIMENSIONLESS
benzene	.7810E+02	.0000E+00
toluene	.9210E+02	.0000E+00
p-xylene	.1062E+03	.0000E+00
111-trichloroethane	.1335E+03	.0000E+00
1122-tetrachloroethane	.1678E+03	.0000E+00
112-trichloroethane	.1334E+03	.0000E+00
11-dichoroethane	.1820E+03	.0000E+00
11-dichoroethene	.9694E+02	.0000E+00
methylenechloride	.1067E+03	.0000E+00
tetrachloroethene	.1658E+03	.0000E+00
trichloroethene	.1314E+03	.0000E+00
vinylacetate	.8600E+02	.0000E+00
vinylchloride	.6250E+02	.0000E+00
Ethylbenzene	.1067E+03	.0000E+00
sgmlti	250509.200000	

RESULTS AT TIME (DAYS) 0.000000E+00

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1326E+03	.3480E+06	.3042E+03	.1466E+04
toluene	.9595E+03	.8682E+07	.1862E+04	.3258E+05
p-xylene	.1019E+03	.3108E+07	.2223E+03	.1121E+05
111-trichloroethane	.9489E+02	.1537E+07	.6625E+03	.7473E+04
1122-tetrachloroethane	.2612E+03	.9791E+07	.6490E+04	.5676E+05
112-trichloroethane	.5254E+02	.3447E+06	.4460E+03	.4697E+04
11-dichoroethane	.3185E+03	.3483E+06	.4037E+03	.8892E+03

	Ascoff.out			
11-dichoroethene	.1047E+04	.3478E+06	.3096E+03	.7649E+03
methylenchloride	.1265E+04	.6976E+06	.5016E+03	.3581E+03
tetrachloroethene	.8795E+01	.9616E+06	.3337E+02	.4742E+03
trichloroethene	.1683E+03	.5812E+06	.1866E+03	.1599E+04
vinylacetate	.3495E+03	.6114E+06	.5454E+03	.9735E+01
vinylchloride	.7974E+04	.5979E+06	.3429E+04	.2938E+04
Ethylbenzene	.3668E+03	.1046E+07	.5718E+02	.2878E+04

TOTAL MASS IN ALL PHASE = .2916E+05

TOTAL MASS IN GAS PHASE (kg)	= .1310E+02
TOTAL MASS IN FREE PHASE (kg)	= .2900E+05
TOTAL MASS IN WATER PHASE (kg)	= .1545E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1241E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.3499E+06	.0000E+00	.0000E+00	.3226E+04
toluene	.8718E+07	.0000E+00	.0000E+00	.8038E+05
p-xylene	.3120E+07	.0000E+00	.0000E+00	.2876E+05
111-trichloroethane	.1545E+07	.0000E+00	.0000E+00	.1425E+05
1122-tetrachloroethane	.9855E+07	.0000E+00	.0000E+00	.9086E+05
112-trichloroethane	.3499E+06	.0000E+00	.0000E+00	.3226E+04
11-dichoroethane	.3499E+06	.0000E+00	.0000E+00	.3226E+04
11-dichoroethene	.3499E+06	.6078E-04	.8561E-03	.3226E+04
methylenchloride	.6997E+06	.1338E-03	.1885E-02	.6452E+04
tetrachloroethene	.9621E+06	.0000E+00	.0000E+00	.8871E+04
trichloroethene	.5831E+06	.0000E+00	.0000E+00	.5376E+04
vinylacetate	.6123E+06	.0000E+00	.0000E+00	.5645E+04
vinylchloride	.6123E+06	.4702E-03	.6623E-02	.5645E+04
Ethylbenzene	.1050E+07	.0000E+00	.0000E+00	.9677E+04
end of initial conditions				

RESULTS AT TIME (DAYS)

368.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1088E+03	.2378E+06	.2497E+03	.1203E+04
toluene	.1030E+04	.7762E+07	.2000E+04	.3498E+05

	Ascoff.out			
p-xylene	.1182E+03	.3002E+07	.2579E+03	.1301E+05
111-trichloroethane	.1069E+03	.1442E+07	.7465E+03	.8422E+04
1122-tetrachloroethane	.3047E+03	.9511E+07	.7571E+04	.6622E+05
112-trichloroethane	.5409E+02	.2955E+06	.4592E+03	.4836E+04
11-dichloroethane	.1538E+03	.1400E+06	.1949E+03	.4293E+03
11-dichloroethene	.6306E+02	.1744E+05	.1865E+02	.4607E+02
methylenechloride	.2490E+03	.1143E+06	.9869E+02	.7047E+02
tetrachloroethene	.1045E+02	.9516E+06	.3966E+02	.5635E+03
trichloroethene	.1512E+03	.4348E+06	.1677E+03	.1437E+04
vinylacetate	.2369E+03	.3451E+06	.3698E+03	.6601E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3102E+03	.7366E+06	.4834E+02	.2433E+04

TOTAL MASS IN ALL PHASE = .2514E+05

TOTAL MASS IN GAS PHASE (kg)	= .2897E+01
TOTAL MASS IN FREE PHASE (kg)	= .2499E+05
TOTAL MASS IN WATER PHASE (kg)	= .1222E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1337E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.2393E+06	.3395E+00	.4781E+01	.2207E+04
toluene	.7800E+07	.3201E+01	.4509E+02	.7192E+05
p-xylene	.3016E+07	.3668E+00	.5166E+01	.2780E+05
111-trichloroethane	.1452E+07	.3320E+00	.4676E+01	.1338E+05
1122-tetrachloroethane	.9585E+07	.9455E+00	.1332E+02	.8837E+05
112-trichloroethane	.3008E+06	.1682E+00	.2369E+01	.2774E+04
11-dichloroethane	.1408E+06	.4834E+00	.6808E+01	.1298E+04
11-dichloroethene	.1757E+05	.2045E+00	.2881E+01	.1620E+03
methylenechloride	.1147E+06	.7932E+00	.1117E+02	.1058E+04
tetrachloroethene	.9522E+06	.3241E-01	.4565E+00	.8779E+04
trichloroethene	.4365E+06	.4711E+00	.6635E+01	.4025E+04
vinylacetate	.3458E+06	.7412E+00	.1044E+02	.3188E+04
vinylchloride	.1296E+02	.0000E+00	.0000E+00	.1194E+00
Ethylbenzene	.7394E+06	.9671E+00	.1362E+02	.6818E+04

RESULTS AT TIME (DAYS) 733.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID

Ascoff.out

benzene	.7939E+02	.1552E+06	.1821E+03	.8778E+03
toluene	.1016E+04	.6848E+07	.1972E+04	.3450E+05
p-xylene	.1271E+03	.2889E+07	.2774E+03	.1399E+05
111-trichloroethane	.1113E+03	.1343E+07	.7774E+03	.8770E+04
1122-tetrachloroethane	.3299E+03	.9211E+07	.8197E+04	.7170E+05
112-trichloroethane	.5095E+02	.2490E+06	.4325E+03	.4555E+04
11-dichloroethane	.6185E+02	.5037E+05	.7839E+02	.1727E+03
11-dichloroethene	.2466E+01	.6101E+03	.7293E+00	.1802E+01
methylenechloride	.3659E+02	.1502E+05	.1450E+02	.1036E+02
tetrachloroethene	.1155E+02	.9404E+06	.4382E+02	.6226E+03
trichloroethene	.1221E+03	.3140E+06	.1354E+03	.1160E+04
vinylacetate	.1394E+03	.1817E+06	.2176E+03	.3884E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.2339E+03	.4969E+06	.3646E+02	.1835E+04

TOTAL MASS IN ALL PHASE = .2285E+05

TOTAL MASS IN GAS PHASE (kg)	= .2323E+01
TOTAL MASS IN FREE PHASE (kg)	= .2269E+05
TOTAL MASS IN WATER PHASE (kg)	= .1237E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1382E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.1563E+06	.2461E+00	.3467E+01	.1441E+04
toluene	.6885E+07	.3150E+01	.4436E+02	.6348E+05
p-xylene	.2903E+07	.3941E+00	.5550E+01	.2677E+05
111-trichloroethane	.1353E+07	.3452E+00	.4862E+01	.1248E+05
1122-tetrachloroethane	.9292E+07	.1023E+01	.1441E+02	.8567E+05
112-trichloroethane	.2540E+06	.1580E+00	.2225E+01	.2342E+04
11-dichloroethane	.5069E+05	.1917E+00	.2700E+01	.4673E+03
11-dichloroethene	.6152E+03	.7625E-02	.1074E+00	.5672E+01
methylenechloride	.1509E+05	.1133E+00	.1596E+01	.1391E+03
tetrachloroethene	.9411E+06	.3580E-01	.5043E+00	.8677E+04
trichloroethene	.3154E+06	.3785E+00	.5331E+01	.2908E+04
vinylacetate	.1820E+06	.4322E+00	.6087E+01	.1678E+04
vinylchloride	.1043E+02	.0000E+00	.0000E+00	.9612E-01
Ethylbenzene	.4990E+06	.7252E+00	.1021E+02	.4601E+04

RESULTS AT TIME (DAYS) 1098.606000

Ascoff.out

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.5475E+02	.9652E+05	.1256E+03	.6054E+03
toluene	.9800E+03	.5957E+07	.1902E+04	.3327E+05
p-xylene	.1350E+03	.2768E+07	.2947E+03	.1486E+05
111-trichloroethane	.1141E+03	.1242E+07	.7966E+03	.8987E+04
1122-tetrachloroethane	.3530E+03	.8890E+07	.8772E+04	.7672E+05
112-trichloroethane	.4671E+02	.2059E+06	.3965E+03	.4176E+04
11-dichloroethane	.2196E+02	.1613E+05	.2783E+02	.6130E+02
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.4202E+01	.1556E+04	.1666E+01	.1189E+01
tetrachloroethene	.1264E+02	.9283E+06	.4795E+02	.6814E+03
trichloroethene	.9426E+02	.2186E+06	.1045E+03	.8954E+03
vinylacetate	.7564E+02	.8890E+05	.1181E+03	.2107E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.1674E+03	.3207E+06	.2609E+02	.1313E+04

TOTAL MASS IN ALL PHASE = .2089E+05

TOTAL MASS IN GAS PHASE (kg)	= .2060E+01
TOTAL MASS IN FREE PHASE (kg)	= .2073E+05
TOTAL MASS IN WATER PHASE (kg)	= .1261E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1416E+03

SPECIES	MASS	CONC		
		WELL GAS	SOIL GAS	SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.9731E+05	.1710E+00	.2408E+01	.8972E+03
toluene	.5993E+07	.3045E+01	.4289E+02	.5526E+05
p-xylene	.2783E+07	.4190E+00	.5901E+01	.2566E+05
111-trichloroethane	.1252E+07	.3542E+00	.4989E+01	.1154E+05
1122-tetrachloroethane	.8976E+07	.1095E+01	.1543E+02	.8276E+05
112-trichloroethane	.2105E+06	.1452E+00	.2046E+01	.1941E+04
11-dichloroethane	.1624E+05	.6922E-01	.9749E+00	.1497E+03
11-dichloroethene	.1599E+02	.0000E+00	.0000E+00	.1474E+00
methylenechloride	.1563E+04	.1347E-01	.1897E+00	.1442E+02
tetrachloroethene	.9290E+06	.3919E-01	.5520E+00	.8565E+04
trichloroethene	.2197E+06	.2938E+00	.4138E+01	.2026E+04
vinylacetate	.8909E+05	.2370E+00	.3338E+01	.8214E+03
vinylchloride	.1041E+02	.0000E+00	.0000E+00	.9598E-01

Ascoff.out

Ethylbenzene .3222E+06 .5223E+00 .7356E+01 .2971E+04

RESULTS AT TIME (DAYS) 1463.606000

Handwritten: 4.85

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.3594E+02	.5703E+05	.8244E+02	.3973E+03
toluene	.9328E+03	.5105E+07	.1811E+04	.3167E+05
p-xylene	.1430E+03	.2640E+07	.3122E+03	.1575E+05
111-trichloroethane	.1161E+03	.1138E+07	.8109E+03	.9148E+04
1122-tetrachloroethane	.3770E+03	.8547E+07	.9368E+04	.8194E+05
112-trichloroethane	.4205E+02	.1668E+06	.3569E+03	.3759E+04
11-dichloroethane	.6899E+01	.4562E+04	.8744E+01	.1926E+02
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.3776E+00	.1259E+03	.1497E+00	.1069E+00
tetrachloroethene	.1384E+02	.9149E+06	.5251E+02	.7460E+03
trichloroethene	.7008E+02	.1463E+06	.7771E+02	.6658E+03
vinylacetate	.3803E+02	.4023E+05	.5935E+02	.1059E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.1144E+03	.1973E+06	.1783E+02	.8975E+03

TOTAL MASS IN ALL PHASE = .1912E+05

TOTAL MASS IN GAS PHASE (kg)	= .1891E+01
TOTAL MASS IN FREE PHASE (kg)	= .1896E+05
TOTAL MASS IN WATER PHASE (kg)	= .1296E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1450E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	
S				SOIL MAS
g	g	g/m3	g/m3	mg/k
benzene	.5754E+05	.1114E+00	.1569E+01	.5306E+03
toluene	.5139E+07	.2892E+01	.4073E+02	.4738E+05
p-xylene	.2656E+07	.4435E+00	.6246E+01	.2449E+05
111-trichloroethane	.1148E+07	.3601E+00	.5072E+01	.1058E+05
1122-tetrachloroethane	.8639E+07	.1169E+01	.1646E+02	.7965E+05
112-trichloroethane	.1710E+06	.1303E+00	.1836E+01	.1576E+04
11-dichloroethane	.4597E+04	.2138E-01	.3011E+00	.4238E+02
11-dichloroethene	.1420E+02	.0000E+00	.0000E+00	.1309E+00
methylenechloride	.1265E+03	.1169E-02	.1646E-01	.1167E+01

	Ascoff.out			
tetrachloroethene	.9157E+06	.4289E-01	.6041E+00	.8443E+04
trichloroethene	.1472E+06	.2173E+00	.3060E+01	.1357E+04
vinylacetate	.4033E+05	.1179E+00	.1660E+01	.3718E+03
vinylchloride	.7881E+01	.0000E+00	.0000E+00	.7266E-01
Ethylbenzene	.1983E+06	.3546E+00	.4994E+01	.1829E+04

RESULTS AT TIME (DAYS) 1828.606000

S. JRS

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.2228E+02	.3181E+05	.5111E+02	.2463E+03
toluene	.8735E+03	.4301E+07	.1695E+04	.2966E+05
p-xylene	.1508E+03	.2504E+07	.3292E+03	.1660E+05
111-trichloroethane	.1172E+03	.1033E+07	.8180E+03	.9228E+04
1122-tetrachloroethane	.4012E+03	.8183E+07	.9968E+04	.8719E+05
112-trichloroethane	.3702E+02	.1321E+06	.3143E+03	.3310E+04
11-dichloroethane	.1890E+01	.1125E+04	.2396E+01	.5277E+01
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.1513E+02	.9004E+06	.5743E+02	.8160E+03
trichloroethene	.4989E+02	.9374E+05	.5532E+02	.4740E+03
vinylacetate	.1753E+02	.1669E+05	.2736E+02	.4884E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.7417E+02	.1151E+06	.1156E+02	.5819E+03

TOTAL MASS IN ALL PHASE = .1747E+05

TOTAL MASS IN GAS PHASE (kg)	= .1761E+01
TOTAL MASS IN FREE PHASE (kg)	= .1731E+05
TOTAL MASS IN WATER PHASE (kg)	= .1333E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1481E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.3213E+05	.6907E-01	.9728E+00	.2962E+03
toluene	.4333E+07	.2708E+01	.3814E+02	.3995E+05
p-xylene	.2521E+07	.4676E+00	.6586E+01	.2325E+05
111-trichloroethane	.1043E+07	.3633E+00	.5117E+01	.9615E+04
1122-tetrachloroethane	.8280E+07	.1244E+01	.1752E+02	.7634E+05

	Ascoff.out			
112-trichloroethane	.1358E+06	.1148E+00	.1616E+01	.1252E+04
11-dichloroethane	.1134E+04	.5857E-02	.8250E-01	.1046E+02
11-dichloroethene	.1241E+02	.0000E+00	.0000E+00	.1144E+00
methylenechloride	.1410E+02	.0000E+00	.0000E+00	.1300E+00
tetrachloroethene	.9013E+06	.4693E-01	.6609E+00	.8310E+04
trichloroethene	.9432E+05	.1547E+00	.2179E+01	.8696E+03
vinylacetate	.1674E+05	.5435E-01	.7655E+00	.1543E+03
vinylchloride	.7867E+01	.0000E+00	.0000E+00	.7253E-01
Ethylbenzene	.1158E+06	.2299E+00	.3238E+01	.1067E+04

RESULTS AT TIME (DAYS) 2193.606000

U y/s

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1297E+02	.1663E+05	.2976E+02	.1434E+03
toluene	.8039E+03	.3554E+07	.1560E+04	.2730E+05
p-xylene	.1584E+03	.2362E+07	.3457E+03	.1744E+05
111-trichloroethane	.1172E+03	.9272E+06	.8179E+03	.9227E+04
1122-tetrachloroethane	.4256E+03	.7795E+07	.1058E+05	.9250E+05
112-trichloroethane	.3183E+02	.1020E+06	.2702E+03	.2846E+04
11-dichloroethane	.4448E+00	.2376E+03	.5638E+00	.1242E+01
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.1656E+02	.8845E+06	.6283E+02	.8927E+03
trichloroethene	.3386E+02	.5713E+05	.3755E+02	.3217E+03
vinylacetate	.7343E+01	.6277E+04	.1146E+02	.2046E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.4537E+02	.6323E+05	.7072E+01	.3560E+03

TOTAL MASS IN ALL PHASE = .1594E+05

TOTAL MASS IN GAS PHASE (kg)	= .1654E+01
TOTAL MASS IN FREE PHASE (kg)	= .1577E+05
TOTAL MASS IN WATER PHASE (kg)	= .1372E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1510E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.1682E+05	.4062E-01	.5721E+00	.1551E+03

	Ascoff.out			
toluene	.3584E+07	.2501E+01	.3523E+02	.3304E+05
p-xylene	.2380E+07	.4919E+00	.6928E+01	.2194E+05
111-trichloroethane	.9374E+06	.3640E+00	.5127E+01	.8643E+04
1122-tetrachloroethane	.7899E+07	.1321E+01	.1861E+02	.7283E+05
112-trichloroethane	.1052E+06	.9912E-01	.1396E+01	.9698E+03
11-dichloroethane	.2399E+03	.1412E-02	.1989E-01	.2212E+01
11-dichloroethene	.1150E+02	.0000E+00	.0000E+00	.1061E+00
methylenechloride	.1290E+02	.0000E+00	.0000E+00	.1189E+00
tetrachloroethene	.8855E+06	.5137E-01	.7236E+00	.8164E+04
trichloroethene	.5752E+05	.1058E+00	.1490E+01	.5303E+03
vinylacetate	.6296E+04	.2311E-01	.3255E+00	.5805E+02
vinylchloride	.5333E+01	.0000E+00	.0000E+00	.4917E-01
Ethylbenzene	.6364E+05	.1420E+00	.2000E+01	.5867E+03

RESULTS AT TIME (DAYS) 2558.606000

7 yrs

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.7049E+01	.8068E+04	.1617E+02	.7794E+02
toluene	.7280E+03	.2874E+07	.1413E+04	.2472E+05
p-xylene	.1662E+03	.2213E+07	.3628E+03	.1830E+05
111-trichloroethane	.1164E+03	.8222E+06	.8125E+03	.9166E+04
1122-tetrachloroethane	.4517E+03	.7385E+07	.1122E+05	.9816E+05
112-trichloroethane	.2674E+02	.7651E+05	.2270E+03	.2390E+04
11-dichloroethane	.8805E-01	.4199E+02	.1116E+00	.2458E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.1818E+02	.8671E+06	.6899E+02	.9803E+03
trichloroethene	.2183E+02	.3287E+05	.2420E+02	.2074E+03
vinylacetate	.2762E+01	.2107E+04	.4310E+01	.7693E-01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.2604E+02	.3240E+05	.4060E+01	.2043E+03

TOTAL MASS IN ALL PHASE = .1448E+05

TOTAL MASS IN GAS PHASE (kg)	= .1565E+01
TOTAL MASS IN FREE PHASE (kg)	= .1431E+05
TOTAL MASS IN WATER PHASE (kg)	= .1416E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1542E+03

SPECIES	MASS	CONC	CONC	CONC
		WELL GAS	SOIL GAS	SOIL MAS

S

g	Ascoff.out			
	g	g/m3	g/m3	mg/k
benzene	.8170E+04	.2185E-01	.3077E+00	.7532E+02
toluene	.2900E+07	.2257E+01	.3179E+02	.2674E+05
p-xylene	.2231E+07	.5154E+00	.7259E+01	.2057E+05
111-trichloroethane	.8323E+06	.3608E+00	.5081E+01	.7674E+04
1122-tetrachloroethane	.7495E+07	.1400E+01	.1972E+02	.6910E+05
112-trichloroethane	.7915E+05	.8288E-01	.1167E+01	.7298E+03
11-dichloroethane	.4244E+02	.2728E-03	.3842E-02	.3913E+00
11-dichloroethene	.9719E+01	.0000E+00	.0000E+00	.8961E-01
methylenechloride	.1112E+02	.0000E+00	.0000E+00	.1025E+00
tetrachloroethene	.8682E+06	.5639E-01	.7942E+00	.8005E+04
trichloroethene	.3313E+05	.6767E-01	.9530E+00	.3054E+03
vinylacetate	.2114E+04	.8559E-02	.1205E+00	.1949E+02
vinylchloride	.5321E+01	.0000E+00	.0000E+00	.4906E-01
Ethylbenzene	.3264E+05	.8073E-01	.1137E+01	.3009E+03

RESULTS AT TIME (DAYS) 2923.606000

8 up

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.3522E+01	.3587E+04	.8080E+01	.3894E+02
toluene	.6447E+03	.2264E+07	.1251E+04	.2189E+05
p-xylene	.1736E+03	.2056E+07	.3789E+03	.1911E+05
111-trichloroethane	.1143E+03	.7186E+06	.7980E+03	.9003E+04
1122-tetrachloroethane	.4777E+03	.6951E+07	.1187E+05	.1038E+06
112-trichloroethane	.2177E+02	.5544E+05	.1848E+03	.1947E+04
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.1999E+02	.8481E+06	.7584E+02	.1078E+04
trichloroethene	.1320E+02	.1769E+05	.1464E+02	.1254E+03
vinylacetate	.9122E+00	.6194E+03	.1424E+01	.2541E-01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.1383E+02	.1531E+05	.2156E+01	.1085E+03

TOTAL MASS IN ALL PHASE = .1310E+05

TOTAL MASS IN GAS PHASE (kg)	= .1484E+01
TOTAL MASS IN FREE PHASE (kg)	= .1293E+05
TOTAL MASS IN WATER PHASE (kg)	= .1459E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1571E+03

Ascoff.out

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.3638E+04	.1106E-01	.1557E+00	.3354E+02
toluene	.2288E+07	.2007E+01	.2827E+02	.2109E+05
p-xylene	.2076E+07	.5392E+00	.7595E+01	.1914E+05
111-trichloroethane	.7285E+06	.3553E+00	.5004E+01	.6717E+04
1122-tetrachloroethane	.7067E+07	.1483E+01	.2089E+02	.6516E+05
112-trichloroethane	.5760E+05	.6787E-01	.9559E+00	.5311E+03
11-dichloroethane	.1759E+02	.0000E+00	.0000E+00	.1621E+00
11-dichloroethene	.8814E+01	.0000E+00	.0000E+00	.8127E-01
methylenechloride	.9928E+01	.0000E+00	.0000E+00	.9154E-01
tetrachloroethene	.8493E+06	.6200E-01	.8732E+00	.7830E+04
trichloroethene	.1785E+05	.4133E-01	.5821E+00	.1646E+03
vinylacetate	.6218E+03	.2881E-02	.4058E-01	.5733E+01
vinylchloride	.5308E+01	.0000E+00	.0000E+00	.4894E-01
Ethylbenzene	.1544E+05	.4338E-01	.6110E+00	.1423E+03

RESULTS AT TIME (DAYS) 3288.606000

9 yrs

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1602E+01	.1440E+04	.3674E+01	.1771E+02
toluene	.5583E+03	.1731E+07	.1084E+04	.1896E+05
p-xylene	.1811E+03	.1893E+07	.3953E+03	.1994E+05
111-trichloroethane	.1113E+03	.6174E+06	.7767E+03	.8763E+04
1122-tetrachloroethane	.5054E+03	.6492E+07	.1256E+05	.1099E+06
112-trichloroethane	.1718E+02	.3861E+05	.1458E+03	.1536E+04
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.2208E+02	.8271E+06	.8378E+02	.1190E+04
trichloroethene	.7441E+01	.8803E+04	.8251E+01	.7069E+02
vinylacetate	.2599E+00	.1558E+03	.4056E+00	.7240E-02
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.6733E+01	.6580E+04	.1050E+01	.5283E+02

TOTAL MASS IN ALL PHASE = .1179E+05

TOTAL MASS IN GAS PHASE (kg) = .1411E+01
 TOTAL MASS IN FREE PHASE (kg) = .1162E+05
 TOTAL MASS IN WATER PHASE (kg) = .1506E+02

Ascoff.out
TOTAL MASS IN SOIL PHASE (kg) = .1604E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.1463E+04	.4963E-02	.6990E-01	.1349E+02
toluene	.1751E+07	.1731E+01	.2437E+02	.1615E+05
p-xylene	.1914E+07	.5614E+00	.7907E+01	.1765E+05
111-trichloroethane	.6271E+06	.3448E+00	.4857E+01	.5782E+04
1122-tetrachloroethane	.6614E+07	.1567E+01	.2207E+02	.6098E+05
112-trichloroethane	.4031E+05	.5325E-01	.7500E+00	.3717E+03
11-dichoroethane	.1553E+02	.0000E+00	.0000E+00	.1432E+00
11-dichoroethene	.7911E+01	.0000E+00	.0000E+00	.7294E-01
methylenechloride	.8734E+01	.0000E+00	.0000E+00	.8053E-01
tetrachloroethene	.8284E+06	.6844E-01	.9640E+00	.7638E+04
trichloroethene	.8889E+04	.2306E-01	.3248E+00	.8196E+02
vinylacetate	.1564E+03	.8052E-03	.1134E-01	.1442E+01
vinylchloride	.5294E+01	.0000E+00	.0000E+00	.4881E-01
Ethylbenzene	.6641E+04	.2087E-01	.2939E+00	.6123E+02

RESULTS AT TIME (DAYS) 3653.606000

10yrs

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.6502E+00	.5128E+03	.1492E+01	.7189E+01
toluene	.4694E+03	.1277E+07	.9111E+03	.1594E+05
p-xylene	.1880E+03	.1724E+07	.4103E+03	.2070E+05
111-trichloroethane	.1068E+03	.5198E+06	.7455E+03	.8410E+04
1122-tetrachloroethane	.5332E+03	.6007E+07	.1325E+05	.1159E+06
112-trichloroethane	.1301E+02	.2566E+05	.1105E+03	.1164E+04
11-dichoroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichoroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.2447E+02	.8040E+06	.9284E+02	.1319E+04
trichloroethene	.3847E+01	.3992E+04	.4266E+01	.3655E+02
vinylacetate	.6216E-01	.3268E+02	.9701E-01	.1732E-02
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.2950E+01	.2529E+04	.4598E+00	.2314E+02

TOTAL MASS IN ALL PHASE = .1055E+05

Ascoff.out

TOTAL MASS IN GAS PHASE (kg) = .1342E+01
 TOTAL MASS IN FREE PHASE (kg) = .1036E+05
 TOTAL MASS IN WATER PHASE (kg) = .1553E+02
 TOTAL MASS IN SOIL PHASE (kg) = .1635E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.5222E+03	.2015E-02	.2838E-01	.4814E+01
toluene	.1294E+07	.1455E+01	.2050E+02	.1193E+05
p-xylene	.1745E+07	.5829E+00	.8209E+01	.1609E+05
111-trichloroethane	.5291E+06	.3310E+00	.4662E+01	.4878E+04
1122-tetrachloroethane	.6137E+07	.1653E+01	.2328E+02	.5658E+05
112-trichloroethane	.2695E+05	.4034E-01	.5682E+00	.2485E+03
11-dichoroethane	.1348E+02	.0000E+00	.0000E+00	.1243E+00
11-dichoroethene	.7008E+01	.0000E+00	.0000E+00	.6462E-01
methylenechloride	.7537E+01	.0000E+00	.0000E+00	.6949E-01
tetrachloroethene	.8054E+06	.7585E-01	.1068E+01	.7426E+04
trichloroethene	.4037E+04	.1193E-01	.1680E+00	.3722E+02
vinylacetate	.3284E+02	.1926E-03	.2713E-02	.3028E+00
vinylchloride	.2771E+01	.0000E+00	.0000E+00	.2554E-01
Ethylbenzene	.2555E+04	.9143E-02	.1288E+00	.2356E+02

RESULTS AT TIME (DAYS) 4018.606000

11 yrs

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.2311E+00	.1587E+03	.5303E+00	.2556E+01
toluene	.3810E+03	.9018E+06	.7396E+03	.1294E+05
p-xylene	.1941E+03	.1549E+07	.4236E+03	.2137E+05
111-trichloroethane	.1008E+03	.4271E+06	.7038E+03	.7940E+04
1122-tetrachloroethane	.5607E+03	.5498E+07	.1393E+05	.1219E+06
112-trichloroethane	.9400E+01	.1613E+05	.7979E+02	.8404E+03
11-dichoroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichoroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.2721E+02	.7783E+06	.1033E+03	.1467E+04
trichloroethene	.1797E+01	.1623E+04	.1992E+01	.1707E+02
vinylacetate	.1249E-01	.5714E+01	.1949E-01	.3479E-03
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00

Ascoff.out

Ethylbenzene	.1142E+01	.8518E+03	.1780E+00	.8958E+01
--------------	-----------	-----------	-----------	-----------

TOTAL MASS IN ALL PHASE = .9357E+04

TOTAL MASS IN GAS PHASE (kg)	= .1276E+01
TOTAL MASS IN FREE PHASE (kg)	= .9174E+04
TOTAL MASS IN WATER PHASE (kg)	= .1599E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1664E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S				
	g	g/m3	g/m3	mg/k
benzene	.1620E+03	.7162E-03	.1009E-01	.1494E+01
toluene	.9159E+06	.1181E+01	.1664E+02	.8445E+04
p-xylene	.1571E+07	.6018E+00	.8476E+01	.1449E+05
111-trichloroethane	.4359E+06	.3125E+00	.4401E+01	.4019E+04
1122-tetrachloroethane	.5634E+07	.1738E+01	.2448E+02	.5195E+05
112-trichloroethane	.1706E+05	.2913E-01	.4103E+00	.1573E+03
11-dichloroethane	.1142E+02	.1293E-03	.1821E-02	.1053E+00
11-dichloroethene	.6106E+01	.0000E+00	.0000E+00	.5630E-01
methylenechloride	.6927E+01	.0000E+00	.0000E+00	.6387E-01
tetrachloroethene	.7799E+06	.8437E-01	.1188E+01	.7191E+04
trichloroethene	.1644E+04	.5569E-02	.7843E-01	.1515E+02
vinylacetate	.5731E+01	.0000E+00	.0000E+00	.5284E-01
vinylchloride	.2761E+01	.0000E+00	.0000E+00	.2546E-01
Ethylbenzene	.8621E+03	.3538E-02	.4983E-01	.7949E+01

RESULTS AT TIME (DAYS) 4383.606000

12 y3

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.6968E-01	.4124E+02	.1599E+00	.7704E+00
toluene	.2962E+03	.6045E+06	.5749E+03	.1006E+05
p-xylene	.1990E+03	.1370E+07	.4343E+03	.2191E+05
111-trichloroethane	.9325E+02	.3407E+06	.6510E+03	.7344E+04
1122-tetrachloroethane	.5872E+03	.4965E+07	.1459E+05	.1276E+06
112-trichloroethane	.6405E+01	.9478E+04	.5438E+02	.5727E+03
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00

	Ascoff.out			
tetrachloroethene	.3040E+02	.7498E+06	.1154E+03	.1639E+04
trichloroethene	.7397E+00	.5760E+03	.8201E+00	.7027E+01
vinylacetate	.1255E-01	.4952E+01	.1959E-01	.3496E-03
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3788E+00	.2437E+03	.5904E-01	.2972E+01

TOTAL MASS IN ALL PHASE = .8227E+04

TOTAL MASS IN GAS PHASE (kg)	= .1214E+01
TOTAL MASS IN FREE PHASE (kg)	= .8040E+04
TOTAL MASS IN WATER PHASE (kg)	= .1642E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1692E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.4225E+02	.2158E-03	.3040E-02	.3895E+00
toluene	.6154E+06	.9181E+00	.1293E+02	.5674E+04
p-xylene	.1392E+07	.6169E+00	.8688E+01	.1283E+05
111-trichloroethane	.3488E+06	.2891E+00	.4071E+01	.3216E+04
1122-tetrachloroethane	.5108E+07	.1820E+01	.2564E+02	.4709E+05
112-trichloroethane	.1011E+05	.1985E-01	.2796E+00	.9323E+02
11-dichloroethane	.9875E+01	.0000E+00	.0000E+00	.9105E-01
11-dichloroethene	.5202E+01	.0000E+00	.0000E+00	.4796E-01
methylenechloride	.5732E+01	.0000E+00	.0000E+00	.5285E-01
tetrachloroethene	.7516E+06	.9425E-01	.1327E+01	.6929E+04
trichloroethene	.5846E+03	.2292E-02	.3228E-01	.5390E+01
vinylacetate	.4968E+01	.0000E+00	.0000E+00	.4580E-01
vinylchloride	.2751E+01	.0000E+00	.0000E+00	.2536E-01
Ethylbenzene	.2471E+03	.1174E-02	.1653E-01	.2278E+01

RESULTS AT TIME (DAYS) 4748.606000

13 yrs

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1712E-01	.8637E+01	.3928E-01	.1893E+00
toluene	.2182E+03	.3796E+06	.4236E+03	.7409E+04
p-xylene	.2022E+03	.1186E+07	.4413E+03	.2226E+05
111-trichloroethane	.8410E+02	.2619E+06	.5872E+03	.6624E+04
1122-tetrachloroethane	.6117E+03	.4409E+07	.1520E+05	.1330E+06

	Ascoff.out			
112-trichloroethane	.4065E+01	.5126E+04	.3451E+02	.3634E+03
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.4834E-01	.5123E+01	.1916E-01	.1368E-01
tetrachloroethene	.3415E+02	.7179E+06	.1296E+03	.1841E+04
trichloroethene	.2604E+00	.1728E+03	.2887E+00	.2473E+01
vinylacetate	.1246E-01	.4189E+01	.1944E-01	.3470E-03
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.1038E+00	.5692E+02	.1618E-01	.8144E+00

TOTAL MASS IN ALL PHASE = .7149E+04

TOTAL MASS IN GAS PHASE (kg)	= .1155E+01
TOTAL MASS IN FREE PHASE (kg)	= .6960E+04
TOTAL MASS IN WATER PHASE (kg)	= .1682E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1715E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
	g	g/m3	g/m3	mg/k
benzene	.8885E+01	.5302E-04	.7468E-03	.8192E-01
toluene	.3877E+06	.6763E+00	.9526E+01	.3575E+04
p-xylene	.1209E+07	.6268E+00	.8829E+01	.1115E+05
111-trichloroethane	.2692E+06	.2607E+00	.3671E+01	.2482E+04
1122-tetrachloroethane	.4557E+07	.1896E+01	.2671E+02	.4202E+05
112-trichloroethane	.5529E+04	.1259E-01	.1774E+00	.5098E+02
11-dichloroethane	.8324E+01	.0000E+00	.0000E+00	.7675E-01
11-dichloroethene	.4299E+01	.0000E+00	.0000E+00	.3964E-01
methylenechloride	.5123E+01	.0000E+00	.0000E+00	.4723E-01
tetrachloroethene	.7199E+06	.1058E+00	.1491E+01	.6637E+04
trichloroethene	.1759E+03	.8066E-03	.1136E-01	.1622E+01
vinylacetate	.4205E+01	.0000E+00	.0000E+00	.3877E-01
vinylchloride	.2739E+01	.0000E+00	.0000E+00	.2525E-01
Ethylbenzene	.5786E+02	.3215E-03	.4528E-02	.5335E+00

RESULTS AT TIME (DAYS) 5113.606000

14 yrs

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.7619E-02	.3229E+01	.1748E-01	.8424E-01

	Ascoff.out			
toluene	.1502E+03	.2195E+06	.2916E+03	.5101E+04
p-xylene	.2033E+03	.1002E+07	.4436E+03	.2238E+05
111-trichloroethane	.7347E+02	.1922E+06	.5129E+03	.5786E+04
1122-tetrachloroethane	.6331E+03	.3833E+07	.1573E+05	.1376E+06
112-trichloroethane	.2361E+01	.2501E+04	.2004E+02	.2110E+03
11-dichoroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichoroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.3862E+02	.6820E+06	.1466E+03	.2082E+04
trichloroethene	.7521E-01	.4194E+02	.8339E-01	.7145E+00
vinylacetate	.1266E-01	.3575E+01	.1975E-01	.3526E-03
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.2234E-01	.1029E+02	.3482E-02	.1753E+00

TOTAL MASS IN ALL PHASE = .6122E+04

TOTAL MASS IN GAS PHASE (kg)	= .1101E+01
TOTAL MASS IN FREE PHASE (kg)	= .5931E+04
TOTAL MASS IN WATER PHASE (kg)	= .1715E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1732E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.3283E+01	.0000E+00	.0000E+00	.3027E-01
toluene	.2251E+06	.4655E+00	.6557E+01	.2075E+04
p-xylene	.1025E+07	.6300E+00	.8873E+01	.9447E+04
111-trichloroethane	.1985E+06	.2277E+00	.3206E+01	.1831E+04
1122-tetrachloroethane	.3987E+07	.1962E+01	.2764E+02	.3676E+05
112-trichloroethane	.2735E+04	.7311E-02	.1030E+00	.2522E+02
11-dichoroethane	.7281E+01	.0000E+00	.0000E+00	.6713E-01
11-dichoroethene	.3396E+01	.0000E+00	.0000E+00	.3131E-01
methylenechloride	.3929E+01	.0000E+00	.0000E+00	.3622E-01
tetrachloroethene	.6842E+06	.1197E+00	.1686E+01	.6309E+04
trichloroethene	.4282E+02	.2329E-03	.3281E-02	.3948E+00
vinylacetate	.3592E+01	.0000E+00	.0000E+00	.3312E-01
vinylchloride	.2079E+00	.0000E+00	.0000E+00	.1917E-02
Ethylbenzene	.1049E+02	.6916E-04	.9741E-03	.9674E-01

RESULTS AT TIME (DAYS) 5478.606000

1543

SPECIES

.....MASS (g) IN PHASES

	Ascoff.out GAS	OIL	WATER	SOLID
benzene	.7658E-02	.2672E+01	.1757E-01	.8468E-01
toluene	.9474E+02	.1140E+06	.1839E+03	.3217E+04
p-xylene	.2015E+03	.8176E+06	.4398E+03	.2218E+05
111-trichloroethane	.6161E+02	.1327E+06	.4301E+03	.4852E+04
1122-tetrachloroethane	.6501E+03	.3241E+07	.1615E+05	.1413E+06
112-trichloroethane	.1225E+01	.1069E+04	.1040E+02	.1095E+03
11-dichoroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichoroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.4410E+02	.6412E+06	.1674E+03	.2378E+04
trichloroethene	.1681E-01	.7719E+01	.1864E-01	.1597E+00
vinylacetate	.1273E-01	.2962E+01	.1987E-01	.3547E-03
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.9573E-02	.3631E+01	.1492E-02	.7511E-01

TOTAL MASS IN ALL PHASE = .5140E+04

TOTAL MASS IN GAS PHASE (kg) = .1053E+01
 TOTAL MASS IN FREE PHASE (kg) = .4947E+04
 TOTAL MASS IN WATER PHASE (kg) = .1739E+02
 TOTAL MASS IN SOIL PHASE (kg) = .1740E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
g				
benzene	.2726E+01	.0000E+00	.0000E+00	.2513E-01
toluene	.1175E+06	.2935E+00	.4134E+01	.1083E+04
p-xylene	.8404E+06	.6243E+00	.8794E+01	.7749E+04
111-trichloroethane	.1380E+06	.1909E+00	.2688E+01	.1273E+04
1122-tetrachloroethane	.3399E+07	.2014E+01	.2837E+02	.3133E+05
112-trichloroethane	.1190E+04	.3793E-02	.5342E-01	.1098E+02
11-dichoroethane	.5732E+01	.0000E+00	.0000E+00	.5285E-01
11-dichoroethene	.2497E+01	.0000E+00	.0000E+00	.2302E-01
methylenchloride	.3321E+01	.0000E+00	.0000E+00	.3062E-01
tetrachloroethene	.6438E+06	.1366E+00	.1925E+01	.5936E+04
trichloroethene	.7916E+01	.5204E-04	.7329E-03	.7298E-01
vinylacetate	.2978E+01	.0000E+00	.0000E+00	.2746E-01
vinylchloride	.2067E+00	.0000E+00	.0000E+00	.1906E-02
Ethylbenzene	.3674E+01	.0000E+00	.0000E+00	.3387E-01

RESULTS AT TIME (DAYS) 5478.606000

Ascoff.out

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.7658E-02	.2672E+01	.1757E-01	.8468E-01
toluene	.9474E+02	.1140E+06	.1839E+03	.3217E+04
p-xylene	.2015E+03	.8176E+06	.4398E+03	.2218E+05
111-trichloroethane	.6161E+02	.1327E+06	.4301E+03	.4852E+04
1122-tetrachloroethane	.6501E+03	.3241E+07	.1615E+05	.1413E+06
112-trichloroethane	.1225E+01	.1069E+04	.1040E+02	.1095E+03
11-dichoroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichoroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.4410E+02	.6412E+06	.1674E+03	.2378E+04
trichloroethene	.1681E-01	.7719E+01	.1864E-01	.1597E+00
vinylacetate	.1273E-01	.2962E+01	.1987E-01	.3547E-03
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.9573E-02	.3631E+01	.1492E-02	.7511E-01


TOTAL MASS IN ALL PHASE = .5140E+04

TOTAL MASS IN GAS PHASE (kg)	= .1053E+01
TOTAL MASS IN FREE PHASE (kg)	= .4947E+04
TOTAL MASS IN WATER PHASE (kg)	= .1739E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1740E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	
S				SOIL MAS
g	g	g/m3	g/m3	mg/k
benzene	.2726E+01	.0000E+00	.0000E+00	.2513E-01
toluene	.1175E+06	.2935E+00	.4134E+01	.1083E+04
p-xylene	.8404E+06	.6243E+00	.8794E+01	.7749E+04
111-trichloroethane	.1380E+06	.1909E+00	.2688E+01	.1273E+04
1122-tetrachloroethane	.3399E+07	.2014E+01	.2837E+02	.3133E+05
112-trichloroethane	.1190E+04	.3793E-02	.5342E-01	.1098E+02
11-dichoroethane	.5732E+01	.0000E+00	.0000E+00	.5285E-01
11-dichoroethene	.2497E+01	.0000E+00	.0000E+00	.2302E-01
methylenchloride	.3321E+01	.0000E+00	.0000E+00	.3062E-01
tetrachloroethene	.6438E+06	.1366E+00	.1925E+01	.5936E+04
trichloroethene	.7916E+01	.5204E-04	.7329E-03	.7298E-01
vinylacetate	.2978E+01	.0000E+00	.0000E+00	.2746E-01


	Ascoff.out			
vinylchloride	.2067E+00	.0000E+00	.0000E+00	.1906E-02
Ethylbenzene	.3674E+01	.0000E+00	.0000E+00	.3387E-01

ACS OFF SITE



5.2 darcy

ACS OFF SITE



Ascoff.out

```
+ + + + +  
+  
+ BiosVE For Window  
+  
+ SOIL VACUUM EXTRACTION CHEMICAL EQUILIBRIUM MODEL  
+ BASED ON JOHNSON ET AL. (1990) GROUND WATER  
+  
+  
+  
+  
+  
+  
+ COPYRIGHT 1995  
+ ASHOK KATYAL, Ph.D.  
+ DRAPER ADEN ENVIRONMENTAL MODELING  
+ BLACKSBURG, VA 24060, U.S.A.  
+  
+  
+ + + + +
```

TITLE: ACS OFF SITE

```

air flow rate      (liters/day)      = .2313E+07
total mass of contaminant (g)        = .2916E+08
maximum simulation time (days)       = .5475E+04
starting time step (days)           = .5000E+00
maximum time step (days)            = .5000E+01
time increment factor                  = .1020E+01
printout time interval (days)       = .3650E+03
volumetric water content(fraction)   = .1500E+00
bulk density (g/cm^3)                = .1700E+01
foc                                   = .5000E-02
contaminated soil vol. (m^3)         = .6380E+02
temperature (C)                      = .2000E+02
intercept in free prod.recov.eqn.    = .1500E+01
exponent in free prod. recov. eqn.   = .2000E-01
bio efficiency (fraction)             = .2000E-01
residual oil mass (kg)               = .2915E+04
venting efficiency (fraction)         = .7100E-01

```

SPECIES	VAP PRES atm	BOILING POINT deg C	SOL LIMIT ppm	KOW g/g
benzene	.1000E+00	.8000E+02	.1780E+04	.1350E+03
toluene	.2900E-01	.1110E+03	.5150E+03	.4900E+03

	Ascoff.out			
p-xylene	.8600E-02	.1380E+03	.1980E+03	.1413E+04
111-trichloroethane	.1620E-01	.7410E+02	.1500E+04	.3160E+03
1122-tetrachloroethane	.7000E-02	.1462E+03	.2900E+04	.2450E+03
112-trichloroethane	.4000E-01	.1138E+03	.4500E+04	.2950E+03
11-dichoroethane	.2400E+00	.5750E+02	.5500E+04	.6170E+02
11-dichoroethene	.7900E+00	.3700E+02	.2250E+04	.6920E+02
methylenechloride	.4760E+00	.9370E+02	.2000E+04	.2000E+02
tetrachloroethene	.2400E-02	.1210E+03	.1500E+03	.3980E+03
trichloroethene	.7600E-01	.8720E+02	.1100E+04	.2400E+03
vinylacetate	.1500E+00	.7200E+02	.2000E+04	.5000E+00
vinylchloride	.3500E+01	.1340E+02	.2670E+04	.2400E+02
Ethylbenzene	.9200E-01	.1362E+03	.1520E+03	.1410E+04
MASS FRACTION SUM	1.000000			

SPECIES	MOL WEIGHT g/mol	HENRY COEFF DIMENSIONLESS
benzene	.7810E+02	.0000E+00
toluene	.9210E+02	.0000E+00
p-xylene	.1062E+03	.0000E+00
111-trichloroethane	.1335E+03	.0000E+00
1122-tetrachloroethane	.1678E+03	.0000E+00
112-trichloroethane	.1334E+03	.0000E+00
11-dichoroethane	.1820E+03	.0000E+00
11-dichoroethene	.9694E+02	.0000E+00
methylenechloride	.1067E+03	.0000E+00
tetrachloroethene	.1658E+03	.0000E+00
trichloroethene	.1314E+03	.0000E+00
vinylacetate	.8600E+02	.0000E+00
vinylchloride	.6250E+02	.0000E+00
Ethylbenzene	.1067E+03	.0000E+00
sgmlti	250509.200000	

RESULTS AT TIME (DAYS) 0.000000E+00

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1326E+03	.3480E+06	.3042E+03	.1466E+04
toluene	.9595E+03	.8682E+07	.1862E+04	.3258E+05
p-xylene	.1019E+03	.3108E+07	.2223E+03	.1121E+05
111-trichloroethane	.9489E+02	.1537E+07	.6625E+03	.7473E+04
1122-tetrachloroethane	.2612E+03	.9791E+07	.6490E+04	.5676E+05
112-trichloroethane	.5254E+02	.3447E+06	.4460E+03	.4697E+04
11-dichoroethane	.3185E+03	.3483E+06	.4037E+03	.8892E+03

	Ascoff.out			
11-dichloroethene	.1047E+04	.3478E+06	.3096E+03	.7649E+03
methylenechloride	.1265E+04	.6976E+06	.5016E+03	.3581E+03
tetrachloroethene	.8795E+01	.9616E+06	.3337E+02	.4742E+03
trichloroethene	.1683E+03	.5812E+06	.1866E+03	.1599E+04
vinylacetate	.3495E+03	.6114E+06	.5454E+03	.9735E+01
vinylchloride	.7974E+04	.5979E+06	.3429E+04	.2938E+04
Ethylbenzene	.3668E+03	.1046E+07	.5718E+02	.2878E+04

TOTAL MASS IN ALL PHASE = .2916E+05

TOTAL MASS IN GAS PHASE (kg)	= .1310E+02
TOTAL MASS IN FREE PHASE (kg)	= .2900E+05
TOTAL MASS IN WATER PHASE (kg)	= .1545E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1241E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
g				
benzene	.3499E+06	.0000E+00	.0000E+00	.3226E+04
toluene	.8718E+07	.0000E+00	.0000E+00	.8038E+05
p-xylene	.3120E+07	.0000E+00	.0000E+00	.2876E+05
111-trichloroethane	.1545E+07	.0000E+00	.0000E+00	.1425E+05
1122-tetrachloroethane	.9855E+07	.0000E+00	.0000E+00	.9086E+05
112-trichloroethane	.3499E+06	.0000E+00	.0000E+00	.3226E+04
11-dichloroethane	.3499E+06	.1921E-04	.2705E-03	.3226E+04
11-dichloroethene	.3499E+06	.6138E-04	.8645E-03	.3226E+04
methylenechloride	.6997E+06	.9008E-04	.1269E-02	.6452E+04
tetrachloroethene	.9621E+06	.0000E+00	.0000E+00	.8871E+04
trichloroethene	.5831E+06	.0000E+00	.0000E+00	.5376E+04
vinylacetate	.6123E+06	.3630E-04	.5113E-03	.5645E+04
vinylchloride	.6123E+06	.4749E-03	.6688E-02	.5645E+04
Ethylbenzene	.1050E+07	.0000E+00	.0000E+00	.9677E+04

end of initial conditions

RESULTS AT TIME (DAYS) 368.606000

lyc ↓

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.5545E+02	.9794E+05	.1272E+03	.6131E+03
toluene	.9805E+03	.5972E+07	.1903E+04	.3329E+05

	Ascoff.out			
p-xylene	.1348E+03	.2770E+07	.2943E+03	.1484E+05
111-trichloroethane	.1140E+03	.1243E+07	.7960E+03	.8980E+04
1122-tetrachloroethane	.3525E+03	.8895E+07	.8759E+04	.7661E+05
112-trichloroethane	.4679E+02	.2066E+06	.3972E+03	.4183E+04
11-dichoroethane	.2341E+02	.1723E+05	.2967E+02	.6536E+02
11-dichoroethene	.1202E+00	.2688E+02	.3556E-01	.8785E-01
methylenechloride	.5323E+01	.1975E+04	.2110E+01	.1507E+01
tetrachloroethene	.1262E+02	.9284E+06	.4787E+02	.6802E+03
trichloroethene	.9496E+02	.2207E+06	.1053E+03	.9022E+03
vinylacetate	.7771E+02	.9151E+05	.1213E+03	.2165E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.1692E+03	.3248E+06	.2637E+02	.1327E+04

TOTAL MASS IN ALL PHASE = .2092E+05

TOTAL MASS IN GAS PHASE (kg)	= .2067E+01
TOTAL MASS IN FREE PHASE (kg)	= .2077E+05
TOTAL MASS IN WATER PHASE (kg)	= .1261E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1415E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
	g	g/m3	g/m3	mg/k
benzene	.9875E+05	.1716E+00	.2417E+01	.9104E+03
toluene	.6008E+07	.3036E+01	.4276E+02	.5539E+05
p-xylene	.2785E+07	.4176E+00	.5881E+01	.2568E+05
111-trichloroethane	.1253E+07	.3531E+00	.4973E+01	.1155E+05
1122-tetrachloroethane	.8980E+07	.1092E+01	.1537E+02	.8280E+05
112-trichloroethane	.2113E+06	.1449E+00	.2041E+01	.1948E+04
11-dichoroethane	.1735E+05	.7230E-01	.1018E+01	.1600E+03
11-dichoroethene	.2714E+02	.3610E-03	.5085E-02	.2502E+00
methylenechloride	.1985E+04	.1631E-01	.2298E+00	.1830E+02
tetrachloroethene	.9292E+06	.3906E-01	.5501E+00	.8567E+04
trichloroethene	.2218E+06	.2940E+00	.4141E+01	.2045E+04
vinylacetate	.9171E+05	.2404E+00	.3386E+01	.8456E+03
vinylchloride	.7730E+01	.0000E+00	.0000E+00	.7128E-01
Ethylbenzene	.3264E+06	.5237E+00	.7376E+01	.3009E+04

RESULTS AT TIME (DAYS) 733.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID

Ascoff.out

benzene	.1370E+02	.1765E+05	.3142E+02	.1514E+03
toluene	.8088E+03	.3594E+07	.1570E+04	.2746E+05
p-xylene	.1581E+03	.2369E+07	.3450E+03	.1740E+05
111-trichloroethane	.1172E+03	.9325E+06	.8184E+03	.9232E+04
1122-tetrachloroethane	.4244E+03	.7814E+07	.1055E+05	.9224E+05
112-trichloroethane	.3219E+02	.1037E+06	.2733E+03	.2878E+04
11-dichloroethane	.5666E+00	.3043E+03	.7181E+00	.1582E+01
11-dichloroethene	.7289E-01	.1189E+02	.2156E-01	.5326E-01
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.1649E+02	.8853E+06	.6256E+02	.8889E+03
trichloroethene	.3505E+02	.5945E+05	.3887E+02	.3330E+03
vinylacetate	.8182E+01	.7030E+04	.1277E+02	.2279E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.4758E+02	.6665E+05	.7416E+01	.3733E+03

TOTAL MASS IN ALL PHASE = .1602E+05

TOTAL MASS IN GAS PHASE (kg)	= .1662E+01
TOTAL MASS IN FREE PHASE (kg)	= .1585E+05
TOTAL MASS IN WATER PHASE (kg)	= .1371E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1510E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.1785E+05	.4247E-01	.5981E+00	.1646E+03
toluene	.3624E+07	.2508E+01	.3532E+02	.3341E+05
p-xylene	.2387E+07	.4901E+00	.6903E+01	.2201E+05
111-trichloroethane	.9427E+06	.3634E+00	.5118E+01	.8691E+04
1122-tetrachloroethane	.7917E+07	.1316E+01	.1853E+02	.7300E+05
112-trichloroethane	.1069E+06	.9980E-01	.1406E+01	.9856E+03
11-dichloroethane	.3072E+03	.1757E-02	.2475E-01	.2832E+01
11-dichloroethene	.1189E+02	.0000E+00	.0000E+00	.1096E+00
methylenechloride	.1196E+02	.0000E+00	.0000E+00	.1103E+00
tetrachloroethene	.8863E+06	.5111E-01	.7199E+00	.8172E+04
trichloroethene	.5985E+05	.1087E+00	.1531E+01	.5519E+03
vinylacetate	.7052E+04	.2537E-01	.3573E+00	.6501E+02
vinylchloride	.7688E+01	.0000E+00	.0000E+00	.7089E-01
Ethylbenzene	.6708E+05	.1475E+00	.2078E+01	.6185E+03

RESULTS AT TIME (DAYS) 1098.606000

3.45

Ascoff.out

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1819E+01	.1654E+04	.4174E+01	.2012E+02
toluene	.5670E+03	.1777E+07	.1100E+04	.1925E+05
p-xylene	.1804E+03	.1907E+07	.3937E+03	.1986E+05
111-trichloroethane	.1115E+03	.6259E+06	.7786E+03	.8784E+04
1122-tetrachloroethane	.5027E+03	.6529E+07	.1249E+05	.1093E+06
112-trichloroethane	.1765E+02	.4013E+05	.1499E+03	.1578E+04
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.2188E+02	.8289E+06	.8303E+02	.1180E+04
trichloroethene	.8079E+01	.9665E+04	.8958E+01	.7676E+02
vinylacetate	.3338E+00	.2023E+03	.5210E+00	.9300E-02
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.7532E+01	.7444E+04	.1174E+01	.5910E+02

TOTAL MASS IN ALL PHASE = .1190E+05

TOTAL MASS IN GAS PHASE (kg)	= .1419E+01
TOTAL MASS IN FREE PHASE (kg)	= .1173E+05
TOTAL MASS IN WATER PHASE (kg)	= .1501E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1601E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	
S				SOIL MAS
g	g	g/m3	g/m3	mg/k
benzene	.1680E+04	.5640E-02	.7944E-01	.1549E+02
toluene	.1798E+07	.1758E+01	.2475E+02	.1658E+05
p-xylene	.1927E+07	.5592E+00	.7876E+01	.1777E+05
111-trichloroethane	.6355E+06	.3457E+00	.4869E+01	.5860E+04
1122-tetrachloroethane	.6651E+07	.1558E+01	.2195E+02	.6132E+05
112-trichloroethane	.4187E+05	.5472E-01	.7707E+00	.3861E+03
11-dichloroethane	.1529E+02	.0000E+00	.0000E+00	.1410E+00
11-dichloroethene	.6593E+01	.0000E+00	.0000E+00	.6079E-01
methylenechloride	.8421E+01	.0000E+00	.0000E+00	.7764E-01
tetrachloroethene	.8302E+06	.6783E-01	.9554E+00	.7654E+04
trichloroethene	.9759E+04	.2505E-01	.3528E+00	.8998E+02
vinylacetate	.2032E+03	.1035E-02	.1458E-01	.1874E+01
vinylchloride	.1841E+00	.0000E+00	.0000E+00	.1698E-02

Ethylbenzene Ascoff.out
 .7512E+04 .2335E-01 .3289E+00 .6926E+02

RESULTS AT TIME (DAYS) 1463.606000

4 yrs

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.9018E-01	.5439E+02	.2069E+00	.9971E+00
toluene	.3074E+03	.6393E+06	.5966E+03	.1044E+05
p-xylene	.1983E+03	.1391E+07	.4327E+03	.2183E+05
111-trichloroethane	.9419E+02	.3507E+06	.6576E+03	.7419E+04
1122-tetrachloroethane	.5834E+03	.5027E+07	.1450E+05	.1268E+06
112-trichloroethane	.6802E+01	.1026E+05	.5775E+02	.6082E+03
11-dichoroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichoroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.2997E+02	.7532E+06	.1137E+03	.1616E+04
trichloroethene	.8776E+00	.6964E+03	.9731E+00	.8337E+01
vinylacetate	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.4764E+00	.3123E+03	.7425E-01	.3738E+01

TOTAL MASS IN ALL PHASE = .8358E+04

TOTAL MASS IN GAS PHASE (kg) = .1222E+01
 TOTAL MASS IN FREE PHASE (kg) = .8172E+04
 TOTAL MASS IN WATER PHASE (kg) = .1636E+02
 TOTAL MASS IN SOIL PHASE (kg) = .1687E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	
S				SOIL MAS
g	g	g/m3	g/m3	mg/k
benzene	.5569E+02	.2795E-03	.3937E-02	.5135E+00
toluene	.6506E+06	.9526E+00	.1342E+02	.5999E+04
p-xylene	.1413E+07	.6145E+00	.8655E+01	.1303E+05
111-trichloroethane	.3588E+06	.2919E+00	.4111E+01	.3308E+04
1122-tetrachloroethane	.5168E+07	.1808E+01	.2547E+02	.4765E+05
112-trichloroethane	.1093E+05	.2108E-01	.2969E+00	.1008E+03
11-dichoroethane	.9199E+01	.0000E+00	.0000E+00	.8481E-01
11-dichoroethene	.3917E+01	.0000E+00	.0000E+00	.3612E-01
methylenechloride	.4876E+01	.0000E+00	.0000E+00	.4496E-01

	Ascoff.out			
tetrachloroethene	.7550E+06	.9289E-01	.1308E+01	.6961E+04
trichloroethene	.7067E+03	.2720E-02	.3831E-01	.6516E+01
vinylacetate	.4736E+01	.0000E+00	.0000E+00	.4367E-01
vinylchloride	.1823E+00	.0000E+00	.0000E+00	.1681E-02
Ethylbenzene	.3166E+03	.1477E-02	.2080E-01	.2919E+01

RESULTS AT TIME (DAYS) 1828.606000

5 yrs
↓

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
toluene	.1036E+03	.1286E+06	.2010E+03	.3516E+04
p-xylene	.2018E+03	.8452E+06	.4404E+03	.2221E+05
111-trichloroethane	.6354E+02	.1413E+06	.4436E+03	.5005E+04
1122-tetrachloroethane	.6470E+03	.3329E+07	.1608E+05	.1406E+06
112-trichloroethane	.1400E+01	.1260E+04	.1188E+02	.1251E+03
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.4315E+02	.6476E+06	.1637E+03	.2327E+04
trichloroethene	.2431E-01	.1152E+02	.2696E-01	.2310E+00
vinylacetate	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00

TOTAL MASS IN ALL PHASE = .5286E+04

TOTAL MASS IN GAS PHASE (kg)	= .1061E+01
TOTAL MASS IN FREE PHASE (kg)	= .5093E+04
TOTAL MASS IN WATER PHASE (kg)	= .1734E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1738E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.2566E+01	.0000E+00	.0000E+00	.2366E-01
toluene	.1324E+06	.3207E+00	.4517E+01	.1221E+04
p-xylene	.8680E+06	.6250E+00	.8803E+01	.8003E+04
111-trichloroethane	.1468E+06	.1968E+00	.2772E+01	.1353E+04
1122-tetrachloroethane	.3486E+07	.2004E+01	.2823E+02	.3214E+05

	Ascoff.out			
112-trichloroethane	.1399E+04	.4333E-02	.6104E-01	.1290E+02
11-dichloroethane	.6091E+01	.0000E+00	.0000E+00	.5616E-01
11-dichloroethene	.1247E+01	.0000E+00	.0000E+00	.1149E-01
methylenechloride	.3084E+01	.0000E+00	.0000E+00	.2843E-01
tetrachloroethene	.6502E+06	.1337E+00	.1882E+01	.5994E+04
trichloroethene	.1181E+02	.7534E-04	.1061E-02	.1089E+00
vinylacetate	.2918E+01	.0000E+00	.0000E+00	.2690E-01
vinylchloride	.1796E+00	.0000E+00	.0000E+00	.1656E-02
Ethylbenzene	.3431E+01	.0000E+00	.0000E+00	.3163E-01

RESULTS AT TIME (DAYS) 2193.606000

6 yrs

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
toluene	.1173E+02	.6586E+04	.2277E+02	.3983E+03
p-xylene	.1748E+03	.3309E+06	.3815E+03	.1924E+05
111-trichloroethane	.2593E+02	.2606E+05	.1810E+03	.2042E+04
1122-tetrachloroethane	.6589E+03	.1533E+07	.1637E+05	.1432E+06
112-trichloroethane	.7555E-01	.3075E+02	.6413E+00	.6754E+01
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.8622E-01	.2949E+01	.3418E-01	.2440E-01
tetrachloroethene	.7167E+02	.4862E+06	.2719E+03	.3864E+04
trichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylacetate	.1409E-01	.1530E+01	.2199E-01	.3926E-03
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00

TOTAL MASS IN ALL PHASE = .2569E+04

TOTAL MASS IN GAS PHASE (kg)	= .9432E+00
TOTAL MASS IN FREE PHASE (kg)	= .2382E+04
TOTAL MASS IN WATER PHASE (kg)	= .1723E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1688E+03

SPECIES	MASS	CONC	CONC	CONC
		WELL GAS	SOIL GAS	SOIL MAS
	g	g/m3	g/m3	mg/k
benzene	.1181E+01	.0000E+00	.0000E+00	.1088E-01

	Ascoff.out			
toluene	.7019E+04	.3634E-01	.5119E+00	.6472E+02
p-xylene	.3507E+06	.5417E+00	.7629E+01	.3233E+04
111-trichloroethane	.2831E+05	.8035E-01	.1132E+01	.2610E+03
1122-tetrachloroethane	.1692E+07	.2042E+01	.2876E+02	.1560E+05
112-trichloroethane	.3823E+02	.2340E-03	.3295E-02	.3525E+00
11-dichoroethane	.1504E+01	.0000E+00	.0000E+00	.1386E-01
11-dichoroethene	.1214E+01	.0000E+00	.0000E+00	.1119E-01
methylenechloride	.3003E+01	.0000E+00	.0000E+00	.2769E-01
tetrachloroethene	.4904E+06	.2220E+00	.3127E+01	.4521E+04
trichloroethene	.1917E+01	.0000E+00	.0000E+00	.1768E-01
vinylacetate	.1543E+01	.0000E+00	.0000E+00	.1423E-01
vinylchloride	.1749E+00	.0000E+00	.0000E+00	.1613E-02
Ethylbenzene	.1351E+01	.2920E-04	.4112E-03	.1246E-01

RESULTS AT TIME (DAYS) 2558.606000

↓ 7 yrs

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
toluene	.9776E-02	.3857E+00	.1898E-01	.3319E+00
p-xylene	.4319E+02	.5746E+04	.9425E+02	.4754E+04
111-trichloroethane	.6634E+00	.4685E+02	.4632E+01	.5225E+02
1122-tetrachloroethane	.3378E+03	.5521E+05	.8393E+04	.7341E+05
112-trichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichoroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichoroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.2456E+03	.1171E+06	.9320E+03	.1324E+05
trichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylacetate	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00

TOTAL MASS IN ALL PHASE = .2796E+03

TOTAL MASS IN GAS PHASE (kg)	= .6272E+00
TOTAL MASS IN FREE PHASE (kg)	= .1781E+03
TOTAL MASS IN WATER PHASE (kg)	= .9424E+01
TOTAL MASS IN SOIL PHASE (kg)	= .9146E+02

SPECIES	MASS	CONC	CONC	CONC
		WELL GAS	SOIL GAS	SOIL MAS

S

	Ascoff.out			
g	g	g/m3	g/m3	mg/k
benzene	.6097E-01	.0000E+00	.0000E+00	.5622E-03
toluene	.5058E+00	.0000E+00	.0000E+00	.4663E-02
p-xylene	.1061E+05	.1332E+00	.1876E+01	.9787E+02
111-trichloroethane	.9321E+02	.1440E-02	.2028E-01	.8594E+00
1122-tetrachloroethane	.1365E+06	.1031E+01	.1453E+02	.1258E+04
112-trichloroethane	.1606E+00	.0000E+00	.0000E+00	.1481E-02
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.1315E+06	.7602E+00	.1071E+02	.1212E+04
trichloroethene	.1381E+00	.0000E+00	.0000E+00	.1274E-02
vinylacetate	.8717E-02	.0000E+00	.0000E+00	.8037E-04
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
no free oil after time (days)		2601.106000		

RESULTS AT TIME (DAYS) 2669.888000

Days

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
toluene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
p-xylene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
111-trichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
1122-tetrachloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
112-trichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
trichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylacetate	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00


TOTAL MASS IN ALL PHASE = .0000E+00

TOTAL MASS IN GAS PHASE (kg)	= .0000E+00
TOTAL MASS IN FREE PHASE (kg)	= .0000E+00
TOTAL MASS IN WATER PHASE (kg)	= .0000E+00
TOTAL MASS IN SOIL PHASE (kg)	= .0000E+00

Ascoff.out


SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
g				
benzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
toluene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
p-xylene	.0000E+00	.7507E-04	.1057E-02	.0000E+00
111-trichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
1122-tetrachloroethane	.0000E+00	.2583E-01	.3638E+00	.0000E+00
112-trichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.0000E+00	.1032E-04	.1453E-03	.0000E+00
trichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylacetate	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00

ACS OFF SITE



10 darcy

ACS OFF SITE



Ascoff.spf

[HEADER]

FILETYPE=
PROJECT_TITLE=ACS OFF SITE
PROJECT_FILE=C:\DAEM\BIOSVE\ASCOFF.SPF
PROJECT_SPECIES_FILE=C:\DAEM\BIOSVE\ASCOFF.SSF
NUMERICAL_MODEL=BIOSVE.PIF
MODEL_INPUT_FILE=C:\DAEM\BIOSVE\ASCOFF.DAT
MODEL_OUTPUT_FILE=C:\DAEM\BIOSVE\ASCOFF.OUT
MODEL_SPECIES_FILE=C:\DAEM\BIOSVE\ASCOFF.SPC
MODEL_ERROR_FILE=C:\DAEM\BIOSVE\ASCOFF.ERR
PREPROCESSOR_VERSION=
NUMERICAL_MODEL_VERSION=

[CONTROL_PARAMETERS]

NTSP=14
IFOUR=1
HSMT=29156
Q=125.6
DELT=0.5
DTMX=5
TFACT=1.02
TMAX=5475
TPNT=180
TEMP=20
ETA=0.071
SOILV=63.8
WC=0.15
RHOB=1.7
FOC=0.005
HIN=1.5
HEX=0.02
EBIO=0.02
HRES=2915

	Ascoff.spc		
'benzene'	0.0120	78.1000	0.1000
80.0000 1780.0000 135.0000			
'toluene'	0.2990	92.1000	0.0290
111.0000 515.0000 490.0000			
'p-xylene'	0.1070	106.2000	0.0086
138.0000 198.0000 1413.0000			
'111-trichloroethane'	0.0530	133.5000	0.0162
74.1000 1500.0000 316.0000			
'1122-tetrachloroethane'	0.3380	167.8300	0.0070
146.2000 2900.0000 245.0000			
'112-trichloroethane'	0.0120	133.4000	0.0400
113.8000 4500.0000 295.0000			
'11-dichloroethane'	0.0120	182.0000	0.2400
57.5000 5500.0000 61.7000			
'11-dichloroethene'	0.0120	96.9400	0.7900
37.0000 2250.0000 69.2000			
'methylenchloride'	0.0240	106.7000	0.4760
93.7000 2000.0000 20.0000			
'tetrachloroethene'	0.0330	165.8000	0.0024
121.0000 150.0000 398.0000			
'trichloroethene'	0.0200	131.4000	0.0760
87.2000 1100.0000 240.0000			
'vinylacetate'	0.0210	86.0000	0.1500
72.0000 2000.0000 0.5000			
'vinylchloride'	0.0210	62.5000	3.5000
13.4000 2670.0000 24.0000			
'Ethylbenzene'	0.0360	106.7000	0.0920
136.2000 152.0000 1410.0000			

	Ascoff.out			
p-xylene	.8600E-02	.1380E+03	.1980E+03	.1413E+04
111-trichloroethane	.1620E-01	.7410E+02	.1500E+04	.3160E+03
1122-tetrachloroethane	.7000E-02	.1462E+03	.2900E+04	.2450E+03
112-trichloroethane	.4000E-01	.1138E+03	.4500E+04	.2950E+03
11-dichoroethane	.2400E+00	.5750E+02	.5500E+04	.6170E+02
11-dichoroethene	.7900E+00	.3700E+02	.2250E+04	.6920E+02
methylenechloride	.4760E+00	.9370E+02	.2000E+04	.2000E+02
tetrachloroethene	.2400E-02	.1210E+03	.1500E+03	.3980E+03
trichloroethene	.7600E-01	.8720E+02	.1100E+04	.2400E+03
vinylacetate	.1500E+00	.7200E+02	.2000E+04	.5000E+00
vinylchloride	.3500E+01	.1340E+02	.2670E+04	.2400E+02
Ethylbenzene	.9200E-01	.1362E+03	.1520E+03	.1410E+04
MASS FRACTION SUM	1.000000			

SPECIES	MOL WEIGHT g/mol	HENRY COEFF DIMENSIONLESS
benzene	.7810E+02	.0000E+00
toluene	.9210E+02	.0000E+00
p-xylene	.1062E+03	.0000E+00
111-trichloroethane	.1335E+03	.0000E+00
1122-tetrachloroethane	.1678E+03	.0000E+00
112-trichloroethane	.1334E+03	.0000E+00
11-dichoroethane	.1820E+03	.0000E+00
11-dichoroethene	.9694E+02	.0000E+00
methylenechloride	.1067E+03	.0000E+00
tetrachloroethene	.1658E+03	.0000E+00
trichloroethene	.1314E+03	.0000E+00
vinylacetate	.8600E+02	.0000E+00
vinylchloride	.6250E+02	.0000E+00
Ethylbenzene	.1067E+03	.0000E+00
sgmlti	250509.200000	

RESULTS AT TIME (DAYS) 0.000000E+00

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1326E+03	.3480E+06	.3042E+03	.1466E+04
toluene	.9595E+03	.8682E+07	.1862E+04	.3258E+05
p-xylene	.1019E+03	.3108E+07	.2223E+03	.1121E+05
111-trichloroethane	.9489E+02	.1537E+07	.6625E+03	.7473E+04
1122-tetrachloroethane	.2612E+03	.9791E+07	.6490E+04	.5676E+05
112-trichloroethane	.5254E+02	.3447E+06	.4460E+03	.4697E+04
11-dichoroethane	.3185E+03	.3483E+06	.4037E+03	.8892E+03

	Ascoff.out			
11-dichloroethene	.1047E+04	.3478E+06	.3096E+03	.7649E+03
methylenchloride	.1265E+04	.6976E+06	.5016E+03	.3581E+03
tetrachloroethene	.8795E+01	.9616E+06	.3337E+02	.4742E+03
trichloroethene	.1683E+03	.5812E+06	.1866E+03	.1599E+04
vinylacetate	.3495E+03	.6114E+06	.5454E+03	.9735E+01
vinylchloride	.7974E+04	.5979E+06	.3429E+04	.2938E+04
Ethylbenzene	.3668E+03	.1046E+07	.5718E+02	.2878E+04

TOTAL MASS IN ALL PHASE = .2916E+05

TOTAL MASS IN GAS PHASE (kg)	= .1310E+02
TOTAL MASS IN FREE PHASE (kg)	= .2900E+05
TOTAL MASS IN WATER PHASE (kg)	= .1545E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1241E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
	g	g/m3	g/m3	mg/k
benzene	.3499E+06	.1490E-04	.2099E-03	.3226E+04
toluene	.8718E+07	.0000E+00	.0000E+00	.8038E+05
p-xylene	.3120E+07	.0000E+00	.0000E+00	.2876E+05
111-trichloroethane	.1545E+07	.0000E+00	.0000E+00	.1425E+05
1122-tetrachloroethane	.9855E+07	.0000E+00	.0000E+00	.9086E+05
112-trichloroethane	.3499E+06	.0000E+00	.0000E+00	.3226E+04
11-dichloroethane	.3499E+06	.1736E-04	.2445E-03	.3226E+04
11-dichloroethene	.3499E+06	.6473E-04	.9117E-03	.3226E+04
methylenchloride	.6997E+06	.8143E-04	.1147E-02	.6452E+04
tetrachloroethene	.9621E+06	.0000E+00	.0000E+00	.8871E+04
trichloroethene	.5831E+06	.0000E+00	.0000E+00	.5376E+04
vinylacetate	.6123E+06	.1641E-04	.2311E-03	.5645E+04
vinylchloride	.6123E+06	.5008E-03	.7054E-02	.5645E+04
Ethylbenzene	.1050E+07	.4072E-04	.5735E-03	.9677E+04

end of initial conditions

RESULTS AT TIME (DAYS) 183.045300

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.4946E+02	.8472E+05	.1135E+03	.5469E+03
toluene	.9678E+03	.5717E+07	.1878E+04	.3286E+05

	Ascoff.out			
p-xylene	.1372E+03	.2732E+07	.2994E+03	.1510E+05
111-trichloroethane	.1147E+03	.1213E+07	.8007E+03	.9033E+04
1122-tetrachloroethane	.3594E+03	.8796E+07	.8932E+04	.7812E+05
112-trichloroethane	.4547E+02	.1947E+06	.3860E+03	.4066E+04
11-dichloroethane	.1732E+02	.1236E+05	.2196E+02	.4836E+02
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.2948E+01	.1061E+04	.1169E+01	.8344E+00
tetrachloroethene	.1296E+02	.9246E+06	.4916E+02	.6985E+03
trichloroethene	.8758E+02	.1974E+06	.9711E+02	.8321E+03
vinylacetate	.6466E+02	.7384E+05	.1009E+03	.1801E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.1525E+03	.2840E+06	.2378E+02	.1197E+04

TOTAL MASS IN ALL PHASE = .2039E+05

TOTAL MASS IN GAS PHASE (kg)	= .2012E+01
TOTAL MASS IN FREE PHASE (kg)	= .2023E+05
TOTAL MASS IN WATER PHASE (kg)	= .1270E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1425E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
	g	g/m3	g/m3	mg/k
benzene	.8544E+05	.1502E+00	.2116E+01	.7877E+03
toluene	.5752E+07	.2939E+01	.4140E+02	.5304E+05
p-xylene	.2748E+07	.4166E+00	.5868E+01	.2534E+05
111-trichloroethane	.1223E+07	.3483E+00	.4906E+01	.1127E+05
1122-tetrachloroethane	.8883E+07	.1092E+01	.1538E+02	.8190E+05
112-trichloroethane	.1992E+06	.1381E+00	.1945E+01	.1837E+04
11-dichloroethane	.1245E+05	.5267E-01	.7418E+00	.1148E+03
11-dichloroethene	.1550E+02	.0000E+00	.0000E+00	.1430E+00
methylenechloride	.1066E+04	.9020E-02	.1270E+00	.9829E+01
tetrachloroethene	.9254E+06	.3934E-01	.5541E+00	.8532E+04
trichloroethene	.1984E+06	.2660E+00	.3747E+01	.1829E+04
vinylacetate	.7401E+05	.1964E+00	.2767E+01	.6824E+03
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.2854E+06	.4634E+00	.6526E+01	.2631E+04

RESULTS AT TIME (DAYS) 367.263000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID

Ascoff.out

benzene	.9653E+01	.1159E+05	.2215E+02	.1067E+03
toluene	.7613E+03	.3152E+07	.1478E+04	.2585E+05
p-xylene	.1629E+03	.2274E+07	.3555E+03	.1793E+05
111-trichloroethane	.1167E+03	.8651E+06	.8150E+03	.9194E+04
1122-tetrachloroethane	.4404E+03	.7553E+07	.1094E+05	.9572E+05
112-trichloroethane	.2897E+02	.8693E+05	.2459E+03	.2590E+04
11-dichloroethane	.2481E+00	.1241E+03	.3145E+00	.6927E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.6819E-01	.1720E+02	.2703E-01	.1930E-01
tetrachloroethene	.1748E+02	.8744E+06	.6633E+02	.9425E+03
trichloroethene	.2711E+02	.4282E+05	.3006E+02	.2575E+03
vinylacetate	.4782E+01	.3827E+04	.7463E+01	.1332E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3453E+02	.4506E+05	.5383E+01	.2709E+03

TOTAL MASS IN ALL PHASE = .1508E+05

TOTAL MASS IN GAS PHASE (kg)	= .1604E+01
TOTAL MASS IN FREE PHASE (kg)	= .1491E+05
TOTAL MASS IN WATER PHASE (kg)	= .1397E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1529E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
	g	g/m3	g/m3	mg/k
benzene	.1173E+05	.2993E-01	.4215E+00	.1081E+03
toluene	.3180E+07	.2360E+01	.3324E+02	.2932E+05
p-xylene	.2292E+07	.5050E+00	.7112E+01	.2113E+05
111-trichloroethane	.8752E+06	.3619E+00	.5097E+01	.8069E+04
1122-tetrachloroethane	.7660E+07	.1365E+01	.1923E+02	.7063E+05
112-trichloroethane	.8979E+05	.8980E-01	.1265E+01	.8279E+03
11-dichloroethane	.1254E+03	.7687E-03	.1083E-01	.1156E+01
11-dichloroethene	.1041E+02	.0000E+00	.0000E+00	.9602E-01
methylenechloride	.1724E+02	.0000E+00	.0000E+00	.1590E+00
tetrachloroethene	.8754E+06	.5419E-01	.7632E+00	.8071E+04
trichloroethene	.4313E+05	.8405E-01	.1184E+01	.3977E+03
vinylacetate	.3840E+04	.1483E-01	.2088E+00	.3540E+02
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.4537E+05	.1071E+00	.1508E+01	.4183E+03

RESULTS AT TIME (DAYS) 551.251300

Ascoff.out

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.8334E+00	.6675E+03	.1912E+01	.9215E+01
toluene	.4816E+03	.1330E+07	.9347E+03	.1635E+05
p-xylene	.1869E+03	.1741E+07	.4080E+03	.2058E+05
111-trichloroethane	.1072E+03	.5300E+06	.7485E+03	.8444E+04
1122-tetrachloroethane	.5292E+03	.6054E+07	.1315E+05	.1150E+06
112-trichloroethane	.1363E+02	.2730E+05	.1157E+03	.1219E+04
11-dichloroethane	.4839E-01	.1615E+02	.6133E-01	.1351E+00
11-dichloroethene	.1011E+00	.1025E+02	.2990E-01	.7386E-01
methylenechloride	.7874E-01	.1325E+02	.3121E-01	.2228E-01
tetrachloroethene	.2416E+02	.8063E+06	.9169E+02	.1303E+04
trichloroethene	.4491E+01	.4733E+04	.4980E+01	.4267E+02
vinylacetate	.1039E+00	.5550E+02	.1622E+00	.2896E-02
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3663E+01	.3188E+04	.5709E+00	.2874E+02

TOTAL MASS IN ALL PHASE = .1068E+05

TOTAL MASS IN GAS PHASE (kg)	= .1352E+01
TOTAL MASS IN FREE PHASE (kg)	= .1050E+05
TOTAL MASS IN WATER PHASE (kg)	= .1546E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1630E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	
S				SOIL MAS
g	g	g/m3	g/m3	mg/k
benzene	.6795E+03	.2583E-02	.3638E-01	.6265E+01
toluene	.1348E+07	.1493E+01	.2102E+02	.1243E+05
p-xylene	.1762E+07	.5794E+00	.8161E+01	.1625E+05
111-trichloroethane	.5393E+06	.3323E+00	.4680E+01	.4972E+04
1122-tetrachloroethane	.6182E+07	.1640E+01	.2310E+02	.5700E+05
112-trichloroethane	.2865E+05	.4226E-01	.5952E+00	.2641E+03
11-dichloroethane	.1624E+02	.0000E+00	.0000E+00	.1497E+00
11-dichloroethene	.1032E+02	.0000E+00	.0000E+00	.9518E-01
methylenechloride	.1330E+02	.0000E+00	.0000E+00	.1226E+00
tetrachloroethene	.8077E+06	.7489E-01	.1055E+01	.7447E+04
trichloroethene	.4785E+04	.1392E-01	.1961E+00	.4412E+02
vinylacetate	.5577E+02	.3221E-03	.4536E-02	.5142E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00

Ethylbenzene Ascoff.out
 .3222E+04 .1135E-01 .1599E+00 .2970E+02

RESULTS AT TIME (DAYS) 735.239600

SPECIESMASS (g) IN PHASES.....			
	GAS	OIL	WATER	SOLID
benzene	.1770E-01	.8646E+01	.4062E-01	.1958E+00
toluene	.2075E+03	.3494E+06	.4027E+03	.7044E+04
p-xylene	.2022E+03	.1148E+07	.4412E+03	.2226E+05
111-trichloroethane	.8217E+02	.2477E+06	.5737E+03	.6472E+04
1122-tetrachloroethane	.6147E+03	.4289E+07	.1527E+05	.1336E+06
112-trichloroethane	.3822E+01	.4666E+04	.3244E+02	.3417E+03
11-dichloroethane	.6214E-01	.1264E+02	.7876E-01	.1735E+00
11-dichloroethene	.1629E+00	.1007E+02	.4817E-01	.1190E+00
methylenechloride	.1272E+00	.1305E+02	.5041E-01	.3599E-01
tetrachloroethene	.3492E+02	.7106E+06	.1325E+03	.1883E+04
trichloroethene	.2507E+00	.1611E+03	.2779E+00	.2381E+01
vinylacetate	.1470E-01	.4788E+01	.2295E-01	.4096E-03
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.1044E+00	.5542E+02	.1627E-01	.8191E+00

TOTAL MASS IN ALL PHASE = .6939E+04

TOTAL MASS IN GAS PHASE (kg)	= .1146E+01
TOTAL MASS IN FREE PHASE (kg)	= .6750E+04
TOTAL MASS IN WATER PHASE (kg)	= .1686E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1716E+03

SPECIES	MASS	CONC		
		WELL GAS	SOIL GAS	SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.8903E+01	.5481E-04	.7720E-03	.8209E-01
toluene	.3570E+06	.6428E+00	.9053E+01	.3292E+04
p-xylene	.1171E+07	.6264E+00	.8823E+01	.1080E+05
111-trichloroethane	.2548E+06	.2546E+00	.3586E+01	.2349E+04
1122-tetrachloroethane	.4438E+07	.1905E+01	.2683E+02	.4091E+05
112-trichloroethane	.5045E+04	.1184E-01	.1668E+00	.4651E+02
11-dichloroethane	.1276E+02	.0000E+00	.0000E+00	.1177E+00
11-dichloroethene	.1019E+02	.0000E+00	.0000E+00	.9397E-01
methylenechloride	.1313E+02	.0000E+00	.0000E+00	.1210E+00

	Ascoff.out			
tetrachloroethene	.7126E+06	.1082E+00	.1524E+01	.6570E+04
trichloroethene	.1640E+03	.7765E-03	.1094E-01	.1512E+01
vinylacetate	.4802E+01	.0000E+00	.0000E+00	.4427E-01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.5637E+02	.3233E-03	.4554E-02	.5198E+00

RESULTS AT TIME (DAYS) 919.227800

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
toluene	.3964E+02	.3349E+05	.7693E+02	.1346E+04
p-xylene	.1920E+03	.5472E+06	.4191E+03	.2114E+05
111-trichloroethane	.4284E+02	.6481E+05	.2991E+03	.3374E+04
1122-tetrachloroethane	.6632E+03	.2322E+07	.1648E+05	.1441E+06
112-trichloroethane	.3799E+00	.2327E+03	.3225E+01	.3396E+02
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.5551E+02	.5668E+06	.2106E+03	.2993E+04
trichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylacetate	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00

TOTAL MASS IN ALL PHASE = .3726E+04

TOTAL MASS IN GAS PHASE (kg)	= .9936E+00
TOTAL MASS IN FREE PHASE (kg)	= .3534E+04
TOTAL MASS IN WATER PHASE (kg)	= .1749E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1730E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	
S	g	g/m3	g/m3	mg/k
benzene	.1585E+01	.0000E+00	.0000E+00	.1461E-01
toluene	.3496E+05	.1229E+00	.1731E+01	.3223E+03
p-xylene	.5689E+06	.5953E+00	.8384E+01	.5245E+04
111-trichloroethane	.6851E+05	.1328E+00	.1870E+01	.6317E+03
1122-tetrachloroethane	.2482E+07	.2056E+01	.2896E+02	.2289E+05

	Ascoff.out			
112-trichloroethane	.2703E+03	.1178E-02	.1659E-01	.2492E+01
11-dichloroethane	.2913E+01	.0000E+00	.0000E+00	.2686E-01
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.5700E+06	.1720E+00	.2423E+01	.5256E+04
trichloroethene	.2581E+01	.0000E+00	.0000E+00	.2380E-01
vinylacetate	.1564E+01	.0000E+00	.0000E+00	.1442E-01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.2269E+01	.0000E+00	.0000E+00	.2092E-01

RESULTS AT TIME (DAYS) 1103.216000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
toluene	.4032E+00	.7102E+02	.7826E+00	.1369E+02
p-xylene	.1138E+03	.6758E+05	.2483E+03	.1252E+05
111-trichloroethane	.5566E+01	.1755E+04	.3886E+02	.4384E+03
1122-tetrachloroethane	.5601E+03	.4087E+06	.1392E+05	.1217E+06
112-trichloroethane	.9934E-02	.1269E+01	.8433E-01	.8881E+00
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.1371E+03	.2917E+06	.5201E+03	.7390E+04
trichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylacetate	.1514E-01	.5156E+00	.2363E-01	.4218E-03
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00

TOTAL MASS IN ALL PHASE = .9275E+03

TOTAL MASS IN GAS PHASE (kg)	= .8169E+00
TOTAL MASS IN FREE PHASE (kg)	= .7698E+03
TOTAL MASS IN WATER PHASE (kg)	= .1473E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1421E+03

SPECIES	MASS	CONC	CONC	CONC
		WELL GAS	SOIL GAS	SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.2475E+00	.0000E+00	.0000E+00	.2282E-02

	Ascoff.out			
toluene	.8583E+02	.1245E-02	.1754E-01	.7914E+00
p-xylene	.8042E+05	.3528E+00	.4969E+01	.7414E+03
111-trichloroethane	.2237E+04	.1726E-01	.2431E+00	.2062E+02
1122-tetrachloroethane	.5445E+06	.1737E+01	.2447E+02	.5020E+04
112-trichloroethane	.1594E+01	.0000E+00	.0000E+00	.1470E-01
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.2997E+06	.4248E+00	.5983E+01	.2763E+04
trichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylacetate	.5286E+00	.0000E+00	.0000E+00	.4874E-02
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.4539E+00	.0000E+00	.0000E+00	.4185E-02
no free oil after time (days)	1178.254000			

RESULTS AT TIME (DAYS) 1209.181000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
toluene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
p-xylene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
111-trichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
1122-tetrachloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
112-trichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
trichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylacetate	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00

TOTAL MASS IN ALL PHASE = .0000E+00


TOTAL MASS IN GAS PHASE (kg)	= .0000E+00
TOTAL MASS IN FREE PHASE (kg)	= .0000E+00
TOTAL MASS IN WATER PHASE (kg)	= .0000E+00
TOTAL MASS IN SOIL PHASE (kg)	= .0000E+00

SPECIES	MASS	CONC	CONC	CONC
		WELL GAS	SOIL GAS	SOIL MAS


Ascoff.out

S	g	g/m3	g/m3	mg/k
benzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
toluene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
p-xylene	.0000E+00	.5039E-03	.7097E-02	.0000E+00
111-trichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
1122-tetrachloroethane	.0000E+00	.1201E+00	.1692E+01	.0000E+00
112-trichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.0000E+00	.1853E-03	.2610E-02	.0000E+00
trichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylacetate	.0000E+00	.0000E+00	.0000E+00	.0000E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.0000E+00	.0000E+00	.0000E+00	.0000E+00


ACS OFF SITE



ACS OFF SITE



ACS OFF SITE



Flowrate Estimation:

- ☐ Medium Sand
- ☐ Fine Sand
- ☐ Silty Sand
- ☐ Clayey Silts
- ☒ Input Your Own Permeability Range

Permeability Range (darcy)

1.75 to 10

Well Radius

2 in

Radius of Influence

30 ft

Interval Thickness*

5 ft

--> Calculate Flowrate Ranges <--

* thickness of screened interval, or permeable zone (whichever is smaller).

- 1) Choose Soil Type, or
Optional - Enter your own permeability values (darcy)
- 2) Enter Well Radius (in)
- 3) Enter Radius of Influence (ft) & Interval Thickness*
- 4) Optional - Enter your own well vacuum (406" = max)
- 5) Click button to calculate Predicted Flowrate Ranges

Predicted Flowrate Ranges

Well Vacuum P_w (in H ₂ O)	Flowrate (SCFM) (single well)	
	1.75 darcy	10 darcy
5	0.46	to 2.65
10	0.92	to 5.27
20	1.82	to 10.41
40	3.55	to 20.29
60	5.19	to 29.65
120	9.55	to 54.59
108	8.75	to 49.98

4

Still bottoms

About Soils (& Unit Conversions)

8

Info about Calculation

Flowrate Estimation:

- ☐ Medium Sand
- ☐ Fine Sand
- ☐ Silty Sand
- ☐ Clayey Silts

Input Your Own Permeability Range

Permeability Range (darcy)

1.75 to 5.2

Well Radius

2 in

Radius of Influence

30 ft

Interval Thickness*

5 ft

--> Calculate Flowrate Ranges <--

*thickness of screened interval, or permeable zone (whichever is smaller).

- 1) Choose Soil Type, or
Optional - Enter your own permeability values (darcy)
- 2) Enter Well Radius (in)
- 3) Enter Radius of Influence (ft) & Interval Thickness*
- 4) Optional - Enter your own well vacuum (406" = max)
- 5) Click button to calculate Predicted Flowrate Ranges

Predicted Flowrate Ranges

Well Vacuum P_w (in H_2O)	Flowrate (SCFM) (single well)	
5	0.46	to 1.38
10	0.92	to 2.74
20	1.82	to 5.41
40	3.55	to 10.55
60	5.19	to 15.42
120	9.55	to 28.38
108	8.75	to 25.99

About Soils (& Unit Conversions)

8

Info about Calculation

Vapor Concentration Estimation - Calculation

1 Type in Temperature (C) (hit <return>)

20

Click to Enter Composition of Contaminant

☒ Enter Distribution

2 or

☐ "Fresh" Gasoline

Choose one of the Default Distributions

☐ "Weathered" Gasoline

3 Click to View Distributions, (optional)

View Distributions

4 Click to Perform Calculations

☒ Perform Calculations

Results:

Sum of Mass Fractions

1.00000

Calc. Vapor Pressure

0.18920

atm

Calc. Vapor Concentration

583.17566

mg/l

How Do I Measure a Distribution?

10

About Calculation

Print Card

Maximum Removal Rate

Estimates

Select your unit preference below

☒ [lb/d]

☐ [kg/d]

Temperature (C)
Soil Type
Soil Permeability Range (darcy)
Well Radius (in)
Radius of Influence (ft)
Contaminant Type
Permeable Zone Thickness (ft)

20	
User Defined	
1.75	to 5.2
2	
30	
User Defined	
5	

Note:

These are "maximum removal rates", and should only be used as screening estimates to determine venting is even feasible at a given site. Continue on to the next card to assess if these rates are acceptable...

P _w - Well Vacuum (in H ₂ O)	Flowrate Estimates [SCFM] (single well)		Max. Removal Rate Estimates [lb/d] (single well)	
5	0.46	to	1.38	24.45 to 73.35
10	0.92	to	2.74	49.52 to 147.47
20	1.82	to	5.41	100.49 to 298.71
40	3.55	to	10.55	206.70 to 614.27
60	5.19	to	15.42	319.61 to 949.61
120	9.55	to	28.38	711.15 to 2113.35
108	8.75	to	25.99	625.41 to 1857.65

Is Soil Venting Appropriate?

At this point, you compare the maximum possible removal rate with your desired removal rate.

If the maximum removal rate does not exceed your desired removal rate, then soil venting is not likely to meet your needs, and you should consider another treatment technology, or make your needs more realistic.

In the next cards, we will refine the removal rate estimates, in order to decide if venting can achieve your objectives.

- Enter ☐ kg
① Estimated Spill Mass ☒ lb
- ② Enter Desired Remediation Time days
- ③

Single Vertical Well Results

Desired Removal Rate:	<input type="text" value="992.876"/>	[lb/d]
Gauge Vacuum (in H ₂ O):	<input type="text" value="120"/>	[in H ₂ O]
Min Flowrate @ 120in H ₂ O	<input type="text" value="9.55"/>	[SCFM]
Max Flowrate @ 120in H ₂ O	<input type="text" value="28.38"/>	[SCFM]
Max. Est. Removal Rate:		
(lower estimate) - per well	<input type="text" value="711.15"/>	[lb/d]
(upper estimate) - per well	<input type="text" value="2113.35"/>	[lb/d]

D -> Import Data <-

FIRST PRESS THE IMPORT DATA
BUTTON!

These are the results for the contaminant
type that you have specified. All of this

Saturated Vapor
Concentration at time=0

.4096E+03

[mg/L]

Min Volume to Remove
>90% of Initial Residual

12.95

[L-air/g-resi
dual]

Temperature (°C):

20

Contaminant Type:

User Defined

Qt/M(0) L-air/ g-residual	Vapor Conc. [% Initial]	Residual Level [% Initial]	BP #1 Residual [% total]	BP #2 Residual [% total]	BP #3 Residual [% total]	BP #4 Residual [% total]	BP #5 Residual [% total]	
10.77	11.25	18.10	.00	.00	.05	5.22	94.73	↑
11.86	11.16	13.10	.00	.00	.00	4.24	95.76	
12.95	11.17	8.10	.00	.00	.00	3.25	96.75	
14.05	11.21	3.10	.00	.00	.00	1.27	98.73	
14.08	11.21	2.94	.00	.00	.00	1.25	98.75	
14.11	11.21	2.80	.00	.00	.00	1.22	98.78	
14.14	11.22	2.66	.00	.00	.00	1.19	98.81	
14.17	11.22	2.52	.00	.00	.00	1.17	98.83	↓

17

Print Card

Is Venting Appropriate?

This is a complete summary of the data and results. Based upon these numbers, a minimum number of wells has been calculated, which should give you some indication of how appropriate venting is for your application. Note that this is the number of wells if circumstances are ideal, which they rarely are.

The next card discusses some of the conditions that may limit the effectiveness

Temperature [°C]:

20

Contaminant Type:

User Defined

Soil Type:

User Defined

Well Radius [m]:

2

Est. Radius of Influence [ft]:

30

Permeable Zone Thickness [ft]:

5

Flowrate per Well (120" Vac) [SCFM]

9.55

Flowrate per Well (120" Vac) [SCFM]

28.38

Min. Vol. of Air [L/g-residual]:

12.95

Estimated Spill Mass:

3624000

lb

Desired Remediation Time [days]:

3650

3.54

Minimum # of Wells Based
on Your Input Parameters

10.52

Help: Boundary Layer Equations - Calculation

① Soil Type (choose one)

- ☐ Medium Sand ☐ Clayey Silts
☐ Silty Sand ☐ Fine Sand
☒ Input Your Own Permeability Range

1.75 to 52 [darcys]

② Process Variables:

5 thickness of screened interval [ft]
30 radius of influence of venting well [ft]
2 venting well radius [in]
60 applied vacuum at well [in H₂O]
225 radial width of contaminated zone

③ --> Calculate <--

greatest removal rates, in this case, correspond to the lowest efficiency values. This is because the driving force for removal is a concentration gradient in the vapor phase.

The most cost-efficient systems, therefore, balance removal rates vs. the cost of removing and treating large volumes of dilute vapors. The screened interval should, in this case, be chosen to produce a relative efficiency of about 20%.

Relative Efficiency =
(%)

100

to

100

Return

H29

Help: Low Permeability Lenses - Calculation

① Process Variables:

(input values)

venting well radius [m]
 radial width of contaminated zone [ft]
 residual contaminant level [mg/kg]

③

--> Calculate <--

② Contaminant Properties:

contaminant molecular weight [g/mole]
 contaminant vapor pressure [mm Hg]
 temperature [C]

☐ use values already input from Card 10

Just enter values into the appropriate fields, then click on the "Calculate" button.



Time (days)	Removal Rate (kg/d)	δ (m)
1	17204.480	0.076
7	6502.682	0.201
30	3141.094	0.415
60	2221.089	0.588
120	1570.547	0.831
180	1282.346	1.018
240	1110.544	1.175
360	906.756	1.439
540	740.363	1.763
720	641.173	2.035
1080	523.516	2.493

Return

H30

Design Input Parameters...

(soil stratigraphy & contaminant characteristics)

Select the total mass units
that you prefer

☐ [kg]

☒ [lb]

Please enter the required information for each distinct soil layer. Please enter the required information for each distinct soil layer, click on the "Update" button, and then proceed to the next card (i.e. click on right arrow at bottom).

Clear All Entries

Description of Soil Unit			Depth BGS* [ft]		Description of Contamination	radius [ft]	interval thickness [ft]	average conc. [mg/kg]	Calc. Total Mass [lb]
1	fill	0	to	3	Mixture	225	3	120410	6102026.7
2	sand	3	to	5	Mixture	225	2	6425	217066.8
3	sand	5	to	10	Mixture	225	5	30758	2597875.8
4	sand	0	to	0	Mixture	225	0	5592	0.0
5			to						0.0
6			to						0.0
7			to						0.0
8			to						0.0

* Below Ground Surface

Update

Return

SD2

Design Input Parameters...

Please enter the required information for each distinct soil layer, and then proceed to the next card.

Note: - click on any table heading to get more info
- use arrow key to move between cells

- ☐ Medium Sand
- ☐ Fine Sand
- ☐ Silty Sand
- ☐ Clayey Silts

					Extraction Well Construction			Critical Volume of Air** [L/g]	Efficiency [%]
Description of Soil Unit	Permeability* [darcy]		Design Vacuum (in H2O)	well radius [in]	screen thickness [ft]	radius of influence [ft]			
1 fill	1.75	to	5.2	60	4	0	30	12.95	100
2 sand	1.75	to	5.2	60	4	2	30	12.95	100
3 sand	1.75	to	5.2	60	4	5	30	12.95	100
4 sand	0	to	0	60	4	0	30	12.95	100
5		to							
6		to							
7		to							
8		to							

* Enter or choose from list at top right

** minimum volume of vapor required to achieve remediation

Clear All Entries

Return

SD3

Design Input Parameters...

Please enter (1) the desired time period for remediation, (2) the design gauge vacuum, and then (3) click the "update" button.

Note: - click on any table heading to get more info
- use arrow key to move between cells

③

Update

		①	②	Minimum Number of Wells				
Description of Soil Unit		Time for Clean-up [days]	Design Vacuum (in H ₂ O)	Flowrate per Vapor Extraction Well [SCFM]		Based on Area	Based on Critical Volume**	
1	fill	3650	60	NA	to	NA	56.3	NA to NA
2	sand	3650	60	2.39	to	7.11	56.3	0.7 to 2.0
3	sand	3650	60	5.99	to	17.79	56.3	4.1 to 12.3
4	sand	0	60	NA	to	NA	56.3	NA to NA
5				NA	to	NA	NA	NA to NA
6				NA	to	NA	NA	NA to NA
7				NA	to	NA	NA	NA to NA
8				NA	to	NA	NA	NA to NA

NA - not enough input data

** minimum volume of vapor required to achieve remediation



Clear All Entries



Return

SD4

Is Soil Venting Appropriate?

At this point, you compare the maximum possible removal rate with your desired removal rate.

If the maximum removal rate does not exceed your desired removal rate, then soil venting is not likely to meet your needs, and you should consider another treatment technology, or make your needs more realistic.

In the next cards, we will refine the removal rate estimates, in order to decide if venting can achieve your objectives.

- Enter ☐ kg
① Estimated Spill Mass ☒ lb
- ② Enter Desired Remediation Time days
- ③

Single Vertical Well Results

Desired Removal Rate:	<input type="text" value="661.917"/>	[lb/d]
Gauge Vacuum (in H ₂ O):	<input type="text" value="120"/>	[in H ₂ O]
Min Flowrate @ 120in H ₂ O	<input type="text" value="9.55"/>	[SCFM]
Max Flowrate @ 120in H ₂ O	<input type="text" value="28.38"/>	[SCFM]
Max. Est. Removal Rate:		
(lower estimate) - per well	<input type="text" value="711.15"/>	[lb/d]
(upper estimate) - per well	<input type="text" value="2113.35"/>	[lb/d]

Is Venting Appropriate?

This is a complete summary of the data and results. Based upon these numbers, a "minimum number of wells" has been calculated, which should give you some indication of how appropriate venting is for your application. Note that this is the number of wells if circumstances are ideal, which they rarely are.

The next card discusses some of the conditions that may limit the effectiveness

Temperature [°C]:

20

Contaminant Type:

User Defined

Soil Type:

User Defined

Well Radius [m]:

2

Est. Radius of Influence [ft]:

30

Permeable Zone Thickness [ft]:

5

Flowrate per Well (120" Vac) [SCFM]

9.55

Flowrate per Well (120" Vac) [SCFM]

28.38

Min. Vol. of Air [L/g-residual]:

12.95

Estimated Spill Mass:

3624000

lb

Desired Remediation Time [days]:

5475


2.36

Minimum # of Wells Based
on Your Input Parameters

7.01


18

ACS Still Bottoms



1.75 darcy

ACS Still Bottoms



Stlbot.spf

[HEADER]

FILETYPE=
PROJECT_TITLE=ACS Still Bottoms
PROJECT_FILE=C:\DAEM\BIOSVE\STLBOT.SPF
PROJECT_SPECIES_FILE=C:\DAEM\BIOSVE\STLBOT.SSF
NUMERICAL_MODEL=BIOSVE.PIF
MODEL_INPUT_FILE=C:\DAEM\BIOSVE\STLBOT.DAT
MODEL_OUTPUT_FILE=C:\DAEM\BIOSVE\STLBOT.OUT
MODEL_SPECIES_FILE=C:\DAEM\BIOSVE\STLBOT.SPC
MODEL_ERROR_FILE=C:\DAEM\BIOSVE\STLBOT.ERR
PREPROCESSOR_VERSION=
NUMERICAL_MODEL_VERSION=

[CONTROL_PARAMETERS]

NTSP=14
IFOUR=1
HSMT=64714
Q=5.19
DELT=0.5
DTMX=5
TFACT=1.02
TMAX=5475
TPNT=365
TEMP=20
ETA=0.071
SOILV=80.5
WC=0.15
RHOB=1.7
FOC=0.005
HIN=1.5
HEX=0.02
EBIO=0.02
HRES=6471

STLBOT.ssf

[SPECIES_DATA]

SNAME1=benzene

PMF1=0.012

PMW1=78.1

PVP1=0.1

PBP1=80

PSI1=1780

PKOW1=135

SNAME2=toluene

PMF2=0.299

PMW2=92.1

PVP2=0.029

PBP2=111

PSI2=515

PKOW2=490

SNAME3=p-xylene

PMF3=0.107

PMW3=106.2

PVP3=0.0086

PBP3=138

PSI3=198

PKOW3=1413

SNAME4=111-trichloroethane

PMF4=0.053

PMW4=133.5

PVP4=0.0162

PBP4=74.1

PSI4=1500

PKOW4=316

SNAME5=1122-tetrachloroethane

PMF5=0.338

PMW5=167.83

PVP5=0.007

PBP5=146.2

PSI5=2900

PKOW5=245

SNAME6=112-trichloroethane

PMF6=0.012

PMW6=133.4

PVP6=0.04

PBP6=113.8

PSI6=4500

PKOW6=295

SNAME7=11-dichloroethane

PMF7=0.012

PMW7=182

PVP7=0.24

PBP7=57.5

PSI7=5500

PKOW7=61.7

SNAME8=11-dichloroethene

STLBOT.ssf

PMF8=0.012
PMW8=96.94
PVP8=0.79
PBP8=37
PSI8=2250
PKOW8=69.2
SNAME9=methylenechloride
PMF9=0.024
PMW9=106.7
PVP9=0.476
PBP9=93.7
PSI9=2000
PKOW9=20
SNAME10=tetrachloroethene
PMF10=0.033
PMW10=165.8
PVP10=0.0024
PBP10=121
PSI10=150
PKOW10=398
SNAME11=trichloroethene
PMF11=0.02
PMW11=131.4
PVP11=0.076
PBP11=87.2
PSI11=1100
PKOW11=240
SNAME12=vinylacetate
PMF12=0.021
PMW12=86
PVP12=0.15
PBP12=72
PSI12=2000
PKOW12=0.5
SNAME13=vinylchloride
PMF13=0.021
PMW13=62.5
PVP13=3.5
PBP13=13.4
PSI13=2670
PKOW13=24
SNAME14=Ethylbenzene
PMF14=0.036
PMW14=106.7
PVP14=0.092
PBP14=136.2
PSI14=152
PKOW14=1410

	Stlbot.spc		
'benzene'	0.0120	78.1000	0.1000
80.0000 1780.0000 135.0000			
'toluene'	0.2990	92.1000	0.0290
111.0000 515.0000 490.0000			
'p-xylene'	0.1070	106.2000	0.0086
138.0000 198.0000 1413.0000			
'111-trichloroethane'	0.0530	133.5000	0.0162
74.1000 1500.0000 316.0000			
'1122-tetrachloroethane'	0.3380	167.8300	0.0070
146.2000 2900.0000 245.0000			
'112-trichloroethane'	0.0120	133.4000	0.0400
113.8000 4500.0000 295.0000			
'11-dichloroethane'	0.0120	182.0000	0.2400
57.5000 5500.0000 61.7000			
'11-dichloroethene'	0.0120	96.9400	0.7900
37.0000 2250.0000 69.2000			
'methylenchloride'	0.0240	106.7000	0.4760
93.7000 2000.0000 20.0000			
'tetrachloroethene'	0.0330	165.8000	0.0024
121.0000 150.0000 398.0000			
'trichloroethene'	0.0200	131.4000	0.0760
87.2000 1100.0000 240.0000			
'vinylacetate'	0.0210	86.0000	0.1500
72.0000 2000.0000 0.5000			
'vinylchloride'	0.0210	62.5000	3.5000
13.4000 2670.0000 24.0000			
'Ethylbenzene'	0.0360	106.7000	0.0920
136.2000 152.0000 1410.0000			

Stlbot.out

BioSVE For Window

SOIL VACUUM EXTRACTION CHEMICAL EQUILIBRIUM MODEL
BASED ON JOHNSON ET AL. (1990) GROUND WATER

COPYRIGHT 1995
ASHOK KATYAL, Ph.D.
DRAPER ADEN ENVIRONMENTAL MODELING
BLACKSBURG, VA 24060, U.S.A.

TITLE: ACS Still Bottoms

air flow rate (liters/day)	= .2115E+06
total mass of contaminant (g)	= .6471E+08
maximum simulation time (days)	= .5475E+04
starting time step (days)	= .5000E+00
maximum time step (days)	= .5000E+01
time increment factor	= .10200E+01
printout time interval (days)	= .36500E+03
volumetric water content(fraction)	= .15000E+00
bulk density (g/cm ³)	= .17000E+01
foc	= .50000E-02
contaminated soil vol. (m ³)	= .80500E+02
temperature (C)	= .20000E+02
intercept in free prod.recov.eqn.	= .15000E+01
exponent in free prod. recov. eqn.	= .20000E-01
bio efficiency (fraction)	= .20000E-01
residual oil mass (kg)	= .64710E+04
venting efficiency (fraction)	= .7100E-01

5.10 cfm

SPECIES	VAP PRES atm	BOILING POINT deg C	SOL LIMIT ppm	KOW g/g
benzene	.1000E+00	.8000E+02	.1780E+04	.1350E+03
toluene	.2900E-01	.1110E+03	.5150E+03	.4900E+03

	Stlbot.out			
p-xylene	.8600E-02	.1380E+03	.1980E+03	.1413E+04
111-trichloroethane	.1620E-01	.7410E+02	.1500E+04	.3160E+03
1122-tetrachloroethane	.7000E-02	.1462E+03	.2900E+04	.2450E+03
112-trichloroethane	.4000E-01	.1138E+03	.4500E+04	.2950E+03
11-dichoroethane	.2400E+00	.5750E+02	.5500E+04	.6170E+02
11-dichoroethene	.7900E+00	.3700E+02	.2250E+04	.6920E+02
methylenechloride	.4760E+00	.9370E+02	.2000E+04	.2000E+02
tetrachloroethene	.2400E-02	.1210E+03	.1500E+03	.3980E+03
trichloroethene	.7600E-01	.8720E+02	.1100E+04	.2400E+03
vinylacetate	.1500E+00	.7200E+02	.2000E+04	.5000E+00
vinylchloride	.3500E+01	.1340E+02	.2670E+04	.2400E+02
Ethylbenzene	.9200E-01	.1362E+03	.1520E+03	.1410E+04
MASS FRACTION SUM	1.000000			

SPECIES	MOL WEIGHT g/mol	HENRY COEFF DIMENSIONLESS
benzene	.7810E+02	.0000E+00
toluene	.9210E+02	.0000E+00
p-xylene	.1062E+03	.0000E+00
111-trichloroethane	.1335E+03	.0000E+00
1122-tetrachloroethane	.1678E+03	.0000E+00
112-trichloroethane	.1334E+03	.0000E+00
11-dichoroethane	.1820E+03	.0000E+00
11-dichoroethene	.9694E+02	.0000E+00
methylenechloride	.1067E+03	.0000E+00
tetrachloroethene	.1658E+03	.0000E+00
trichloroethene	.1314E+03	.0000E+00
vinylacetate	.8600E+02	.0000E+00
vinylchloride	.6250E+02	.0000E+00
Ethylbenzene	.1067E+03	.0000E+00
sgmlti	556024.500000	

RESULTS AT TIME (DAYS) 0.000000E+00

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1673E+03	.7742E+06	.3838E+03	.1850E+04
toluene	.1210E+04	.1930E+08	.2348E+04	.4107E+05
p-xylene	.1284E+03	.6910E+07	.2802E+03	.1414E+05
111-trichloroethane	.1197E+03	.3419E+07	.8357E+03	.9428E+04
1122-tetrachloroethane	.3296E+03	.2179E+08	.8191E+04	.7164E+05
112-trichloroethane	.6655E+02	.7700E+06	.5650E+03	.5950E+04
11-dichoroethane	.4017E+03	.7745E+06	.5091E+03	.1121E+04

	Stlbot.out			
11-dichloroethene	.1321E+04	.7739E+06	.3907E+03	.9652E+03
methylenchloride	.1595E+04	.1550E+07	.6322E+03	.4514E+03
tetrachloroethene	.1107E+02	.2135E+07	.4201E+02	.5969E+03
trichloroethene	.2122E+03	.1292E+07	.2352E+03	.2015E+04
vinylacetate	.4401E+03	.1358E+07	.6869E+03	.1226E+02
vinylchloride	.1014E+05	.1341E+07	.4360E+04	.3736E+04
Ethylbenzene	.4623E+03	.2326E+07	.7206E+02	.3627E+04

TOTAL MASS IN ALL PHASE = .6471E+05

TOTAL MASS IN GAS PHASE (kg)	= .1660E+02
TOTAL MASS IN FREE PHASE (kg)	= .6452E+05
TOTAL MASS IN WATER PHASE (kg)	= .1953E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1566E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
g				
benzene	.7766E+06	.0000E+00	.0000E+00	.5675E+04
toluene	.1935E+08	.0000E+00	.0000E+00	.1414E+06
p-xylene	.6924E+07	.0000E+00	.0000E+00	.5060E+05
111-trichloroethane	.3430E+07	.0000E+00	.0000E+00	.2506E+05
1122-tetrachloroethane	.2187E+08	.0000E+00	.0000E+00	.1598E+06
112-trichloroethane	.7766E+06	.0000E+00	.0000E+00	.5675E+04
11-dichloroethane	.7766E+06	.0000E+00	.0000E+00	.5675E+04
11-dichloroethene	.7766E+06	.0000E+00	.0000E+00	.5675E+04
methylenchloride	.1553E+07	.0000E+00	.0000E+00	.1135E+05
tetrachloroethene	.2136E+07	.0000E+00	.0000E+00	.1561E+05
trichloroethene	.1294E+07	.0000E+00	.0000E+00	.9458E+04
vinylacetate	.1359E+07	.0000E+00	.0000E+00	.9931E+04
vinylchloride	.1359E+07	.0000E+00	.0000E+00	.9931E+04
Ethylbenzene	.2330E+07	.0000E+00	.0000E+00	.1702E+05

end of initial conditions

RESULTS AT TIME (DAYS) 368.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1689E+03	.7416E+06	.3876E+03	.1868E+04
toluene	.1259E+04	.1906E+08	.2444E+04	.4275E+05

	Stlbot.out			
p-xylene	.1348E+03	.6883E+07	.2942E+03	.1484E+05
111-trichloroethane	.1253E+03	.3395E+07	.8746E+03	.9866E+04
1122-tetrachloroethane	.3463E+03	.2172E+08	.8605E+04	.7527E+05
112-trichloroethane	.6893E+02	.7566E+06	.5852E+03	.6163E+04
11-dichoroethane	.3821E+03	.6990E+06	.4843E+03	.1067E+04
11-dichoroethene	.9940E+03	.5524E+06	.2940E+03	.7263E+03
methylenechloride	.1372E+04	.1265E+07	.5437E+03	.3882E+03
tetrachloroethene	.1166E+02	.2132E+07	.4423E+02	.6285E+03
trichloroethene	.2164E+03	.1250E+07	.2400E+03	.2056E+04
vinylacetate	.4351E+03	.1273E+07	.6790E+03	.1212E+02
vinylchloride	.2419E+04	.3034E+06	.1040E+04	.8912E+03
Ethylbenzene	.4685E+03	.2236E+07	.7302E+02	.3675E+04

TOTAL MASS IN ALL PHASE = .6246E+05

TOTAL MASS IN GAS PHASE (kg)	= .8402E+01
TOTAL MASS IN FREE PHASE (kg)	= .6227E+05
TOTAL MASS IN WATER PHASE (kg)	= .1659E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1602E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.7441E+06	.4156E+00	.5854E+01	.5437E+04
toluene	.1911E+08	.3097E+01	.4362E+02	.1396E+06
p-xylene	.6898E+07	.3319E+00	.4674E+01	.5041E+05
111-trichloroethane	.3406E+07	.3082E+00	.4341E+01	.2489E+05
1122-tetrachloroethane	.2180E+08	.8518E+00	.1200E+02	.1593E+06
112-trichloroethane	.7634E+06	.1696E+00	.2388E+01	.5578E+04
11-dichoroethane	.7010E+06	.9411E+00	.1325E+02	.5122E+04
11-dichoroethene	.5544E+06	.2456E+01	.3459E+02	.4051E+04
methylenechloride	.1267E+07	.3383E+01	.4764E+02	.9261E+04
tetrachloroethene	.2133E+07	.2863E-01	.4033E+00	.1559E+05
trichloroethene	.1253E+07	.5324E+00	.7499E+01	.9155E+04
vinylacetate	.1275E+07	.1071E+01	.1508E+02	.9313E+04
vinylchloride	.3078E+06	.6072E+01	.8552E+02	.2250E+04
Ethylbenzene	.2240E+07	.1152E+01	.1623E+02	.1637E+05

RESULTS AT TIME (DAYS) 733.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID

Stlbot.out

benzene	.1662E+03	.7097E+06	.3813E+03	.1838E+04
toluene	.1278E+04	.1882E+08	.2481E+04	.4339E+05
p-xylene	.1381E+03	.6855E+07	.3013E+03	.1520E+05
111-trichloroethane	.1279E+03	.3370E+07	.8927E+03	.1007E+05
1122-tetrachloroethane	.3549E+03	.2165E+08	.8819E+04	.7713E+05
112-trichloroethane	.6962E+02	.7432E+06	.5910E+03	.6225E+04
11-dichloroethane	.3536E+03	.6291E+06	.4482E+03	.9872E+03
11-dichloroethene	.7226E+03	.3906E+06	.2137E+03	.5280E+03
methylenchloride	.1144E+04	.1026E+07	.4535E+03	.3238E+03
tetrachloroethene	.1197E+02	.2130E+07	.4542E+02	.6454E+03
trichloroethene	.2152E+03	.1209E+07	.2386E+03	.2044E+04
vinylacetate	.4187E+03	.1192E+07	.6535E+03	.1167E+02
vinylchloride	.5382E+03	.6566E+05	.2314E+03	.1983E+03
Ethylbenzene	.4625E+03	.2147E+07	.7209E+02	.3629E+04

TOTAL MASS IN ALL PHASE = .6112E+05

TOTAL MASS IN GAS PHASE (kg)	= .6002E+01
TOTAL MASS IN FREE PHASE (kg)	= .6093E+05
TOTAL MASS IN WATER PHASE (kg)	= .1582E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1622E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.7121E+06	.4090E+00	.5761E+01	.5203E+04
toluene	.1886E+08	.3143E+01	.4427E+02	.1378E+06
p-xylene	.6871E+07	.3397E+00	.4785E+01	.5021E+05
111-trichloroethane	.3381E+07	.3144E+00	.4428E+01	.2471E+05
1122-tetrachloroethane	.2173E+08	.8729E+00	.1229E+02	.1588E+06
112-trichloroethane	.7501E+06	.1713E+00	.2413E+01	.5481E+04
11-dichloroethane	.6309E+06	.8709E+00	.1227E+02	.4610E+04
11-dichloroethene	.3921E+06	.1786E+01	.2515E+02	.2865E+04
methylenchloride	.1028E+07	.2822E+01	.3975E+02	.7514E+04
tetrachloroethene	.2130E+07	.2940E-01	.4140E+00	.1557E+05
trichloroethene	.1212E+07	.5295E+00	.7458E+01	.8853E+04
vinylacetate	.1193E+07	.1031E+01	.1452E+02	.8718E+04
vinylchloride	.6664E+05	.1352E+01	.1904E+02	.4870E+03
Ethylbenzene	.2151E+07	.1138E+01	.1603E+02	.1572E+05

RESULTS AT TIME (DAYS) 1098.606000

Stlbot.out

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1622E+03	.6784E+06	.3721E+03	.1793E+04
toluene	.1287E+04	.1857E+08	.2499E+04	.4371E+05
p-xylene	.1404E+03	.6827E+07	.3063E+03	.1545E+05
111-trichloroethane	.1295E+03	.3345E+07	.9044E+03	.1020E+05
1122-tetrachloroethane	.3610E+03	.2158E+08	.8971E+04	.7847E+05
112-trichloroethane	.6979E+02	.7299E+06	.5925E+03	.6239E+04
11-dichloroethane	.3240E+03	.5648E+06	.4107E+03	.9047E+03
11-dichloroethene	.5173E+03	.2739E+06	.1530E+03	.3780E+03
methylenechloride	.9429E+03	.8286E+06	.3737E+03	.2669E+03
tetrachloroethene	.1220E+02	.2127E+07	.4631E+02	.6580E+03
trichloroethene	.2123E+03	.1168E+07	.2354E+03	.2017E+04
vinylacetate	.3995E+03	.1114E+07	.6235E+03	.1113E+02
vinylchloride	.1147E+03	.1370E+05	.4930E+02	.4224E+02
Ethylbenzene	.4529E+03	.2059E+07	.7060E+02	.3554E+04

TOTAL MASS IN ALL PHASE = .6006E+05

TOTAL MASS IN GAS PHASE (kg)	= .5126E+01
TOTAL MASS IN FREE PHASE (kg)	= .5988E+05
TOTAL MASS IN WATER PHASE (kg)	= .1561E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1637E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.6808E+06	.3992E+00	.5622E+01	.4975E+04
toluene	.1862E+08	.3167E+01	.4460E+02	.1360E+06
p-xylene	.6843E+07	.3452E+00	.4862E+01	.5001E+05
111-trichloroethane	.3356E+07	.3186E+00	.4487E+01	.2452E+05
1122-tetrachloroethane	.2166E+08	.8890E+00	.1252E+02	.1583E+06
112-trichloroethane	.7368E+06	.1717E+00	.2419E+01	.5384E+04
11-dichloroethane	.5664E+06	.7982E+00	.1124E+02	.4139E+04
11-dichloroethene	.2750E+06	.1279E+01	.1801E+02	.2009E+04
methylenechloride	.8302E+06	.2326E+01	.3276E+02	.6066E+04
tetrachloroethene	.2128E+07	.3001E-01	.4227E+00	.1555E+05
trichloroethene	.1171E+07	.5224E+00	.7357E+01	.8555E+04
vinylacetate	.1115E+07	.9836E+00	.1385E+02	.8149E+04
vinylchloride	.1391E+05	.2882E+00	.4059E+01	.1017E+03

RESULTS AT TIME (DAYS) 1463.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1577E+03	.6480E+06	.3619E+03	.1744E+04
toluene	.1293E+04	.1832E+08	.2510E+04	.4391E+05
p-xylene	.1423E+03	.6799E+07	.3106E+03	.1567E+05
111-trichloroethane	.1309E+03	.3320E+07	.9139E+03	.1031E+05
1122-tetrachloroethane	.3664E+03	.2150E+08	.9103E+04	.7962E+05
112-trichloroethane	.6976E+02	.7165E+06	.5922E+03	.6237E+04
11-dichloroethane	.2956E+03	.5060E+06	.3747E+03	.8252E+03
11-dichloroethene	.3669E+03	.1908E+06	.1085E+03	.2680E+03
methylenechloride	.7718E+03	.6662E+06	.3060E+03	.2184E+03
tetrachloroethene	.1241E+02	.2124E+07	.4709E+02	.6691E+03
trichloroethene	.2087E+03	.1128E+07	.2314E+03	.1983E+04
vinylacetate	.3797E+03	.1040E+07	.5926E+03	.1058E+02
vinylchloride	.2364E+02	.2775E+04	.1017E+02	.8712E+01
Ethylbenzene	.4421E+03	.1974E+07	.6891E+02	.3469E+04

TOTAL MASS IN ALL PHASE = .5912E+05

TOTAL MASS IN GAS PHASE (kg)	=	.4661E+01
TOTAL MASS IN FREE PHASE (kg)	=	.5894E+05
TOTAL MASS IN WATER PHASE (kg)	=	.1553E+02
TOTAL MASS IN SOIL PHASE (kg)	=	.1649E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.6503E+06	.3882E+00	.5468E+01	.4752E+04
toluene	.1837E+08	.3182E+01	.4481E+02	.1342E+06
p-xylene	.6815E+07	.3503E+00	.4934E+01	.4980E+05
111-trichloroethane	.3331E+07	.3220E+00	.4535E+01	.2434E+05
1122-tetrachloroethane	.2159E+08	.9014E+00	.1270E+02	.1578E+06
112-trichloroethane	.7234E+06	.1717E+00	.2418E+01	.5286E+04
11-dichloroethane	.5075E+06	.7281E+00	.1026E+02	.3708E+04
11-dichloroethene	.1915E+06	.9069E+00	.1277E+02	.1400E+04
methylenechloride	.6675E+06	.1904E+01	.2682E+02	.4877E+04

	Stlbot.out			
tetrachloroethene	.2125E+07	.3062E-01	.4313E+00	.1553E+05
trichloroethene	.1131E+07	.5136E+00	.7234E+01	.8262E+04
vinylacetate	.1041E+07	.9349E+00	.1317E+02	.7607E+04
vinylchloride	.2819E+04	.5945E-01	.8374E+00	.2060E+02
Ethylbenzene	.1978E+07	.1088E+01	.1532E+02	.1446E+05

RESULTS AT TIME (DAYS) 1828.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1531E+03	.6184E+06	.3512E+03	.1693E+04
toluene	.1297E+04	.1807E+08	.2518E+04	.4405E+05
p-xylene	.1441E+03	.6771E+07	.3145E+03	.1587E+05
111-trichloroethane	.1321E+03	.3294E+07	.9222E+03	.1040E+05
1122-tetrachloroethane	.3713E+03	.2143E+08	.9225E+04	.8069E+05
112-trichloroethane	.6962E+02	.7031E+06	.5910E+03	.6224E+04
11-dichloroethane	.2688E+03	.4524E+06	.3407E+03	.7504E+03
11-dichloroethene	.2582E+03	.1320E+06	.7636E+02	.1887E+03
methylenchloride	.6286E+03	.5335E+06	.2492E+03	.1779E+03
tetrachloroethene	.1260E+02	.2122E+07	.4783E+02	.6796E+03
trichloroethene	.2048E+03	.1089E+07	.2271E+03	.1946E+04
vinylacetate	.3600E+03	.9696E+06	.5618E+03	.1003E+02
vinylchloride	.4736E+01	.5467E+03	.2037E+01	.1745E+01
Ethylbenzene	.4306E+03	.1891E+07	.6712E+02	.3379E+04

TOTAL MASS IN ALL PHASE = .5826E+05

TOTAL MASS IN GAS PHASE (kg)	= .4336E+01
TOTAL MASS IN FREE PHASE (kg)	= .5808E+05
TOTAL MASS IN WATER PHASE (kg)	= .1549E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1661E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.6206E+06	.3768E+00	.5307E+01	.4535E+04
toluene	.1812E+08	.3191E+01	.4494E+02	.1324E+06
p-xylene	.6787E+07	.3546E+00	.4995E+01	.4959E+05
111-trichloroethane	.3305E+07	.3250E+00	.4577E+01	.2415E+05
1122-tetrachloroethane	.2152E+08	.9138E+00	.1287E+02	.1572E+06

	Stlbot.out			
112-trichloroethane	.7100E+06	.1713E+00	.2413E+01	.5188E+04
11-dichloroethane	.4538E+06	.6621E+00	.9326E+01	.3316E+04
11-dichloroethene	.1326E+06	.6384E+00	.8991E+01	.9687E+03
methylenechloride	.5346E+06	.1551E+01	.2185E+02	.3906E+04
tetrachloroethene	.2122E+07	.3093E-01	.4356E+00	.1551E+05
trichloroethene	.1091E+07	.5041E+00	.7099E+01	.7973E+04
vinylacetate	.9705E+06	.8863E+00	.1248E+02	.7092E+04
vinylchloride	.5554E+03	.1191E-01	.1678E+00	.4058E+01
Ethylbenzene	.1895E+07	.1060E+01	.1493E+02	.1385E+05

RESULTS AT TIME (DAYS) 2193.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1483E+03	.5898E+06	.3403E+03	.1640E+04
toluene	.1300E+04	.1782E+08	.2523E+04	.4414E+05
p-xylene	.1458E+03	.6742E+07	.3182E+03	.1605E+05
111-trichloroethane	.1332E+03	.3268E+07	.9296E+03	.1049E+05
1122-tetrachloroethane	.3759E+03	.2135E+08	.9340E+04	.8170E+05
112-trichloroethane	.6940E+02	.6898E+06	.5891E+03	.6204E+04
11-dichloroethane	.2437E+03	.4038E+06	.3090E+03	.6805E+03
11-dichloroethene	.1805E+03	.9084E+05	.5338E+02	.1319E+03
methylenechloride	.5097E+03	.4258E+06	.2020E+03	.1443E+03
tetrachloroethene	.1279E+02	.2119E+07	.4853E+02	.6896E+03
trichloroethene	.2007E+03	.1050E+07	.2226E+03	.1907E+04
vinylacetate	.3406E+03	.9029E+06	.5316E+03	.9489E+01
vinylchloride	.9230E+00	.1049E+03	.3969E+00	.3401E+00
Ethylbenzene	.4188E+03	.1810E+07	.6528E+02	.3286E+04

TOTAL MASS IN ALL PHASE = .5745E+05

TOTAL MASS IN GAS PHASE (kg)	= .4080E+01
TOTAL MASS IN FREE PHASE (kg)	= .5727E+05
TOTAL MASS IN WATER PHASE (kg)	= .1547E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1671E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	
S	g	g/m3	g/m3	mg/k
benzene	.5919E+06	.3651E+00	.5142E+01	.4325E+04

	Stlbot.out			
toluene	.1787E+08	.3198E+01	.4504E+02	.1306E+06
p-xylene	.6758E+07	.3585E+00	.5050E+01	.4938E+05
111-trichloroethane	.3280E+07	.3277E+00	.4615E+01	.2396E+05
1122-tetrachloroethane	.2144E+08	.9249E+00	.1303E+02	.1567E+06
112-trichloroethane	.6967E+06	.1707E+00	.2405E+01	.5091E+04
11-dichloroethane	.4051E+06	.6005E+00	.8458E+01	.2960E+04
11-dichloroethene	.9121E+05	.4462E+00	.6285E+01	.6665E+03
methylenechloride	.4266E+06	.1258E+01	.1771E+02	.3117E+04
tetrachloroethene	.2120E+07	.3154E-01	.4442E+00	.1549E+05
trichloroethene	.1052E+07	.4940E+00	.6957E+01	.7690E+04
vinylacetate	.9038E+06	.8387E+00	.1181E+02	.6604E+04
vinylchloride	.1066E+03	.2323E-02	.3271E-01	.7786E+00
Ethylbenzene	.1814E+07	.1031E+01	.1452E+02	.1325E+05

RESULTS AT TIME (DAYS) 2558.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1435E+03	.5620E+06	.3293E+03	.1587E+04
toluene	.1301E+04	.1757E+08	.2526E+04	.4419E+05
p-xylene	.1474E+03	.6713E+07	.3217E+03	.1623E+05
111-trichloroethane	.1341E+03	.3242E+07	.9364E+03	.1056E+05
1122-tetrachloroethane	.3803E+03	.2127E+08	.9450E+04	.8266E+05
112-trichloroethane	.6911E+02	.6766E+06	.5867E+03	.6179E+04
11-dichloroethane	.2205E+03	.3598E+06	.2795E+03	.6157E+03
11-dichloroethene	.1253E+03	.6213E+05	.3707E+02	.9157E+02
methylenechloride	.4115E+03	.3385E+06	.1631E+03	.1165E+03
tetrachloroethene	.1297E+02	.2116E+07	.4921E+02	.6993E+03
trichloroethene	.1965E+03	.1012E+07	.2178E+03	.1866E+04
vinylacetate	.3217E+03	.8399E+06	.5021E+03	.8963E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.4068E+03	.1732E+07	.6341E+02	.3192E+04

TOTAL MASS IN ALL PHASE = .5669E+05

TOTAL MASS IN GAS PHASE (kg)	= .3871E+01
TOTAL MASS IN FREE PHASE (kg)	= .5650E+05
TOTAL MASS IN WATER PHASE (kg)	= .1546E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1680E+03

SPECIES	MASS	CONC	CONC	CONC
		WELL GAS	SOIL GAS	SOIL MAS
S				

	Stlbot.out			
g	g	g/m3	g/m3	mg/k
benzene	.5641E+06	.3533E+00	.4975E+01	.4122E+04
toluene	.1762E+08	.3202E+01	.4510E+02	.1288E+06
p-xylene	.6729E+07	.3629E+00	.5111E+01	.4917E+05
111-trichloroethane	.3254E+07	.3299E+00	.4646E+01	.2378E+05
1122-tetrachloroethane	.2137E+08	.9361E+00	.1318E+02	.1561E+06
112-trichloroethane	.6834E+06	.1701E+00	.2395E+01	.4994E+04
11-dichloroethane	.3609E+06	.5433E+00	.7652E+01	.2637E+04
11-dichloroethene	.6238E+05	.3099E+00	.4365E+01	.4558E+03
methylenechloride	.3392E+06	.1015E+01	.1430E+02	.2479E+04
tetrachloroethene	.2117E+07	.3185E-01	.4485E+00	.1547E+05
trichloroethene	.1015E+07	.4835E+00	.6810E+01	.7413E+04
vinylacetate	.8407E+06	.7922E+00	.1116E+02	.6143E+04
vinylchloride	.2882E+02	.0000E+00	.0000E+00	.2106E+00
Ethylbenzene	.1735E+07	.1001E+01	.1410E+02	.1268E+05

RESULTS AT TIME (DAYS) 2923.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1387E+03	.5352E+06	.3182E+03	.1534E+04
toluene	.1302E+04	.1732E+08	.2527E+04	.4421E+05
p-xylene	.1490E+03	.6683E+07	.3251E+03	.1640E+05
111-trichloroethane	.1350E+03	.3216E+07	.9427E+03	.1063E+05
1122-tetrachloroethane	.3846E+03	.2120E+08	.9556E+04	.8358E+05
112-trichloroethane	.6878E+02	.6634E+06	.5839E+03	.6149E+04
11-dichloroethane	.1990E+03	.3200E+06	.2523E+03	.5557E+03
11-dichloroethene	.8650E+02	.4224E+05	.2558E+02	.6320E+02
methylenechloride	.3310E+03	.2683E+06	.1312E+03	.9367E+02
tetrachloroethene	.1315E+02	.2113E+07	.4988E+02	.7087E+03
trichloroethene	.1921E+03	.9752E+06	.2130E+03	.1825E+04
vinylacetate	.3034E+03	.7804E+06	.4735E+03	.8452E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3947E+03	.1655E+07	.6152E+02	.3097E+04

TOTAL MASS IN ALL PHASE = .5596E+05

TOTAL MASS IN GAS PHASE (kg)	= .3698E+01
TOTAL MASS IN FREE PHASE (kg)	= .5577E+05
TOTAL MASS IN WATER PHASE (kg)	= .1546E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1689E+03

Stlbot.out

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.5372E+06	.3414E+00	.4808E+01	.3925E+04
toluene	.1737E+08	.3203E+01	.4512E+02	.1269E+06
p-xylene	.6700E+07	.3664E+00	.5160E+01	.4896E+05
111-trichloroethane	.3228E+07	.3321E+00	.4678E+01	.2358E+05
1122-tetrachloroethane	.2129E+08	.9460E+00	.1332E+02	.1556E+06
112-trichloroethane	.6702E+06	.1692E+00	.2383E+01	.4897E+04
11-dichoroethane	.3210E+06	.4904E+00	.6907E+01	.2346E+04
11-dichoroethene	.4242E+05	.2139E+00	.3013E+01	.3100E+03
methylenchloride	.2688E+06	.8167E+00	.1150E+02	.1964E+04
tetrachloroethene	.2114E+07	.3231E-01	.4550E+00	.1545E+05
trichloroethene	.9775E+06	.4727E+00	.6658E+01	.7143E+04
vinylacetate	.7812E+06	.7471E+00	.1052E+02	.5708E+04
vinylchloride	.2881E+02	.0000E+00	.0000E+00	.2106E+00
Ethylbenzene	.1659E+07	.9714E+00	.1368E+02	.1212E+05

RESULTS AT TIME (DAYS) 3288.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1339E+03	.5092E+06	.3072E+03	.1480E+04
toluene	.1302E+04	.1707E+08	.2527E+04	.4420E+05
p-xylene	.1504E+03	.6653E+07	.3283E+03	.1656E+05
111-trichloroethane	.1359E+03	.3189E+07	.9485E+03	.1070E+05
1122-tetrachloroethane	.3887E+03	.2112E+08	.9659E+04	.8448E+05
112-trichloroethane	.6839E+02	.6503E+06	.5806E+03	.6115E+04
11-dichoroethane	.1793E+03	.2841E+06	.2272E+03	.5005E+03
11-dichoroethene	.5933E+02	.2856E+05	.1755E+02	.4335E+02
methylenchloride	.2651E+03	.2119E+06	.1051E+03	.7504E+02
tetrachloroethene	.1332E+02	.2110E+07	.5053E+02	.7180E+03
trichloroethene	.1876E+03	.9390E+06	.2081E+03	.1783E+04
vinylacetate	.2857E+03	.7244E+06	.4459E+03	.7959E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3825E+03	.1581E+07	.5962E+02	.3001E+04

TOTAL MASS IN ALL PHASE = .5526E+05

TOTAL MASS IN GAS PHASE (kg) = .3552E+01
TOTAL MASS IN FREE PHASE (kg) = .5507E+05
TOTAL MASS IN WATER PHASE (kg) = .1546E+02

Stlbot.out

TOTAL MASS IN SOIL PHASE (kg) = .1697E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.5112E+06	.3296E+00	.4642E+01	.3735E+04
toluene	.1712E+08	.3202E+01	.4510E+02	.1251E+06
p-xylene	.6670E+07	.3699E+00	.5210E+01	.4874E+05
111-trichloroethane	.3201E+07	.3341E+00	.4706E+01	.2339E+05
1122-tetrachloroethane	.2121E+08	.9559E+00	.1346E+02	.1550E+06
112-trichloroethane	.6571E+06	.1683E+00	.2370E+01	.4801E+04
11-dichoroethane	.2850E+06	.4417E+00	.6221E+01	.2083E+04
11-dichoroethene	.2869E+05	.1467E+00	.2067E+01	.2096E+03
methylenechloride	.2123E+06	.6543E+00	.9216E+01	.1551E+04
tetrachloroethene	.2111E+07	.3277E-01	.4615E+00	.1543E+05
trichloroethene	.9412E+06	.4618E+00	.6505E+01	.6878E+04
vinylacetate	.7251E+06	.7035E+00	.9908E+01	.5298E+04
vinylchloride	.2813E+02	.0000E+00	.0000E+00	.2055E+00
Ethylbenzene	.1585E+07	.9414E+00	.1326E+02	.1158E+05

RESULTS AT TIME (DAYS) 3653.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1291E+03	.4842E+06	.2962E+03	.1428E+04
toluene	.1301E+04	.1682E+08	.2525E+04	.4417E+05
p-xylene	.1519E+03	.6623E+07	.3315E+03	.1672E+05
111-trichloroethane	.1366E+03	.3163E+07	.9539E+03	.1076E+05
1122-tetrachloroethane	.3927E+03	.2104E+08	.9759E+04	.8535E+05
112-trichloroethane	.6797E+02	.6373E+06	.5770E+03	.6077E+04
11-dichoroethane	.1612E+03	.2518E+06	.2043E+03	.4499E+03
11-dichoroethene	.4046E+02	.1921E+05	.1197E+02	.2956E+02
methylenechloride	.2116E+03	.1667E+06	.8389E+02	.5990E+02
tetrachloroethene	.1349E+02	.2107E+07	.5118E+02	.7271E+03
trichloroethene	.1831E+03	.9037E+06	.2031E+03	.1740E+04
vinylacetate	.2686E+03	.6716E+06	.4192E+03	.7484E+01
vinylchloride	.2625E+00	.2812E+02	.1129E+00	.9670E-01
Ethylbenzene	.3703E+03	.1510E+07	.5772E+02	.2905E+04

TOTAL MASS IN ALL PHASE = .5459E+05

Stlbot.out

TOTAL MASS IN GAS PHASE (kg) = .3428E+01
 TOTAL MASS IN FREE PHASE (kg) = .5440E+05
 TOTAL MASS IN WATER PHASE (kg) = .1547E+02
 TOTAL MASS IN SOIL PHASE (kg) = .1704E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.4861E+06	.3178E+00	.4477E+01	.3552E+04
toluene	.1687E+08	.3201E+01	.4508E+02	.1233E+06
p-xylene	.6640E+07	.3738E+00	.5265E+01	.4852E+05
111-trichloroethane	.3175E+07	.3361E+00	.4733E+01	.2320E+05
1122-tetrachloroethane	.2114E+08	.9659E+00	.1360E+02	.1544E+06
112-trichloroethane	.6440E+06	.1673E+00	.2356E+01	.4706E+04
11-dichoroethane	.2526E+06	.3971E+00	.5593E+01	.1846E+04
11-dichoroethene	.1929E+05	.1001E+00	.1409E+01	.1409E+03
methylenechloride	.1671E+06	.5223E+00	.7356E+01	.1221E+04
tetrachloroethene	.2108E+07	.3307E-01	.4658E+00	.1541E+05
trichloroethene	.9058E+06	.4507E+00	.6348E+01	.6619E+04
vinylacetate	.6723E+06	.6615E+00	.9316E+01	.4913E+04
vinylchloride	.2812E+02	.0000E+00	.0000E+00	.2055E+00
Ethylbenzene	.1513E+07	.9115E+00	.1284E+02	.1105E+05

RESULTS AT TIME (DAYS) 4018.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1244E+03	.4601E+06	.2854E+03	.1375E+04
toluene	.1299E+04	.1657E+08	.2522E+04	.4411E+05
p-xylene	.1533E+03	.6593E+07	.3345E+03	.1687E+05
111-trichloroethane	.1374E+03	.3136E+07	.9590E+03	.1082E+05
1122-tetrachloroethane	.3967E+03	.2096E+08	.9857E+04	.8621E+05
112-trichloroethane	.6752E+02	.6243E+06	.5732E+03	.6036E+04
11-dichoroethane	.1446E+03	.2228E+06	.1833E+03	.4037E+03
11-dichoroethene	.2743E+02	.1284E+05	.8112E+01	.2004E+02
methylenechloride	.1683E+03	.1308E+06	.6672E+02	.4764E+02
tetrachloroethene	.1365E+02	.2104E+07	.5181E+02	.7362E+03
trichloroethene	.1786E+03	.8692E+06	.1980E+03	.1697E+04
vinylacetate	.2523E+03	.6221E+06	.3937E+03	.7027E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00

Ethylbenzene Stilbot.out
 .3582E+03 .1440E+07 .5583E+02 .2810E+04

TOTAL MASS IN ALL PHASE = .5394E+05

TOTAL MASS IN GAS PHASE (kg) = .3321E+01
 TOTAL MASS IN FREE PHASE (kg) = .5375E+05
 TOTAL MASS IN WATER PHASE (kg) = .1549E+02
 TOTAL MASS IN SOIL PHASE (kg) = .1711E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.4619E+06	.3062E+00	.4313E+01	.3375E+04
toluene	.1662E+08	.3197E+01	.4502E+02	.1214E+06
p-xylene	.6610E+07	.3770E+00	.5310E+01	.4830E+05
111-trichloroethane	.3148E+07	.3380E+00	.4761E+01	.2300E+05
1122-tetrachloroethane	.2106E+08	.9770E+00	.1376E+02	.1539E+06
112-trichloroethane	.6310E+06	.1661E+00	.2340E+01	.4611E+04
11-dichoroethane	.2236E+06	.3562E+00	.5017E+01	.1634E+04
11-dichoroethene	.1290E+05	.6785E-01	.9556E+00	.9426E+02
methylenechloride	.1311E+06	.4154E+00	.5851E+01	.9578E+03
tetrachloroethene	.2105E+07	.3353E-01	.4723E+00	.1538E+05
trichloroethene	.8713E+06	.4396E+00	.6191E+01	.6367E+04
vinylacetate	.6227E+06	.6212E+00	.8749E+01	.4550E+04
vinylchloride	.2743E+02	.0000E+00	.0000E+00	.2005E+00
Ethylbenzene	.1443E+07	.8817E+00	.1242E+02	.1055E+05

RESULTS AT TIME (DAYS) 4383.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1197E+03	.4369E+06	.2747E+03	.1324E+04
toluene	.1297E+04	.1632E+08	.2518E+04	.4404E+05
p-xylene	.1547E+03	.6562E+07	.3375E+03	.1702E+05
111-trichloroethane	.1380E+03	.3109E+07	.9638E+03	.1087E+05
1122-tetrachloroethane	.4005E+03	.2088E+08	.9953E+04	.8705E+05
112-trichloroethane	.6703E+02	.6115E+06	.5690E+03	.5993E+04
11-dichoroethane	.1295E+03	.1969E+06	.1641E+03	.3615E+03
11-dichoroethene	.1849E+02	.8540E+04	.5468E+01	.1351E+02
methylenechloride	.1334E+03	.1023E+06	.5287E+02	.3775E+02

	Stlbot.out			
tetrachloroethene	.1382E+02	.2101E+07	.5245E+02	.7452E+03
trichloroethene	.1740E+03	.8356E+06	.1930E+03	.1653E+04
vinylacetate	.2366E+03	.5756E+06	.3692E+03	.6591E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3462E+03	.1373E+07	.5396E+02	.2716E+04

TOTAL MASS IN ALL PHASE = .5331E+05

TOTAL MASS IN GAS PHASE (kg)	= .3229E+01
TOTAL MASS IN FREE PHASE (kg)	= .5312E+05
TOTAL MASS IN WATER PHASE (kg)	= .1551E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1718E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.4386E+06	.2947E+00	.4151E+01	.3205E+04
toluene	.1637E+08	.3191E+01	.4494E+02	.1196E+06
p-xylene	.6580E+07	.3805E+00	.5359E+01	.4808E+05
111-trichloroethane	.3121E+07	.3398E+00	.4785E+01	.2281E+05
1122-tetrachloroethane	.2098E+08	.9857E+00	.1388E+02	.1533E+06
112-trichloroethane	.6181E+06	.1649E+00	.2323E+01	.4517E+04
11-dichloroethane	.1975E+06	.3190E+00	.4493E+01	.1443E+04
11-dichloroethene	.8578E+04	.4574E-01	.6442E+00	.6268E+02
methylenechloride	.1025E+06	.3292E+00	.4637E+01	.7488E+03
tetrachloroethene	.2102E+07	.3399E-01	.4787E+00	.1536E+05
trichloroethene	.8377E+06	.4283E+00	.6033E+01	.6121E+04
vinylacetate	.5762E+06	.5826E+00	.8206E+01	.4210E+04
vinylchloride	.2675E+02	.0000E+00	.0000E+00	.1954E+00
Ethylbenzene	.1376E+07	.8521E+00	.1200E+02	.1006E+05

RESULTS AT TIME (DAYS) 4748.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1151E+03	.4146E+06	.2642E+03	.1273E+04
toluene	.1294E+04	.1607E+08	.2513E+04	.4395E+05
p-xylene	.1560E+03	.6531E+07	.3404E+03	.1717E+05
111-trichloroethane	.1387E+03	.3083E+07	.9683E+03	.1092E+05
1122-tetrachloroethane	.4044E+03	.2080E+08	.1005E+05	.8788E+05

	Stlbot.out			
112-trichloroethane	.6652E+02	.5987E+06	.5647E+03	.5947E+04
11-dichloroethane	.1157E+03	.1736E+06	.1467E+03	.3231E+03
11-dichloroethene	.1239E+02	.5648E+04	.3665E+01	.9054E+01
methylenechloride	.1053E+03	.7968E+05	.4175E+02	.2981E+02
tetrachloroethene	.1399E+02	.2098E+07	.5307E+02	.7541E+03
trichloroethene	.1695E+03	.8029E+06	.1879E+03	.1610E+04
vinylacetate	.2216E+03	.5320E+06	.3459E+03	.6174E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3343E+03	.1308E+07	.5211E+02	.2623E+04

TOTAL MASS IN ALL PHASE = .5269E+05

TOTAL MASS IN GAS PHASE (kg)	= .3148E+01
TOTAL MASS IN FREE PHASE (kg)	= .5250E+05
TOTAL MASS IN WATER PHASE (kg)	= .1553E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1725E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.4162E+06	.2834E+00	.3992E+01	.3042E+04
toluene	.1612E+08	.3184E+01	.4485E+02	.1178E+06
p-xylene	.6549E+07	.3837E+00	.5404E+01	.4785E+05
111-trichloroethane	.3095E+07	.3412E+00	.4806E+01	.2261E+05
1122-tetrachloroethane	.2090E+08	.9944E+00	.1401E+02	.1527E+06
112-trichloroethane	.6053E+06	.1637E+00	.2305E+01	.4423E+04
11-dichloroethane	.1742E+06	.2851E+00	.4016E+01	.1273E+04
11-dichloroethene	.5673E+04	.3066E-01	.4318E+00	.4146E+02
methylenechloride	.7985E+05	.2600E+00	.3662E+01	.5835E+03
tetrachloroethene	.2099E+07	.3430E-01	.4830E+00	.1534E+05
trichloroethene	.8049E+06	.4171E+00	.5875E+01	.5881E+04
vinylacetate	.5325E+06	.5457E+00	.7686E+01	.3891E+04
vinylchloride	.2674E+02	.0000E+00	.0000E+00	.1954E+00
Ethylbenzene	.1311E+07	.8228E+00	.1159E+02	.9582E+04

RESULTS AT TIME (DAYS) 5113.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1106E+03	.3931E+06	.2538E+03	.1223E+04

	Stlbot.out			
toluene	.1291E+04	.1582E+08	.2507E+04	.4385E+05
p-xylene	.1573E+03	.6500E+07	.3433E+03	.1732E+05
111-trichloroethane	.1393E+03	.3056E+07	.9726E+03	.1097E+05
1122-tetrachloroethane	.4081E+03	.2072E+08	.1014E+05	.8870E+05
112-trichloroethane	.6598E+02	.5861E+06	.5601E+03	.5899E+04
11-dichoroethane	.1032E+03	.1528E+06	.1309E+03	.2882E+03
11-dichoroethene	.8259E+01	.3715E+04	.2443E+01	.6034E+01
methylenechloride	.8289E+02	.6188E+05	.3286E+02	.2346E+02
tetrachloroethene	.1415E+02	.2095E+07	.5370E+02	.7630E+03
trichloroethene	.1649E+03	.7711E+06	.1829E+03	.1567E+04
vinylacetate	.2073E+03	.4912E+06	.3236E+03	.5776E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3226E+03	.1246E+07	.5028E+02	.2531E+04

TOTAL MASS IN ALL PHASE = .5209E+05

TOTAL MASS IN GAS PHASE (kg)	= .3076E+01
TOTAL MASS IN FREE PHASE (kg)	= .5190E+05
TOTAL MASS IN WATER PHASE (kg)	= .1555E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1731E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.3947E+06	.2724E+00	.3836E+01	.2884E+04
toluene	.1587E+08	.3177E+01	.4475E+02	.1160E+06
p-xylene	.6518E+07	.3872E+00	.5453E+01	.4763E+05
111-trichloroethane	.3068E+07	.3427E+00	.4827E+01	.2242E+05
1122-tetrachloroethane	.2082E+08	.1004E+01	.1414E+02	.1521E+06
112-trichloroethane	.5926E+06	.1623E+00	.2286E+01	.4331E+04
11-dichoroethane	.1534E+06	.2544E+00	.3583E+01	.1121E+04
11-dichoroethene	.3731E+04	.2043E-01	.2878E+00	.2727E+02
methylenechloride	.6202E+05	.2046E+00	.2882E+01	.4532E+03
tetrachloroethene	.2096E+07	.3476E-01	.4895E+00	.1532E+05
trichloroethene	.7730E+06	.4059E+00	.5717E+01	.5648E+04
vinylacetate	.4917E+06	.5106E+00	.7191E+01	.3593E+04
vinylchloride	.2606E+02	.0000E+00	.0000E+00	.1904E+00
Ethylbenzene	.1249E+07	.7939E+00	.1118E+02	.9125E+04

RESULTS AT TIME (DAYS) 5478.606000

SPECIESMASS (g) IN PHASES

	Stlbot.out GAS	OIL	WATER	SOLID
benzene	.1062E+03	.3725E+06	.2437E+03	.1174E+04
toluene	.1288E+04	.1558E+08	.2500E+04	.4373E+05
p-xylene	.1586E+03	.6469E+07	.3462E+03	.1746E+05
111-trichloroethane	.1399E+03	.3028E+07	.9767E+03	.1102E+05
1122-tetrachloroethane	.4119E+03	.2063E+08	.1023E+05	.8951E+05
112-trichloroethane	.6542E+02	.5736E+06	.5554E+03	.5849E+04
11-dichloroethane	.9194E+02	.1343E+06	.1165E+03	.2567E+03
11-dichloroethene	.5473E+01	.2430E+04	.1619E+01	.3999E+01
methylenechloride	.6500E+02	.4789E+05	.2577E+02	.1840E+02
tetrachloroethene	.1432E+02	.2092E+07	.5433E+02	.7720E+03
trichloroethene	.1604E+03	.7401E+06	.1778E+03	.1524E+04
vinylacetate	.1938E+03	.4530E+06	.3024E+03	.5398E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3110E+03	.1185E+07	.4847E+02	.2440E+04

TOTAL MASS IN ALL PHASE = .5150E+05

TOTAL MASS IN GAS PHASE (kg)	= .3012E+01
TOTAL MASS IN FREE PHASE (kg)	= .5131E+05
TOTAL MASS IN WATER PHASE (kg)	= .1558E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1738E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.3740E+06	.2615E+00	.3683E+01	.2733E+04
toluene	.1562E+08	.3169E+01	.4464E+02	.1142E+06
p-xylene	.6487E+07	.3899E+00	.5492E+01	.4740E+05
111-trichloroethane	.3041E+07	.3442E+00	.4848E+01	.2222E+05
1122-tetrachloroethane	.2073E+08	.1013E+01	.1427E+02	.1515E+06
112-trichloroethane	.5800E+06	.1610E+00	.2268E+01	.4239E+04
11-dichloroethane	.1348E+06	.2266E+00	.3191E+01	.9851E+03
11-dichloroethene	.2441E+04	.1354E-01	.1907E+00	.1783E+02
methylenechloride	.4800E+05	.1605E+00	.2260E+01	.3508E+03
tetrachloroethene	.2093E+07	.3521E-01	.4960E+00	.1529E+05
trichloroethene	.7419E+06	.3947E+00	.5559E+01	.5421E+04
vinylacetate	.4535E+06	.4772E+00	.6721E+01	.3314E+04
vinylchloride	.2605E+02	.0000E+00	.0000E+00	.1904E+00
Ethylbenzene	.1188E+07	.7656E+00	.1078E+02	.8683E+04

RESULTS AT TIME (DAYS) 5478.606000

Stlbot.out

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1062E+03	.3725E+06	.2437E+03	.1174E+04
toluene	.1288E+04	.1558E+08	.2500E+04	.4373E+05
p-xylene	.1586E+03	.6469E+07	.3462E+03	.1746E+05
111-trichloroethane	.1399E+03	.3028E+07	.9767E+03	.1102E+05
1122-tetrachloroethane	.4119E+03	.2063E+08	.1023E+05	.8951E+05
112-trichloroethane	.6542E+02	.5736E+06	.5554E+03	.5849E+04
11-dichloroethane	.9194E+02	.1343E+06	.1165E+03	.2567E+03
11-dichloroethene	.5473E+01	.2430E+04	.1619E+01	.3999E+01
methylenechloride	.6500E+02	.4789E+05	.2577E+02	.1840E+02
tetrachloroethene	.1432E+02	.2092E+07	.5433E+02	.7720E+03
trichloroethene	.1604E+03	.7401E+06	.1778E+03	.1524E+04
vinylacetate	.1938E+03	.4530E+06	.3024E+03	.5398E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3110E+03	.1185E+07	.4847E+02	.2440E+04


TOTAL MASS IN ALL PHASE = .5150E+05

TOTAL MASS IN GAS PHASE (kg)	= .3012E+01
TOTAL MASS IN FREE PHASE (kg)	= .5131E+05
TOTAL MASS IN WATER PHASE (kg)	= .1558E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1738E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	
S				SOIL MAS
g	g	g/m3	g/m3	mg/k
benzene	.3740E+06	.2615E+00	.3683E+01	.2733E+04
toluene	.1562E+08	.3169E+01	.4464E+02	.1142E+06
p-xylene	.6487E+07	.3899E+00	.5492E+01	.4740E+05
111-trichloroethane	.3041E+07	.3442E+00	.4848E+01	.2222E+05
1122-tetrachloroethane	.2073E+08	.1013E+01	.1427E+02	.1515E+06
112-trichloroethane	.5800E+06	.1610E+00	.2268E+01	.4239E+04
11-dichloroethane	.1348E+06	.2266E+00	.3191E+01	.9851E+03
11-dichloroethene	.2441E+04	.1354E-01	.1907E+00	.1783E+02
methylenechloride	.4800E+05	.1605E+00	.2260E+01	.3508E+03
tetrachloroethene	.2093E+07	.3521E-01	.4960E+00	.1529E+05
trichloroethene	.7419E+06	.3947E+00	.5559E+01	.5421E+04
vinylacetate	.4535E+06	.4772E+00	.6721E+01	.3314E+04


	Stlbot.out			
vinylchloride	.2605E+02	.0000E+00	.0000E+00	.1904E+00
Ethylbenzene	.1188E+07	.7656E+00	.1078E+02	.8683E+04

ACS Still Bottoms



5.2 darcy

ACS Still Bottoms



Stlbot.out

```
+ + + + +  
+  
+ BiosVE For Window  
+  
+ SOIL VACUUM EXTRACTION CHEMICAL EQUILIBRIUM MODEL  
+ BASED ON JOHNSON ET AL. (1990) GROUND WATER  
+  
+  
+  
+  
+ COPYRIGHT 1995  
+ ASHOK KATYAL, Ph.D.  
+ DRAPER ADEN ENVIRONMENTAL MODELING  
+ BLACKSBURG, VA 24060, U.S.A.  
+  
+ + + + +
```

TITLE: ACS Still Bottoms

— — — — —

```

air flow rate      (liters/day)      = .6284E+06
total mass of contaminant (g)        = .6471E+08
maximum simulation time (days)       = .5475E+04
starting time step (days)           = .5000E+00
maximum time step (days)            = .5000E+01
time increment factor                 = .1020E+01
printout time interval (days)       = .3650E+03
volumetric water content(fraction)   = .1500E+00
bulk density (g/cm^3)               = .1700E+01
foc                                  = .5000E-02
contaminated soil vol. (m^3)         = .8050E+02
temperature (C)                      = .2000E+02
intercept in free prod.recov.eqn.   = .1500E+01
exponent in free prod. recov. eqn.  = .2000E-01
bio efficiency (fraction)            = .2000E-01
residual oil mass (kg)               = .6471E+04
venting efficiency (fraction)        = .7100E-01

```

SPECIES	VAP PRES atm	BOILING POINT deg C	SOL LIMIT ppm	KOW g/g
benzene	.1000E+00	.8000E+02	.1780E+04	.1350E+03
toluene	.2900E-01	.1110E+03	.5150E+03	.4900E+03

	Stlbot.out			
p-xylene	.8600E-02	.1380E+03	.1980E+03	.1413E+04
111-trichloroethane	.1620E-01	.7410E+02	.1500E+04	.3160E+03
1122-tetrachloroethane	.7000E-02	.1462E+03	.2900E+04	.2450E+03
112-trichloroethane	.4000E-01	.1138E+03	.4500E+04	.2950E+03
11-dichoroethane	.2400E+00	.5750E+02	.5500E+04	.6170E+02
11-dichoroethene	.7900E+00	.3700E+02	.2250E+04	.6920E+02
methylenechloride	.4760E+00	.9370E+02	.2000E+04	.2000E+02
tetrachloroethene	.2400E-02	.1210E+03	.1500E+03	.3980E+03
trichloroethene	.7600E-01	.8720E+02	.1100E+04	.2400E+03
vinylacetate	.1500E+00	.7200E+02	.2000E+04	.5000E+00
vinylchloride	.3500E+01	.1340E+02	.2670E+04	.2400E+02
Ethylbenzene	.9200E-01	.1362E+03	.1520E+03	.1410E+04
MASS FRACTION SUM	1.000000			

SPECIES	MOL WEIGHT g/mol	HENRY COEFF DIMENSIONLESS
benzene	.7810E+02	.0000E+00
toluene	.9210E+02	.0000E+00
p-xylene	.1062E+03	.0000E+00
111-trichloroethane	.1335E+03	.0000E+00
1122-tetrachloroethane	.1678E+03	.0000E+00
112-trichloroethane	.1334E+03	.0000E+00
11-dichoroethane	.1820E+03	.0000E+00
11-dichoroethene	.9694E+02	.0000E+00
methylenechloride	.1067E+03	.0000E+00
tetrachloroethene	.1658E+03	.0000E+00
trichloroethene	.1314E+03	.0000E+00
vinylacetate	.8600E+02	.0000E+00
vinylchloride	.6250E+02	.0000E+00
Ethylbenzene	.1067E+03	.0000E+00
sgmlti	556024.500000	

RESULTS AT TIME (DAYS) 0.000000E+00

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1673E+03	.7742E+06	.3838E+03	.1850E+04
toluene	.1210E+04	.1930E+08	.2348E+04	.4107E+05
p-xylene	.1284E+03	.6910E+07	.2802E+03	.1414E+05
111-trichloroethane	.1197E+03	.3419E+07	.8357E+03	.9428E+04
1122-tetrachloroethane	.3296E+03	.2179E+08	.8191E+04	.7164E+05
112-trichloroethane	.6655E+02	.7700E+06	.5650E+03	.5950E+04
11-dichoroethane	.4017E+03	.7745E+06	.5091E+03	.1121E+04

	Stlbot.out			
11-dichoroethene	.1321E+04	.7739E+06	.3907E+03	.9652E+03
methylenchloride	.1595E+04	.1550E+07	.6322E+03	.4514E+03
tetrachloroethene	.1107E+02	.2135E+07	.4201E+02	.5969E+03
trichloroethene	.2122E+03	.1292E+07	.2352E+03	.2015E+04
vinylacetate	.4401E+03	.1358E+07	.6869E+03	.1226E+02
vinylchloride	.1014E+05	.1341E+07	.4360E+04	.3736E+04
Ethylbenzene	.4623E+03	.2326E+07	.7206E+02	.3627E+04

TOTAL MASS IN ALL PHASE = .6471E+05

TOTAL MASS IN GAS PHASE (kg)	= .1660E+02
TOTAL MASS IN FREE PHASE (kg)	= .6452E+05
TOTAL MASS IN WATER PHASE (kg)	= .1953E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1566E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.7766E+06	.0000E+00	.0000E+00	.5675E+04
toluene	.1935E+08	.0000E+00	.0000E+00	.1414E+06
p-xylene	.6924E+07	.0000E+00	.0000E+00	.5060E+05
111-trichloroethane	.3430E+07	.0000E+00	.0000E+00	.2506E+05
1122-tetrachloroethane	.2187E+08	.0000E+00	.0000E+00	.1598E+06
112-trichloroethane	.7766E+06	.0000E+00	.0000E+00	.5675E+04
11-dichoroethane	.7766E+06	.0000E+00	.0000E+00	.5675E+04
11-dichoroethene	.7766E+06	.0000E+00	.0000E+00	.5675E+04
methylenchloride	.1553E+07	.0000E+00	.0000E+00	.1135E+05
tetrachloroethene	.2136E+07	.0000E+00	.0000E+00	.1561E+05
trichloroethene	.1294E+07	.0000E+00	.0000E+00	.9458E+04
vinylacetate	.1359E+07	.0000E+00	.0000E+00	.9931E+04
vinylchloride	.1359E+07	.3885E-03	.5472E-02	.9931E+04
Ethylbenzene	.2330E+07	.0000E+00	.0000E+00	.1702E+05
end of initial conditions				

RESULTS AT TIME (DAYS) 368.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1621E+03	.6788E+06	.3718E+03	.1792E+04
toluene	.1286E+04	.1857E+08	.2496E+04	.4367E+05

	Stlbot.out			
p-xylene	.1402E+03	.6828E+07	.3060E+03	.1543E+05
111-trichloroethane	.1294E+03	.3345E+07	.9034E+03	.1019E+05
1122-tetrachloroethane	.3606E+03	.2158E+08	.8961E+04	.7838E+05
112-trichloroethane	.6972E+02	.7300E+06	.5919E+03	.6233E+04
11-dichloroethane	.3240E+03	.5654E+06	.4107E+03	.9045E+03
11-dichloroethene	.5174E+03	.2743E+06	.1530E+03	.3780E+03
methylenechloride	.9432E+03	.8299E+06	.3739E+03	.2669E+03
tetrachloroethene	.1219E+02	.2127E+07	.4625E+02	.6572E+03
trichloroethene	.2121E+03	.1169E+07	.2352E+03	.2015E+04
vinylacetate	.3993E+03	.1115E+07	.6232E+03	.1112E+02
vinylchloride	.1098E+03	.1314E+05	.4723E+02	.4047E+02
Ethylbenzene	.4526E+03	.2061E+07	.7055E+02	.3551E+04

TOTAL MASS IN ALL PHASE = .6007E+05

TOTAL MASS IN GAS PHASE (kg)	= .5119E+01
TOTAL MASS IN FREE PHASE (kg)	= .5989E+05
TOTAL MASS IN WATER PHASE (kg)	= .1559E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1635E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.6811E+06	.3992E+00	.5622E+01	.4977E+04
toluene	.1862E+08	.3163E+01	.4456E+02	.1361E+06
p-xylene	.6844E+07	.3447E+00	.4855E+01	.5001E+05
111-trichloroethane	.3357E+07	.3182E+00	.4481E+01	.2453E+05
1122-tetrachloroethane	.2166E+08	.8868E+00	.1249E+02	.1583E+06
112-trichloroethane	.7369E+06	.1715E+00	.2416E+01	.5385E+04
11-dichloroethane	.5670E+06	.8000E+00	.1127E+02	.4144E+04
11-dichloroethene	.2753E+06	.1291E+01	.1818E+02	.2012E+04
methylenechloride	.8315E+06	.2339E+01	.3295E+02	.6076E+04
tetrachloroethene	.2128E+07	.2994E-01	.4217E+00	.1555E+05
trichloroethene	.1171E+07	.5221E+00	.7354E+01	.8559E+04
vinylacetate	.1116E+07	.9844E+00	.1386E+02	.8155E+04
vinylchloride	.1335E+05	.2883E+00	.4061E+01	.9759E+02
Ethylbenzene	.2065E+07	.1115E+01	.1570E+02	.1509E+05

RESULTS AT TIME (DAYS) 733.606000

SPECIESMASS (g) IN PHASES
	GAS OIL WATER SOLID

Stlbot.out

benzene	.1484E+03	.5910E+06	.3405E+03	.1641E+04
toluene	.1299E+04	.1783E+08	.2521E+04	.4410E+05
p-xylene	.1456E+03	.6743E+07	.3178E+03	.1603E+05
111-trichloroethane	.1330E+03	.3269E+07	.9286E+03	.1048E+05
1122-tetrachloroethane	.3754E+03	.2136E+08	.9328E+04	.8159E+05
112-trichloroethane	.6935E+02	.6904E+06	.5888E+03	.6200E+04
11-dichloroethane	.2444E+03	.4056E+06	.3098E+03	.6825E+03
11-dichloroethene	.1817E+03	.9160E+05	.5374E+02	.1328E+03
methylenechloride	.5125E+03	.4288E+06	.2032E+03	.1451E+03
tetrachloroethene	.1277E+02	.2119E+07	.4846E+02	.6886E+03
trichloroethene	.2007E+03	.1052E+07	.2226E+03	.1907E+04
vinylacetate	.3411E+03	.9056E+06	.5324E+03	.9503E+01
vinylchloride	.8397E+00	.9554E+02	.3611E+00	.3094E+00
Ethylbenzene	.4190E+03	.1814E+07	.6531E+02	.3287E+04

TOTAL MASS IN ALL PHASE = .5749E+05

TOTAL MASS IN GAS PHASE (kg)	= .4084E+01
TOTAL MASS IN FREE PHASE (kg)	= .5730E+05
TOTAL MASS IN WATER PHASE (kg)	= .1546E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1669E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
	g	g/m3	g/m3	mg/k
benzene	.5931E+06	.3656E+00	.5149E+01	.4334E+04
toluene	.1788E+08	.3195E+01	.4500E+02	.1307E+06
p-xylene	.6760E+07	.3581E+00	.5043E+01	.4940E+05
111-trichloroethane	.3281E+07	.3271E+00	.4608E+01	.2397E+05
1122-tetrachloroethane	.2145E+08	.9231E+00	.1300E+02	.1567E+06
112-trichloroethane	.6973E+06	.1707E+00	.2404E+01	.5095E+04
11-dichloroethane	.4068E+06	.6038E+00	.8504E+01	.2973E+04
11-dichloroethene	.9197E+05	.4537E+00	.6390E+01	.6721E+03
methylenechloride	.4297E+06	.1272E+01	.1791E+02	.3140E+04
tetrachloroethene	.2120E+07	.3143E-01	.4427E+00	.1549E+05
trichloroethene	.1054E+07	.4943E+00	.6962E+01	.7703E+04
vinylacetate	.9065E+06	.8412E+00	.1185E+02	.6624E+04
vinylchloride	.9716E+02	.2212E-02	.3116E-01	.7100E+00
Ethylbenzene	.1817E+07	.1032E+01	.1454E+02	.1328E+05

RESULTS AT TIME (DAYS) 1098.606000

Stlbot.out

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1341E+03	.5111E+06	.3078E+03	.1483E+04
toluene	.1301E+04	.1709E+08	.2525E+04	.4417E+05
p-xylene	.1502E+03	.6656E+07	.3278E+03	.1654E+05
111-trichloroethane	.1357E+03	.3192E+07	.9474E+03	.1069E+05
1122-tetrachloroethane	.3881E+03	.2113E+08	.9644E+04	.8435E+05
112-trichloroethane	.6837E+02	.6513E+06	.5804E+03	.6113E+04
11-dichloroethane	.1804E+03	.2864E+06	.2286E+03	.5036E+03
11-dichloroethene	.6016E+02	.2902E+05	.1779E+02	.4396E+02
methylenechloride	.2681E+03	.2146E+06	.1063E+03	.7588E+02
tetrachloroethene	.1329E+02	.2111E+07	.5045E+02	.7168E+03
trichloroethene	.1878E+03	.9417E+06	.2083E+03	.1784E+04
vinylacetate	.2867E+03	.7282E+06	.4474E+03	.7986E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3831E+03	.1587E+07	.5971E+02	.3006E+04

TOTAL MASS IN ALL PHASE = .5531E+05

TOTAL MASS IN GAS PHASE (kg)	= .3557E+01
TOTAL MASS IN FREE PHASE (kg)	= .5513E+05
TOTAL MASS IN WATER PHASE (kg)	= .1545E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1695E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.5131E+06	.3305E+00	.4655E+01	.3749E+04
toluene	.1714E+08	.3201E+01	.4508E+02	.1252E+06
p-xylene	.6673E+07	.3696E+00	.5205E+01	.4876E+05
111-trichloroethane	.3203E+07	.3338E+00	.4701E+01	.2341E+05
1122-tetrachloroethane	.2122E+08	.9544E+00	.1344E+02	.1551E+06
112-trichloroethane	.6581E+06	.1683E+00	.2370E+01	.4809E+04
11-dichloroethane	.2873E+06	.4457E+00	.6277E+01	.2099E+04
11-dichloroethene	.2914E+05	.1503E+00	.2117E+01	.2129E+03
methylenechloride	.2151E+06	.6657E+00	.9376E+01	.1572E+04
tetrachloroethene	.2111E+07	.3272E-01	.4609E+00	.1543E+05
trichloroethene	.9439E+06	.4626E+00	.6515E+01	.6897E+04
vinylacetate	.7290E+06	.7071E+00	.9959E+01	.5327E+04
vinylchloride	.2775E+02	.0000E+00	.0000E+00	.2028E+00

Ethylbenzene

Stlbot.out

.1590E+07

.9437E+00

1.1329E+02

1162E+05

RESULTS AT TIME (DAYS)

1463.606000

SPECIES

.....MASS (σ) IN PHASES

GAS

OIL

WATER

SOLID

benzene	.1201E+03	.4393E+06	.2756E+03	.1328E+04
toluene	.1296E+04	.1635E+08	.2516E+04	.4402E+05
p-xylene	.1544E+03	.6566E+07	.3370E+03	.1700E+05
111-trichloroethane	.1379E+03	.3113E+07	.9626E+03	.1086E+05
1122-tetrachloroethane	.3998E+03	.2089E+08	.9936E+04	.8690E+05
112-trichloroethane	.6703E+02	.6129E+06	.5691E+03	.5993E+04
11-dichloroethane	.1307E+03	.1992E+06	.1657E+03	.3649E+03
11-dichloroethene	.1889E+02	.8744E+04	.5586E+01	.1380E+02
methylenechloride	.1357E+03	.1042E+06	.5378E+02	.3840E+02
tetrachloroethene	.1379E+02	.2102E+07	.5234E+02	.7437E+03
trichloroethene	.1744E+03	.8392E+06	.1934E+03	.1657E+04
vinylacetate	.2379E+03	.5801E+06	.3713E+03	.6628E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3472E+03	.1380E+07	.5411E+02	.2724E+04

TOTAL MASS IN ALL PHASE = .5338E+05

```

TOTAL MASS IN GAS PHASE (kg)      = .3234E+01
TOTAL MASS IN FREE PHASE (kg)     = .5319E+05
TOTAL MASS IN WATER PHASE (kg)    = .1549E+02
TOTAL MASS IN SOIL PHASE (kg)     = .1716E+03

```

SPECIES

MASS

CONC
WELL GAS

CONC
SOIL GAS

CONC
SOIL MAS

S

g

 g/m^3 g / m³

mg / k

g

benzene	.4410E+06	.2960E+00	.4169E+01	.3223E+04
toluene	.1640E+08	.3190E+01	.4493E+02	.1198E+06
p-xylene	.6584E+07	.3797E+00	.5348E+01	.4811E+05
111-trichloroethane	.3125E+07	.3391E+00	.4776E+01	.2283E+05
1122-tetrachloroethane	.2099E+08	.9832E+00	.1385E+02	.1534E+06
112-trichloroethane	.6195E+06	.1650E+00	.2324E+01	.4527E+04
11-dichloroethane	.1998E+06	.3230E+00	.4549E+01	.1460E+04
11-dichloroethene	.8783E+04	.4723E-01	.6652E+00	.6418E+02
methylenedichloride	.1045E+06	.3370E+00	.4747E+01	.7634E+03

	Stlbot.out			
tetrachloroethene	.2103E+07	.3391E-01	.4776E+00	.1537E+05
trichloroethene	.8412E+06	.4295E+00	.6049E+01	.6147E+04
vinylacetate	.5807E+06	.5869E+00	.8266E+01	.4243E+04
vinylchloride	.2570E+02	.0000E+00	.0000E+00	.1878E+00
Ethylbenzene	.1383E+07	.8553E+00	.1205E+02	.1011E+05

RESULTS AT TIME (DAYS) 1828.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1067E+03	.3753E+06	.2449E+03	.1180E+04
toluene	.1288E+04	.1561E+08	.2499E+04	.4372E+05
p-xylene	.1583E+03	.6474E+07	.3456E+03	.1743E+05
111-trichloroethane	.1397E+03	.3033E+07	.9755E+03	.1100E+05
1122-tetrachloroethane	.4111E+03	.2065E+08	.1021E+05	.8934E+05
112-trichloroethane	.6545E+02	.5753E+06	.5556E+03	.5852E+04
11-dichloroethane	.9315E+02	.1365E+06	.1181E+03	.2601E+03
11-dichloroethene	.5636E+01	.2508E+04	.1667E+01	.4118E+01
methylenechloride	.6654E+02	.4916E+05	.2638E+02	.1883E+02
tetrachloroethene	.1429E+02	.2093E+07	.5421E+02	.7702E+03
trichloroethene	.1609E+03	.7443E+06	.1784E+03	.1528E+04
vinylacetate	.1953E+03	.4578E+06	.3048E+03	.5441E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3123E+03	.1194E+07	.4868E+02	.2450E+04

TOTAL MASS IN ALL PHASE = .5159E+05

TOTAL MASS IN GAS PHASE (kg)	= .3017E+01
TOTAL MASS IN FREE PHASE (kg)	= .5139E+05
TOTAL MASS IN WATER PHASE (kg)	= .1557E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1736E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
g				
benzene	.3768E+06	.2630E+00	.3704E+01	.2753E+04
toluene	.1566E+08	.3169E+01	.4463E+02	.1144E+06
p-xylene	.6492E+07	.3895E+00	.5486E+01	.4744E+05
111-trichloroethane	.3045E+07	.3437E+00	.4841E+01	.2225E+05
1122-tetrachloroethane	.2075E+08	.1011E+01	.1424E+02	.1516E+06

	Stlbot.out			
112-trichloroethane	.5818E+06	.1611E+00	.2269E+01	.4252E+04
11-dichloroethane	.1369E+06	.2303E+00	.3243E+01	.1001E+04
11-dichloroethene	.2520E+04	.1410E-01	.1986E+00	.1842E+02
methylenechloride	.4927E+05	.1654E+00	.2329E+01	.3600E+03
tetrachloroethene	.2094E+07	.3515E-01	.4950E+00	.1530E+05
trichloroethene	.7461E+06	.3962E+00	.5581E+01	.5452E+04
vinylacetate	.4583E+06	.4818E+00	.6787E+01	.3349E+04
vinylchloride	.2569E+02	.0000E+00	.0000E+00	.1877E+00
Ethylbenzene	.1196E+07	.7695E+00	.1084E+02	.8742E+04

RESULTS AT TIME (DAYS) 2193.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.9415E+02	.3186E+06	.2160E+03	.1041E+04
toluene	.1275E+04	.1488E+08	.2476E+04	.4331E+05
p-xylene	.1622E+03	.6380E+07	.3539E+03	.1785E+05
111-trichloroethane	.1413E+03	.2951E+07	.9866E+03	.1113E+05
1122-tetrachloroethane	.4220E+03	.2040E+08	.1049E+05	.9172E+05
112-trichloroethane	.6369E+02	.5388E+06	.5407E+03	.5694E+04
11-dichloroethane	.6535E+02	.9213E+05	.8283E+02	.1824E+03
11-dichloroethene	.1599E+01	.6847E+03	.4728E+00	.1168E+01
methylenechloride	.3165E+02	.2250E+05	.1255E+02	.8957E+01
tetrachloroethene	.1478E+02	.2084E+07	.5608E+02	.7968E+03
trichloroethene	.1476E+03	.6570E+06	.1636E+03	.1402E+04
vinylacetate	.1587E+03	.3579E+06	.2476E+03	.4421E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.2791E+03	.1026E+07	.4350E+02	.2189E+04

TOTAL MASS IN ALL PHASE = .4990E+05

TOTAL MASS IN GAS PHASE (kg)	= .2857E+01
TOTAL MASS IN FREE PHASE (kg)	= .4971E+05
TOTAL MASS IN WATER PHASE (kg)	= .1567E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1753E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.3199E+06	.2321E+00	.3268E+01	.2338E+04

	Stlbot.out			
toluene	.1493E+08	.3138E+01	.4420E+02	.1091E+06
p-xylene	.6398E+07	.3987E+00	.5616E+01	.4675E+05
111-trichloroethane	.2964E+07	.3476E+00	.4896E+01	.2166E+05
1122-tetrachloroethane	.2050E+08	.1038E+01	.1462E+02	.1498E+06
112-trichloroethane	.5451E+06	.1568E+00	.2208E+01	.3983E+04
11-dichloroethane	.9246E+05	.1616E+00	.2276E+01	.6756E+03
11-dichloroethene	.6880E+03	.4003E-02	.5638E-01	.5028E+01
methylenechloride	.2255E+05	.7868E-01	.1108E+01	.1648E+03
tetrachloroethene	.2084E+07	.3633E-01	.5117E+00	.1523E+05
trichloroethene	.6587E+06	.3635E+00	.5119E+01	.4813E+04
vinylacetate	.3584E+06	.3915E+00	.5515E+01	.2619E+04
vinylchloride	.2365E+02	.0000E+00	.0000E+00	.1728E+00
Ethylbenzene	.1029E+07	.6876E+00	.9685E+01	.7518E+04

RESULTS AT TIME (DAYS) 2558.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.8249E+02	.2687E+06	.1893E+03	.9121E+03
toluene	.1260E+04	.1416E+08	.2446E+04	.4279E+05
p-xylene	.1659E+03	.6283E+07	.3620E+03	.1826E+05
111-trichloroethane	.1427E+03	.2870E+07	.9963E+03	.1124E+05
1122-tetrachloroethane	.4329E+03	.2014E+08	.1076E+05	.9408E+05
112-trichloroethane	.6179E+02	.5032E+06	.5246E+03	.5524E+04
11-dichloroethane	.4513E+02	.6125E+05	.5720E+02	.1260E+03
11-dichloroethene	.4309E+00	.1777E+03	.1274E+00	.3148E+00
methylenechloride	.1459E+02	.9987E+04	.5784E+01	.4130E+01
tetrachloroethene	.1528E+02	.2074E+07	.5798E+02	.8238E+03
trichloroethene	.1346E+03	.5771E+06	.1493E+03	.1279E+04
vinylacetate	.1276E+03	.2772E+06	.1992E+03	.3556E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.2478E+03	.8774E+06	.3862E+02	.1944E+04

TOTAL MASS IN ALL PHASE = .4830E+05

TOTAL MASS IN GAS PHASE (kg)	= .2732E+01
TOTAL MASS IN FREE PHASE (kg)	= .4810E+05
TOTAL MASS IN WATER PHASE (kg)	= .1578E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1770E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	
S				

	Stlbot.out			
g	g	g/m3	g/m3	mg/k
benzene	.2699E+06	.2033E+00	.2864E+01	.1972E+04
toluene	.1420E+08	.3101E+01	.4368E+02	.1038E+06
p-xylene	.6302E+07	.4080E+00	.5746E+01	.4605E+05
111-trichloroethane	.2882E+07	.3510E+00	.4944E+01	.2106E+05
1122-tetrachloroethane	.2025E+08	.1065E+01	.1499E+02	.1480E+06
112-trichloroethane	.5093E+06	.1521E+00	.2142E+01	.3722E+04
11-dichloroethane	.6148E+05	.1116E+00	.1572E+01	.4492E+03
11-dichloroethene	.1786E+03	.1080E-02	.1521E-01	.1305E+01
methylenechloride	.1001E+05	.3629E-01	.5112E+00	.7316E+02
tetrachloroethene	.2075E+07	.3757E-01	.5291E+00	.1516E+05
trichloroethene	.5787E+06	.3317E+00	.4672E+01	.4229E+04
vinylacetate	.2775E+06	.3150E+00	.4436E+01	.2028E+04
vinylchloride	.2364E+02	.0000E+00	.0000E+00	.1727E+00
Ethylbenzene	.8796E+06	.6107E+00	.8601E+01	.6428E+04

RESULTS AT TIME (DAYS) 2923.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.7179E+02	.2252E+06	.1647E+03	.7938E+03
toluene	.1243E+04	.1344E+08	.2412E+04	.4220E+05
p-xylene	.1695E+03	.6184E+07	.3700E+03	.1866E+05
111-trichloroethane	.1439E+03	.2787E+07	.1005E+04	.1134E+05
1122-tetrachloroethane	.4437E+03	.1988E+08	.1102E+05	.9642E+05
112-trichloroethane	.5978E+02	.4688E+06	.5075E+03	.5345E+04
11-dichloroethane	.3067E+02	.4009E+05	.3887E+02	.8562E+02
11-dichloroethene	.1102E+00	.4375E+02	.3259E-01	.8050E-01
methylenechloride	.6519E+01	.4296E+04	.2584E+01	.1845E+01
tetrachloroethene	.1579E+02	.2064E+07	.5991E+02	.8513E+03
trichloroethene	.1222E+03	.5044E+06	.1355E+03	.1161E+04
vinylacetate	.1016E+03	.2125E+06	.1586E+03	.2831E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.2187E+03	.7456E+06	.3408E+02	.1716E+04

TOTAL MASS IN ALL PHASE = .4676E+05

TOTAL MASS IN GAS PHASE (kg)	= .2627E+01
TOTAL MASS IN FREE PHASE (kg)	= .4656E+05
TOTAL MASS IN WATER PHASE (kg)	= .1591E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1786E+03

Stlbot.out

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S.	g	g/m3	g/m3	mg/k
benzene	.2262E+06	.1770E+00	.2492E+01	.1653E+04
toluene	.1349E+08	.3059E+01	.4308E+02	.9857E+05
p-xylene	.6204E+07	.4170E+00	.5873E+01	.4533E+05
111-trichloroethane	.2799E+07	.3541E+00	.4987E+01	.2046E+05
1122-tetrachloroethane	.1999E+08	.1091E+01	.1536E+02	.1461E+06
112-trichloroethane	.4747E+06	.1471E+00	.2072E+01	.3469E+04
11-dichloroethane	.4024E+05	.7586E-01	.1068E+01	.2941E+03
11-dichloroethene	.4398E+02	.2763E-03	.3891E-02	.3214E+00
methylenechloride	.4307E+04	.1622E-01	.2284E+00	.3147E+02
tetrachloroethene	.2065E+07	.3886E-01	.5473E+00	.1509E+05
trichloroethene	.5059E+06	.3011E+00	.4241E+01	.3696E+04
vinylacetate	.2128E+06	.2508E+00	.3533E+01	.1555E+04
vinylchloride	.2159E+02	.0000E+00	.0000E+00	.1578E+00
Ethylbenzene	.7475E+06	.5389E+00	.7590E+01	.5462E+04

RESULTS AT TIME (DAYS) 3288.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.6205E+02	.1875E+06	.1424E+03	.6861E+03
toluene	.1223E+04	.1274E+08	.2374E+04	.4152E+05
p-xylene	.1732E+03	.6084E+07	.3779E+03	.1906E+05
111-trichloroethane	.1450E+03	.2704E+07	.1012E+04	.1142E+05
1122-tetrachloroethane	.4545E+03	.1961E+08	.1129E+05	.9877E+05
112-trichloroethane	.5767E+02	.4356E+06	.4896E+03	.5156E+04
11-dichloroethane	.2051E+02	.2581E+05	.2599E+02	.5725E+02
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.2819E+01	.1789E+04	.1117E+01	.7978E+00
tetrachloroethene	.1631E+02	.2054E+07	.6190E+02	.8795E+03
trichloroethene	.1103E+03	.4387E+06	.1224E+03	.1048E+04
vinylacetate	.8010E+02	.1613E+06	.1250E+03	.2231E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.1917E+03	.6296E+06	.2988E+02	.1504E+04

TOTAL MASS IN ALL PHASE = .4527E+05

TOTAL MASS IN GAS PHASE (kg) = .2537E+01
TOTAL MASS IN FREE PHASE (kg) = .4508E+05
TOTAL MASS IN WATER PHASE (kg) = .1605E+02

Stlbot.out

TOTAL MASS IN SOIL PHASE (kg) = .1801E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.1884E+06	.1530E+00	.2155E+01	.1376E+04
toluene	.1279E+08	.3010E+01	.4239E+02	.9343E+05
p-xylene	.6103E+07	.4259E+00	.5999E+01	.4460E+05
111-trichloroethane	.2716E+07	.3566E+00	.5022E+01	.1985E+05
1122-tetrachloroethane	.1972E+08	.1118E+01	.1574E+02	.1441E+06
112-trichloroethane	.4413E+06	.1420E+00	.2000E+01	.3225E+04
11-dichloroethane	.2592E+05	.5073E-01	.7146E+00	.1894E+03
11-dichloroethene	.3471E+02	.0000E+00	.0000E+00	.2536E+00
methylenechloride	.1794E+04	.7017E-02	.9883E-01	.1311E+02
tetrachloroethene	.2054E+07	.4014E-01	.5654E+00	.1501E+05
trichloroethene	.4399E+06	.2719E+00	.3829E+01	.3215E+04
vinylacetate	.1615E+06	.1977E+00	.2785E+01	.1180E+04
vinylchloride	.2158E+02	.0000E+00	.0000E+00	.1577E+00
Ethylbenzene	.6313E+06	.4726E+00	.6656E+01	.4613E+04

RESULTS AT TIME (DAYS) 3653.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.5326E+02	.1550E+06	.1222E+03	.5889E+03
toluene	.1201E+04	.1205E+08	.2331E+04	.4078E+05
p-xylene	.1768E+03	.5981E+07	.3858E+03	.1946E+05
111-trichloroethane	.1459E+03	.2620E+07	.1018E+04	.1149E+05
1122-tetrachloroethane	.4653E+03	.1934E+08	.1156E+05	.1011E+06
112-trichloroethane	.5549E+02	.4036E+06	.4711E+03	.4961E+04
11-dichloroethane	.1348E+02	.1634E+05	.1709E+02	.3764E+02
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.1179E+01	.7204E+03	.4672E+00	.3336E+00
tetrachloroethene	.1685E+02	.2043E+07	.6394E+02	.9086E+03
trichloroethene	.9911E+02	.3794E+06	.1099E+03	.9416E+03
vinylacetate	.6246E+02	.1212E+06	.9749E+02	.1740E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.1670E+03	.5282E+06	.2604E+02	.1311E+04

TOTAL MASS IN ALL PHASE = .4384E+05

Stlbot.out

TOTAL MASS IN GAS PHASE (kg) = .2458E+01
 TOTAL MASS IN FREE PHASE (kg) = .4364E+05
 TOTAL MASS IN WATER PHASE (kg) = .1621E+02
 TOTAL MASS IN SOIL PHASE (kg) = .1816E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.1557E+06	.1313E+00	.1849E+01	.1138E+04
toluene	.1209E+08	.2956E+01	.4163E+02	.8837E+05
p-xylene	.6001E+07	.4348E+00	.6124E+01	.4385E+05
111-trichloroethane	.2632E+07	.3588E+00	.5054E+01	.1924E+05
1122-tetrachloroethane	.1945E+08	.1145E+01	.1612E+02	.1421E+06
112-trichloroethane	.4091E+06	.1366E+00	.1924E+01	.2989E+04
11-dichoroethane	.1641E+05	.3336E-01	.4699E+00	.1199E+03
11-dichoroethene	.3327E+02	.0000E+00	.0000E+00	.2431E+00
methylenechloride	.7224E+03	.2935E-02	.4134E-01	.5279E+01
tetrachloroethene	.2044E+07	.4143E-01	.5836E+00	.1493E+05
trichloroethene	.3806E+06	.2442E+00	.3440E+01	.2781E+04
vinylacetate	.1213E+06	.1542E+00	.2172E+01	.8865E+03
vinylchloride	.2157E+02	.0000E+00	.0000E+00	.1576E+00
Ethylbenzene	.5297E+06	.4117E+00	.5799E+01	.3871E+04

RESULTS AT TIME (DAYS) 4018.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.4539E+02	.1272E+06	.1041E+03	.5018E+03
toluene	.1177E+04	.1137E+08	.2285E+04	.3997E+05
p-xylene	.1804E+03	.5876E+07	.3936E+03	.1986E+05
111-trichloroethane	.1466E+03	.2536E+07	.1024E+04	.1155E+05
1122-tetrachloroethane	.4762E+03	.1906E+08	.1183E+05	.1035E+06
112-trichloroethane	.5324E+02	.3729E+06	.4520E+03	.4760E+04
11-dichoroethane	.8711E+01	.1017E+05	.1104E+02	.2432E+02
11-dichoroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.4758E+00	.2800E+03	.1886E+00	.1347E+00
tetrachloroethene	.1741E+02	.2032E+07	.6605E+02	.9385E+03
trichloroethene	.8854E+02	.3264E+06	.9817E+02	.8411E+03
vinylacetate	.4819E+02	.9000E+05	.7520E+02	.1342E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00

Stlbot.out

Ethylbenzene .1446E+03 .4402E+06 .2253E+02 .1134E+04

TOTAL MASS IN ALL PHASE = .4244E+05

TOTAL MASS IN GAS PHASE (kg) = .2387E+01
 TOTAL MASS IN FREE PHASE (kg) = .4224E+05
 TOTAL MASS IN WATER PHASE (kg) = .1636E+02
 TOTAL MASS IN SOIL PHASE (kg) = .1831E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.1278E+06	.1119E+00	.1576E+01	.9339E+03
toluene	.1141E+08	.2897E+01	.4080E+02	.8341E+05
p-xylene	.5896E+07	.4436E+00	.6248E+01	.4308E+05
111-trichloroethane	.2548E+07	.3607E+00	.5080E+01	.1862E+05
1122-tetrachloroethane	.1918E+08	.1171E+01	.1649E+02	.1401E+06
112-trichloroethane	.3782E+06	.1311E+00	.1846E+01	.2763E+04
11-dichoroethane	.1021E+05	.2156E-01	.3037E+00	.7462E+02
11-dichoroethene	.3254E+02	.0000E+00	.0000E+00	.2378E+00
methylenchloride	.2809E+03	.1186E-02	.1670E-01	.2052E+01
tetrachloroethene	.2033E+07	.4282E-01	.6031E+00	.1485E+05
trichloroethene	.3274E+06	.2182E+00	.3073E+01	.2392E+04
vinylacetate	.9012E+05	.1190E+00	.1676E+01	.6585E+03
vinylchloride	.1953E+02	.0000E+00	.0000E+00	.1427E+00
Ethylbenzene	.4415E+06	.3564E+00	.5020E+01	.3226E+04

RESULTS AT TIME (DAYS) 4383.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.3839E+02	.1035E+06	.8808E+02	.4245E+03
toluene	.1151E+04	.1071E+08	.2235E+04	.3909E+05
p-xylene	.1839E+03	.5768E+07	.4014E+03	.2025E+05
111-trichloroethane	.1472E+03	.2451E+07	.1028E+04	.1159E+05
1122-tetrachloroethane	.4872E+03	.1877E+08	.1211E+05	.1059E+06
112-trichloroethane	.5094E+02	.3435E+06	.4324E+03	.4554E+04
11-dichoroethane	.5527E+01	.6211E+04	.7005E+01	.1543E+02
11-dichoroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenchloride	.1852E+00	.1050E+03	.7342E-01	.5242E-01

	Stlbot.out			
tetrachloroethene	.1798E+02	.2020E+07	.6822E+02	.9694E+03
trichloroethene	.7865E+02	.2791E+06	.8720E+02	.7472E+03
vinylacetate	.3675E+02	.6609E+05	.5736E+02	.1024E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.1243E+03	.3643E+06	.1937E+02	.9750E+03

TOTAL MASS IN ALL PHASE = .4109E+05

TOTAL MASS IN GAS PHASE (kg)	= .2322E+01
TOTAL MASS IN FREE PHASE (kg)	= .4088E+05
TOTAL MASS IN WATER PHASE (kg)	= .1653E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1845E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
	g	g/m3	g/m3	mg/k
benzene	.1041E+06	.9468E-01	.1334E+01	.7607E+03
toluene	.1075E+08	.2834E+01	.3991E+02	.7856E+05
p-xylene	.5789E+07	.4525E+00	.6373E+01	.4230E+05
111-trichloroethane	.2464E+07	.3622E+00	.5101E+01	.1800E+05
1122-tetrachloroethane	.1889E+08	.1199E+01	.1688E+02	.1380E+06
112-trichloroethane	.3485E+06	.1254E+00	.1766E+01	.2547E+04
11-dichloroethane	.6239E+04	.1368E-01	.1927E+00	.4559E+02
11-dichloroethene	.3110E+02	.0000E+00	.0000E+00	.2272E+00
methylenechloride	.1053E+03	.4618E-03	.6504E-02	.7692E+00
tetrachloroethene	.2022E+07	.4421E-01	.6227E+00	.1477E+05
trichloroethene	.2800E+06	.1938E+00	.2730E+01	.2046E+04
vinylacetate	.6618E+05	.9077E-01	.1278E+01	.4836E+03
vinylchloride	.1951E+02	.0000E+00	.0000E+00	.1426E+00
Ethylbenzene	.3654E+06	.3064E+00	.4315E+01	.2670E+04

RESULTS AT TIME (DAYS) 4748.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.3223E+02	.8366E+05	.7394E+02	.3564E+03
toluene	.1124E+04	.1006E+08	.2181E+04	.3816E+05
p-xylene	.1875E+03	.5659E+07	.4092E+03	.2064E+05
111-trichloroethane	.1477E+03	.2366E+07	.1031E+04	.1163E+05
1122-tetrachloroethane	.4983E+03	.1848E+08	.1238E+05	.1083E+06

	Stlbot.out			
112-trichloroethane	.4860E+02	.3154E+06	.4126E+03	.4345E+04
11-dichloroethane	.3441E+01	.3722E+04	.4362E+01	.9608E+01
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.6942E-01	.3786E+02	.2752E-01	.1965E-01
tetrachloroethene	.1857E+02	.2009E+07	.7048E+02	.1001E+04
trichloroethene	.6946E+02	.2372E+06	.7702E+02	.6599E+03
vinylacetate	.2771E+02	.4795E+05	.4324E+02	.7719E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.1061E+03	.2993E+06	.1653E+02	.8322E+03

TOTAL MASS IN ALL PHASE = .3976E+05

TOTAL MASS IN GAS PHASE (kg)	= .2263E+01
TOTAL MASS IN FREE PHASE (kg)	= .3956E+05
TOTAL MASS IN WATER PHASE (kg)	= .1670E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1859E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
	g	g/m3	g/m3	mg/k
benzene	.8412E+05	.7949E-01	.1120E+01	.6147E+03
toluene	.1010E+08	.2766E+01	.3896E+02	.7381E+05
p-xylene	.5681E+07	.4612E+00	.6496E+01	.4151E+05
111-trichloroethane	.2379E+07	.3633E+00	.5117E+01	.1738E+05
1122-tetrachloroethane	.1860E+08	.1226E+01	.1726E+02	.1359E+06
112-trichloroethane	.3202E+06	.1196E+00	.1685E+01	.2340E+04
11-dichloroethane	.3740E+04	.8523E-02	.1200E+00	.2733E+02
11-dichloroethene	.2965E+02	.0000E+00	.0000E+00	.2167E+00
methylenechloride	.3797E+02	.1731E-03	.2439E-02	.2775E+00
tetrachloroethene	.2010E+07	.4571E-01	.6438E+00	.1469E+05
trichloroethene	.2380E+06	.1712E+00	.2411E+01	.1739E+04
vinylacetate	.4802E+05	.6844E-01	.9639E+00	.3509E+03
vinylchloride	.1747E+02	.0000E+00	.0000E+00	.1277E+00
Ethylbenzene	.3002E+06	.2615E+00	.3684E+01	.2194E+04

RESULTS AT TIME (DAYS) 5113.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.2684E+02	.6703E+05	.6158E+02	.2968E+03

	Stlbot.out			
toluene	.1095E+04	.9427E+07	.2125E+04	.3717E+05
p-xylene	.1911E+03	.5548E+07	.4169E+03	.2103E+05
111-trichloroethane	.1480E+03	.2281E+07	.1033E+04	.1165E+05
1122-tetrachloroethane	.5095E+03	.1818E+08	.1266E+05	.1107E+06
112-trichloroethane	.4623E+02	.2886E+06	.3924E+03	.4133E+04
11-dichoroethane	.2101E+01	.2186E+04	.2663E+01	.5866E+01
11-dichoroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.1919E+02	.1997E+07	.7281E+02	.1035E+04
trichloroethene	.6098E+02	.2004E+06	.6761E+02	.5793E+03
vinylacetate	.2063E+02	.3435E+05	.3220E+02	.5748E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.8987E+02	.2440E+06	.1401E+02	.7051E+03

TOTAL MASS IN ALL PHASE = .3847E+05

TOTAL MASS IN GAS PHASE (kg)	= .2209E+01
TOTAL MASS IN FREE PHASE (kg)	= .3827E+05
TOTAL MASS IN WATER PHASE (kg)	= .1688E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1873E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.6742E+05	.6620E-01	.9324E+00	.4926E+03
toluene	.9468E+07	.2694E+01	.3795E+02	.6918E+05
p-xylene	.5570E+07	.4699E+00	.6618E+01	.4070E+05
111-trichloroethane	.2294E+07	.3640E+00	.5126E+01	.1676E+05
1122-tetrachloroethane	.1830E+08	.1253E+01	.1765E+02	.1337E+06
112-trichloroethane	.2932E+06	.1138E+00	.1603E+01	.2143E+04
11-dichoroethane	.2197E+04	.5205E-02	.7331E-01	.1605E+02
11-dichoroethene	.2892E+02	.0000E+00	.0000E+00	.2114E+00
methylenechloride	.3196E+02	.0000E+00	.0000E+00	.2335E+00
tetrachloroethene	.1998E+07	.4715E-01	.6641E+00	.1460E+05
trichloroethene	.2011E+06	.1503E+00	.2117E+01	.1469E+04
vinylacetate	.3441E+05	.5098E-01	.7180E+00	.2514E+03
vinylchloride	.1746E+02	.0000E+00	.0000E+00	.1276E+00
Ethylbenzene	.2448E+06	.2216E+00	.3121E+01	.1789E+04

RESULTS AT TIME (DAYS) 5478.606000

SPECIESMASS (g) IN PHASES

	Stlbot.out GAS	OIL	WATER	SOLID
benzene	.2217E+02	.5324E+05	.5085E+02	.2451E+03
toluene	.1064E+04	.8812E+07	.2065E+04	.3613E+05
p-xylene	.1946E+03	.5435E+07	.4247E+03	.2142E+05
111-trichloroethane	.1481E+03	.2196E+07	.1034E+04	.1166E+05
1122-tetrachloroethane	.5209E+03	.1787E+08	.1294E+05	.1132E+06
112-trichloroethane	.4384E+02	.2632E+06	.3722E+03	.3919E+04
11-dichloroethane	.1257E+01	.1257E+04	.1593E+01	.3508E+01
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.1983E+02	.1984E+07	.7523E+02	.1069E+04
trichloroethene	.5320E+02	.1681E+06	.5898E+02	.5054E+03
vinylacetate	.1517E+02	.2429E+05	.2368E+02	.4226E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.7557E+02	.1973E+06	.1178E+02	.5929E+03

TOTAL MASS IN ALL PHASE = .3721E+05

TOTAL MASS IN GAS PHASE (kg)	= .2159E+01
TOTAL MASS IN FREE PHASE (kg)	= .3701E+05
TOTAL MASS IN WATER PHASE (kg)	= .1706E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1888E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
g				
benzene	.5356E+05	.5468E-01	.7702E+00	.3914E+03
toluene	.8852E+07	.2619E+01	.3688E+02	.6468E+05
p-xylene	.5457E+07	.4786E+00	.6741E+01	.3987E+05
111-trichloroethane	.2209E+07	.3643E+00	.5131E+01	.1614E+05
1122-tetrachloroethane	.1800E+08	.1281E+01	.1804E+02	.1315E+06
112-trichloroethane	.2676E+06	.1079E+00	.1520E+01	.1955E+04
11-dichloroethane	.1264E+04	.3114E-02	.4386E-01	.9236E+01
11-dichloroethene	.2748E+02	.0000E+00	.0000E+00	.2008E+00
methylenechloride	.3052E+02	.0000E+00	.0000E+00	.2230E+00
tetrachloroethene	.1985E+07	.4875E-01	.6866E+00	.1451E+05
trichloroethene	.1687E+06	.1311E+00	.1847E+01	.1233E+04
vinylacetate	.2433E+05	.3749E-01	.5280E+00	.1778E+03
vinylchloride	.1745E+02	.0000E+00	.0000E+00	.1275E+00
Ethylbenzene	.1980E+06	.1864E+00	.2625E+01	.1447E+04

RESULTS AT TIME (DAYS) 5478.606000

Stlbot.out

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.2217E+02	.5324E+05	.5085E+02	.2451E+03
toluene	.1064E+04	.8812E+07	.2065E+04	.3613E+05
p-xylene	.1946E+03	.5435E+07	.4247E+03	.2142E+05
111-trichloroethane	.1481E+03	.2196E+07	.1034E+04	.1166E+05
1122-tetrachloroethane	.5209E+03	.1787E+08	.1294E+05	.1132E+06
112-trichloroethane	.4384E+02	.2632E+06	.3722E+03	.3919E+04
11-dichloroethane	.1257E+01	.1257E+04	.1593E+01	.3508E+01
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.1983E+02	.1984E+07	.7523E+02	.1069E+04
trichloroethene	.5320E+02	.1681E+06	.5898E+02	.5054E+03
vinylacetate	.1517E+02	.2429E+05	.2368E+02	.4226E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.7557E+02	.1973E+06	.1178E+02	.5929E+03


TOTAL MASS IN ALL PHASE = .3721E+05

TOTAL MASS IN GAS PHASE (kg)	= .2159E+01
TOTAL MASS IN FREE PHASE (kg)	= .3701E+05
TOTAL MASS IN WATER PHASE (kg)	= .1706E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1888E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.5356E+05	.5468E-01	.7702E+00	.3914E+03
toluene	.8852E+07	.2619E+01	.3688E+02	.6468E+05
p-xylene	.5457E+07	.4786E+00	.6741E+01	.3987E+05
111-trichloroethane	.2209E+07	.3643E+00	.5131E+01	.1614E+05
1122-tetrachloroethane	.1800E+08	.1281E+01	.1804E+02	.1315E+06
112-trichloroethane	.2676E+06	.1079E+00	.1520E+01	.1955E+04
11-dichloroethane	.1264E+04	.3114E-02	.4386E-01	.9236E+01
11-dichloroethene	.2748E+02	.0000E+00	.0000E+00	.2008E+00
methylenechloride	.3052E+02	.0000E+00	.0000E+00	.2230E+00
tetrachloroethene	.1985E+07	.4875E-01	.6866E+00	.1451E+05
trichloroethene	.1687E+06	.1311E+00	.1847E+01	.1233E+04
vinylacetate	.2433E+05	.3749E-01	.5280E+00	.1778E+03


	Stlbot.out			
vinylchloride	.1745E+02	.0000E+00	.0000E+00	.1275E+00
Ethylbenzene	.1980E+06	.1864E+00	.2625E+01	.1447E+04

ACS Still Bottoms



10 darcy

ACS Still Bottoms



Stlbot.out

```
+ + + + + + + + + + + + + + + + + + + + + + + + + + + +  
+  
+ BioSVE For Window  
+  
+ SOIL VACUUM EXTRACTION CHEMICAL EQUILIBRIUM MODEL  
+ BASED ON JOHNSON ET AL. (1990) GROUND WATER  
+  
+  
+  
+  
+  
+  
+ COPYRIGHT 1995  
+ ASHOK KATYAL, Ph.D.  
+ DRAPER ADEN ENVIRONMENTAL MODELING  
+ BLACKSBURG, VA 24060, U.S.A.  
+  
+ + + + + + + + + + + + + + + + + + + + + + + + + + + +
```

TITLE: ACS Still Bottoms

```

air flow rate      (liters/day)      = .1208E+07
total mass of contaminant (g)        = .6471E+08
maximum simulation time (days)       = .5475E+04
starting time step (days)           = .5000E+00
maximum time step (days)            = .5000E+01
time increment factor                 = .10200E+01
printout time interval (days)       = .36500E+03
volumetric water content(fraction)   = .15000E+00
bulk density (g/cm^3)                = .17000E+01
foc                                   = .50000E-02
contaminated soil vol. (m^3)         = .80500E+02
temperature (C)                      = .20000E+02
intercept in free prod.recov.eqn.   = .15000E+01
exponent in free prod. recov. eqn.  = .20000E-01
bio efficiency (fraction)            = .20000E-01
residual oil mass (kg)               = .64710E+04
venting efficiency (fraction)        = .7100E-01

```

SPECIES	VAP PRES atm	BOILING POINT deg C	SOL LIMIT ppm	KOW g/g
benzene	.1000E+00	.8000E+02	.1780E+04	.1350E+03
toluene	.2900E-01	.1110E+03	.5150E+03	.4900E+03

	Stlbot.out			
p-xylene	.8600E-02	.1380E+03	.1980E+03	.1413E+04
111-trichloroethane	.1620E-01	.7410E+02	.1500E+04	.3160E+03
1122-tetrachloroethane	.7000E-02	.1462E+03	.2900E+04	.2450E+03
112-trichloroethane	.4000E-01	.1138E+03	.4500E+04	.2950E+03
11-dichoroethane	.2400E+00	.5750E+02	.5500E+04	.6170E+02
11-dichoroethene	.7900E+00	.3700E+02	.2250E+04	.6920E+02
methylenechloride	.4760E+00	.9370E+02	.2000E+04	.2000E+02
tetrachloroethene	.2400E-02	.1210E+03	.1500E+03	.3980E+03
trichloroethene	.7600E-01	.8720E+02	.1100E+04	.2400E+03
vinylacetate	.1500E+00	.7200E+02	.2000E+04	.5000E+00
vinylchloride	.3500E+01	.1340E+02	.2670E+04	.2400E+02
Ethylbenzene	.9200E-01	.1362E+03	.1520E+03	.1410E+04
MASS FRACTION SUM	1.000000			

SPECIES	MOL WEIGHT g/mol	HENRY COEFF DIMENSIONLESS
benzene	.7810E+02	.0000E+00
toluene	.9210E+02	.0000E+00
p-xylene	.1062E+03	.0000E+00
111-trichloroethane	.1335E+03	.0000E+00
1122-tetrachloroethane	.1678E+03	.0000E+00
112-trichloroethane	.1334E+03	.0000E+00
11-dichoroethane	.1820E+03	.0000E+00
11-dichoroethene	.9694E+02	.0000E+00
methylenechloride	.1067E+03	.0000E+00
tetrachloroethene	.1658E+03	.0000E+00
trichloroethene	.1314E+03	.0000E+00
vinylacetate	.8600E+02	.0000E+00
vinylchloride	.6250E+02	.0000E+00
Ethylbenzene	.1067E+03	.0000E+00
sgmlti	556024.500000	

RESULTS AT TIME (DAYS) 0.000000E+00

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1673E+03	.7742E+06	.3838E+03	.1850E+04
toluene	.1210E+04	.1930E+08	.2348E+04	.4107E+05
p-xylene	.1284E+03	.6910E+07	.2802E+03	.1414E+05
111-trichloroethane	.1197E+03	.3419E+07	.8357E+03	.9428E+04
1122-tetrachloroethane	.3296E+03	.2179E+08	.8191E+04	.7164E+05
112-trichloroethane	.6655E+02	.7700E+06	.5650E+03	.5950E+04
11-dichoroethane	.4017E+03	.7745E+06	.5091E+03	.1121E+04

	Stlbot.out			
11-dichoroethene	.1321E+04	.7739E+06	.3907E+03	.9652E+03
methylenchloride	.1595E+04	.1550E+07	.6322E+03	.4514E+03
tetrachloroethene	.1107E+02	.2135E+07	.4201E+02	.5969E+03
trichloroethene	.2122E+03	.1292E+07	.2352E+03	.2015E+04
vinylacetate	.4401E+03	.1358E+07	.6869E+03	.1226E+02
vinylchloride	.1014E+05	.1341E+07	.4360E+04	.3736E+04
Ethylbenzene	.4623E+03	.2326E+07	.7206E+02	.3627E+04

TOTAL MASS IN ALL PHASE = .6471E+05

TOTAL MASS IN GAS PHASE (kg)	= .1660E+02
TOTAL MASS IN FREE PHASE (kg)	= .6452E+05
TOTAL MASS IN WATER PHASE (kg)	= .1953E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1566E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S				
	g	g/m3	g/m3	mg/k
benzene	.7766E+06	.0000E+00	.0000E+00	.5675E+04
toluene	.1935E+08	.0000E+00	.0000E+00	.1414E+06
p-xylene	.6924E+07	.0000E+00	.0000E+00	.5060E+05
111-trichloroethane	.3430E+07	.0000E+00	.0000E+00	.2506E+05
1122-tetrachloroethane	.2187E+08	.0000E+00	.0000E+00	.1598E+06
112-trichloroethane	.7766E+06	.0000E+00	.0000E+00	.5675E+04
11-dichoroethane	.7766E+06	.0000E+00	.0000E+00	.5675E+04
11-dichoroethene	.7766E+06	.7835E-04	.1103E-02	.5675E+04
methylenchloride	.1553E+07	.0000E+00	.0000E+00	.1135E+05
tetrachloroethene	.2136E+07	.0000E+00	.0000E+00	.1561E+05
trichloroethene	.1294E+07	.0000E+00	.0000E+00	.9458E+04
vinylacetate	.1359E+07	.0000E+00	.0000E+00	.9931E+04
vinylchloride	.1359E+07	.4041E-03	.5692E-02	.9931E+04
Ethylbenzene	.2330E+07	.0000E+00	.0000E+00	.1702E+05

end of initial conditions

RESULTS AT TIME (DAYS) 368.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1492E+03	.5968E+06	.3423E+03	.1650E+04
toluene	.1297E+04	.1789E+08	.2517E+04	.4403E+05

	Stlbot.out			
p-xylene	.1451E+03	.6750E+07	.3167E+03	.1598E+05
111-trichloroethane	.1326E+03	.3275E+07	.9260E+03	.1045E+05
1122-tetrachloroethane	.3740E+03	.2137E+08	.9294E+04	.8129E+05
112-trichloroethane	.6932E+02	.6932E+06	.5885E+03	.6198E+04
11-dichoroethane	.2491E+03	.4152E+06	.3157E+03	.6955E+03
11-dichoroethene	.1951E+03	.9878E+05	.5770E+02	.1425E+03
methylenechloride	.5343E+03	.4490E+06	.2118E+03	.1512E+03
tetrachloroethene	.1272E+02	.2120E+07	.4826E+02	.6857E+03
trichloroethene	.2013E+03	.1060E+07	.2232E+03	.1913E+04
vinylacetate	.3446E+03	.9190E+06	.5379E+03	.9601E+01
vinylchloride	.1136E+01	.1298E+03	.4886E+00	.4186E+00
Ethylbenzene	.4209E+03	.1830E+07	.6561E+02	.3303E+04

TOTAL MASS IN ALL PHASE = .5765E+05

TOTAL MASS IN GAS PHASE (kg)	= .4126E+01
TOTAL MASS IN FREE PHASE (kg)	= .5746E+05
TOTAL MASS IN WATER PHASE (kg)	= .1544E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1665E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.5989E+06	.3680E+00	.5183E+01	.4377E+04
toluene	.1793E+08	.3190E+01	.4493E+02	.1310E+06
p-xylene	.6766E+07	.3567E+00	.5024E+01	.4944E+05
111-trichloroethane	.3286E+07	.3261E+00	.4593E+01	.2401E+05
1122-tetrachloroethane	.2146E+08	.9193E+00	.1295E+02	.1568E+06
112-trichloroethane	.7000E+06	.1706E+00	.2403E+01	.5115E+04
11-dichoroethane	.4164E+06	.6176E+00	.8699E+01	.3043E+04
11-dichoroethene	.9919E+05	.4939E+00	.6956E+01	.7248E+03
methylenechloride	.4499E+06	.1336E+01	.1882E+02	.3287E+04
tetrachloroethene	.2120E+07	.3125E-01	.4401E+00	.1549E+05
trichloroethene	.1062E+07	.4962E+00	.6988E+01	.7760E+04
vinylacetate	.9199E+06	.8516E+00	.1199E+02	.6722E+04
vinylchloride	.1322E+03	.3200E-02	.4507E-01	.9658E+00
Ethylbenzene	.1834E+07	.1038E+01	.1462E+02	.1340E+05

RESULTS AT TIME (DAYS) 733.606000

SPECIESMASS (g) IN PHASES
	GAS OIL WATER SOLID

Stlbot.out

benzene	.1220E+03	.4494E+06	.2800E+03	.1349E+04
toluene	.1296E+04	.1646E+08	.2516E+04	.4401E+05
p-xylene	.1537E+03	.6580E+07	.3353E+03	.1691E+05
111-trichloroethane	.1374E+03	.3125E+07	.9596E+03	.1083E+05
1122-tetrachloroethane	.3978E+03	.2093E+08	.9884E+04	.8645E+05
112-trichloroethane	.6718E+02	.6186E+06	.5703E+03	.6006E+04
11-dichloroethane	.1369E+03	.2101E+06	.1735E+03	.3822E+03
11-dichloroethene	.2208E+02	.1029E+05	.6529E+01	.1613E+02
methylenchloride	.1493E+03	.1155E+06	.5918E+02	.4226E+02
tetrachloroethene	.1371E+02	.2103E+07	.5201E+02	.7390E+03
trichloroethene	.1762E+03	.8538E+06	.1954E+03	.1674E+04
vinylacetate	.2444E+03	.6001E+06	.3814E+03	.6808E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3520E+03	.1409E+07	.5487E+02	.2762E+04

TOTAL MASS IN ALL PHASE = .5365E+05

TOTAL MASS IN GAS PHASE (kg)	= .3269E+01
TOTAL MASS IN FREE PHASE (kg)	= .5346E+05
TOTAL MASS IN WATER PHASE (kg)	= .1547E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1712E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
	g	g/m3	g/m3	mg/k
benzene	.4511E+06	.3011E+00	.4241E+01	.3297E+04
toluene	.1651E+08	.3189E+01	.4492E+02	.1206E+06
p-xylene	.6597E+07	.3778E+00	.5321E+01	.4821E+05
111-trichloroethane	.3136E+07	.3380E+00	.4761E+01	.2292E+05
1122-tetrachloroethane	.2102E+08	.9779E+00	.1377E+02	.1536E+06
112-trichloroethane	.6252E+06	.1654E+00	.2329E+01	.4569E+04
11-dichloroethane	.2108E+06	.3397E+00	.4785E+01	.1540E+04
11-dichloroethene	.1034E+05	.5604E-01	.7893E+00	.7555E+02
methylenchloride	.1158E+06	.3741E+00	.5269E+01	.8460E+03
tetrachloroethene	.2104E+07	.3369E-01	.4745E+00	.1538E+05
trichloroethene	.8559E+06	.4344E+00	.6118E+01	.6254E+04
vinylacetate	.6007E+06	.6043E+00	.8512E+01	.4389E+04
vinylchloride	.2517E+02	.0000E+00	.0000E+00	.1840E+00
Ethylbenzene	.1412E+07	.8684E+00	.1223E+02	.1032E+05

RESULTS AT TIME (DAYS) 1098.606000

Stlbot.out

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.9680E+02	.3307E+06	.2221E+03	.1070E+04
toluene	.1277E+04	.1505E+08	.2479E+04	.4337E+05
p-xylene	.1611E+03	.6402E+07	.3517E+03	.1774E+05
111-trichloroethane	.1408E+03	.2970E+07	.9833E+03	.1109E+05
1122-tetrachloroethane	.4192E+03	.2046E+08	.1042E+05	.9110E+05
112-trichloroethane	.6404E+02	.5470E+06	.5437E+03	.5726E+04
11-dichloroethane	.7064E+02	.1006E+06	.8954E+02	.1972E+03
11-dichloroethene	.2059E+01	.8904E+03	.6090E+00	.1504E+01
methylenechloride	.3705E+02	.2660E+05	.1469E+02	.1049E+02
tetrachloroethene	.1465E+02	.2086E+07	.5560E+02	.7900E+03
trichloroethene	.1504E+03	.6760E+06	.1667E+03	.1429E+04
vinylacetate	.1662E+03	.3785E+06	.2593E+03	.4629E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.2861E+03	.1062E+07	.4459E+02	.2245E+04

TOTAL MASS IN ALL PHASE = .5028E+05

TOTAL MASS IN GAS PHASE (kg)	= .2886E+01
TOTAL MASS IN FREE PHASE (kg)	= .5009E+05
TOTAL MASS IN WATER PHASE (kg)	= .1563E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1748E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	
S				SOIL MAS
g	g	g/m3	g/m3	mg/k
benzene	.3321E+06	.2390E+00	.3366E+01	.2427E+04
toluene	.1509E+08	.3143E+01	.4427E+02	.1103E+06
p-xylene	.6420E+07	.3963E+00	.5581E+01	.4691E+05
111-trichloroethane	.2982E+07	.3464E+00	.4879E+01	.2179E+05
1122-tetrachloroethane	.2056E+08	.1030E+01	.1451E+02	.1502E+06
112-trichloroethane	.5533E+06	.1577E+00	.2221E+01	.4043E+04
11-dichloroethane	.1009E+06	.1755E+00	.2471E+01	.7375E+03
11-dichloroethene	.8948E+03	.5240E-02	.7380E-01	.6538E+01
methylenechloride	.2666E+05	.9299E-01	.1310E+01	.1948E+03
tetrachloroethene	.2087E+07	.3602E-01	.5073E+00	.1525E+05
trichloroethene	.6778E+06	.3708E+00	.5223E+01	.4953E+04
vinylacetate	.3789E+06	.4111E+00	.5790E+01	.2769E+04
vinylchloride	.2515E+02	.0000E+00	.0000E+00	.1838E+00

Ethylbenzene	.1065E+07	.7060E+00	.9943E+01	.7782E+04
--------------	-----------	-----------	-----------	-----------

RESULTS AT TIME (DAYS) 1463.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.7485E+02	.2377E+06	.1717E+03	.8276E+03
toluene	.1247E+04	.1366E+08	.2421E+04	.4235E+05
p-xylene	.1683E+03	.6215E+07	.3672E+03	.1852E+05
111-trichloroethane	.1434E+03	.2812E+07	.1001E+04	.1130E+05
1122-tetrachloroethane	.4399E+03	.1996E+08	.1093E+05	.9562E+05
112-trichloroethane	.6035E+02	.4792E+06	.5123E+03	.5395E+04
11-dichloroethane	.3438E+02	.4550E+05	.4357E+02	.9598E+02
11-dichloroethene	.1585E+00	.6373E+02	.4687E-01	.1158E+00
methylenechloride	.8193E+01	.5467E+04	.3248E+01	.2319E+01
tetrachloroethene	.1562E+02	.2067E+07	.5926E+02	.8420E+03
trichloroethene	.1258E+03	.5258E+06	.1395E+03	.1195E+04
vinylacetate	.1088E+03	.2304E+06	.1698E+03	.3031E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.2270E+03	.7838E+06	.3538E+02	.1781E+04

TOTAL MASS IN ALL PHASE = .4723E+05

TOTAL MASS IN GAS PHASE (kg)	=	.2654E+01
TOTAL MASS IN FREE PHASE (kg)	=	.4703E+05
TOTAL MASS IN WATER PHASE (kg)	=	.1586E+02
TOTAL MASS IN SOIL PHASE (kg)	=	.1779E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
g				
benzene	.2388E+06	.1848E+00	.2603E+01	.1745E+04
toluene	.1371E+08	.3070E+01	.4324E+02	.1002E+06
p-xylene	.6234E+07	.4138E+00	.5828E+01	.4556E+05
111-trichloroethane	.2825E+07	.3528E+00	.4969E+01	.2064E+05
1122-tetrachloroethane	.2007E+08	.1082E+01	.1523E+02	.1467E+06
112-trichloroethane	.4852E+06	.1486E+00	.2093E+01	.3546E+04
11-dichloroethane	.4568E+05	.8545E-01	.1204E+01	.3338E+03
11-dichloroethene	.6406E+02	.4044E-03	.5696E-02	.4681E+00
methylenchloride	.5481E+04	.2059E-01	.2901E+00	.4005E+02

	Stlbot.out			
tetrachloroethene	.2068E+07	.3838E-01	.5405E+00	.1511E+05
trichloroethene	.5273E+06	.3103E+00	.4370E+01	.3853E+04
vinylacetate	.2307E+06	.2693E+00	.3793E+01	.1686E+04
vinylchloride	.2122E+02	.0000E+00	.0000E+00	.1551E+00
Ethylbenzene	.7858E+06	.5604E+00	.7892E+01	.5742E+04

RESULTS AT TIME (DAYS) 1828.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.5643E+02	.1667E+06	.1295E+03	.6239E+03
toluene	.1209E+04	.1232E+08	.2346E+04	.4104E+05
p-xylene	.1752E+03	.6021E+07	.3824E+03	.1929E+05
111-trichloroethane	.1454E+03	.2652E+07	.1015E+04	.1145E+05
1122-tetrachloroethane	.4607E+03	.1945E+08	.1145E+05	.1001E+06
112-trichloroethane	.5628E+02	.4158E+06	.4778E+03	.5032E+04
11-dichloroethane	.1575E+02	.1939E+05	.1996E+02	.4398E+02
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.1606E+01	.9969E+03	.6365E+00	.4545E+00
tetrachloroethene	.1663E+02	.2047E+07	.6309E+02	.8964E+03
trichloroethene	.1032E+03	.4013E+06	.1144E+03	.9805E+03
vinylacetate	.6859E+02	.1351E+06	.1071E+03	.1911E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.1760E+03	.5652E+06	.2743E+02	.1381E+04

TOTAL MASS IN ALL PHASE = .4439E+05

TOTAL MASS IN GAS PHASE (kg)	= .2484E+01
TOTAL MASS IN FREE PHASE (kg)	= .4419E+05
TOTAL MASS IN WATER PHASE (kg)	= .1613E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1809E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.1676E+06	.1394E+00	.1963E+01	.1224E+04
toluene	.1236E+08	.2975E+01	.4190E+02	.9032E+05
p-xylene	.6041E+07	.4309E+00	.6069E+01	.4414E+05
111-trichloroethane	.2665E+07	.3577E+00	.5038E+01	.1947E+05
1122-tetrachloroethane	.1956E+08	.1133E+01	.1596E+02	.1429E+06

	Stlbot.out			
112-trichloroethane	.4214E+06	.1386E+00	.1952E+01	.3079E+04
11-dichloroethane	.1947E+05	.3919E-01	.5519E+00	.1423E+03
11-dichloroethene	.3360E+02	.0000E+00	.0000E+00	.2455E+00
methylenechloride	.9996E+03	.4043E-02	.5695E-01	.7305E+01
tetrachloroethene	.2048E+07	.4087E-01	.5756E+00	.1497E+05
trichloroethene	.4025E+06	.2547E+00	.3587E+01	.2941E+04
vinylacetate	.1353E+06	.1699E+00	.2393E+01	.9887E+03
vinylchloride	.2120E+02	.0000E+00	.0000E+00	.1549E+00
Ethylbenzene	.5668E+06	.4345E+00	.6120E+01	.4142E+04

RESULTS AT TIME (DAYS) 2193.606000.

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.4144E+02	.1139E+06	.9507E+02	.4582E+03
toluene	.1162E+04	.1102E+08	.2256E+04	.3947E+05
p-xylene	.1821E+03	.5819E+07	.3974E+03	.2005E+05
111-trichloroethane	.1468E+03	.2491E+07	.1025E+04	.1156E+05
1122-tetrachloroethane	.4817E+03	.1891E+08	.1197E+05	.1047E+06
112-trichloroethane	.5196E+02	.3570E+06	.4411E+03	.4645E+04
11-dichloroethane	.6771E+01	.7753E+04	.8582E+01	.1890E+02
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.2767E+00	.1598E+03	.1097E+00	.7833E-01
tetrachloroethene	.1769E+02	.2026E+07	.6714E+02	.9540E+03
trichloroethene	.8301E+02	.3002E+06	.9204E+02	.7886E+03
vinylacetate	.4156E+02	.7613E+05	.6486E+02	.1158E+01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.1332E+03	.3977E+06	.2075E+02	.1045E+04

TOTAL MASS IN ALL PHASE = .4171E+05

TOTAL MASS IN GAS PHASE (kg)	= .2349E+01
TOTAL MASS IN FREE PHASE (kg)	= .4151E+05
TOTAL MASS IN WATER PHASE (kg)	= .1644E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1837E+03

SPECIES	MASS	CONC		CONC SOIL MAS
		WELL GAS	SOIL GAS	
S				
g	g	g/m3	g/m3	mg/k
benzene	.1145E+06	.1024E+00	.1442E+01	.8365E+03

	Stlbot.out			
toluene	.1106E+08	.2862E+01	.4030E+02	.8080E+05
p-xylene	.5840E+07	.4478E+00	.6308E+01	.4267E+05
111-trichloroethane	.2503E+07	.3612E+00	.5087E+01	.1829E+05
1122-tetrachloroethane	.1903E+08	.1184E+01	.1668E+02	.1390E+06
112-trichloroethane	.3621E+06	.1280E+00	.1803E+01	.2646E+04
11-dichoroethane	.7787E+04	.1686E-01	.2375E+00	.5690E+02
11-dichoroethene	.3083E+02	.0000E+00	.0000E+00	.2253E+00
methylenechloride	.1602E+03	.6981E-03	.9832E-02	.1171E+01
tetrachloroethene	.2027E+07	.4350E-01	.6126E+00	.1481E+05
trichloroethene	.3011E+06	.2049E+00	.2886E+01	.2200E+04
vinylacetate	.7624E+05	.1030E+00	.1450E+01	.5571E+03
vinylchloride	.1727E+02	.0000E+00	.0000E+00	.1262E+00
Ethylbenzene	.3989E+06	.3289E+00	.4632E+01	.2915E+04

RESULTS AT TIME (DAYS) 2558.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.2960E+02	.7556E+05	.6790E+02	.3272E+03
toluene	.1110E+04	.9770E+07	.2154E+04	.3768E+05
p-xylene	.1890E+03	.5610E+07	.4123E+03	.2080E+05
111-trichloroethane	.1477E+03	.2327E+07	.1031E+04	.1163E+05
1122-tetrachloroethane	.5029E+03	.1834E+08	.1250E+05	.1093E+06
112-trichloroethane	.4747E+02	.3030E+06	.4030E+03	.4244E+04
11-dichoroethane	.2717E+01	.2891E+04	.3444E+01	.7586E+01
11-dichoroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.1883E+02	.2003E+07	.7146E+02	.1015E+04
trichloroethene	.6537E+02	.2196E+06	.7249E+02	.6211E+03
vinylacetate	.2412E+02	.4106E+05	.3765E+02	.6720E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.9819E+02	.2725E+06	.1531E+02	.7704E+03

TOTAL MASS IN ALL PHASE = .3917E+05

TOTAL MASS IN GAS PHASE (kg)	= .2236E+01
TOTAL MASS IN FREE PHASE (kg)	= .3897E+05
TOTAL MASS IN WATER PHASE (kg)	= .1677E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1864E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S				

	Stlbot.out			
g	g	g/m3	g/m3	mg/k
benzene	.7599E+05	.7316E-01	.1030E+01	.5553E+03
toluene	.9811E+07	.2732E+01	.3848E+02	.7169E+05
p-xylene	.5631E+07	.4646E+00	.6544E+01	.4115E+05
111-trichloroethane	.2340E+07	.3633E+00	.5117E+01	.1710E+05
1122-tetrachloroethane	.1847E+08	.1237E+01	.1742E+02	.1349E+06
112-trichloroethane	.3077E+06	.1169E+00	.1647E+01	.2248E+04
11-dichoroethane	.2905E+04	.6773E-02	.9539E-01	.2123E+02
11-dichoroethene	.2942E+02	.0000E+00	.0000E+00	.2150E+00
methylenechloride	.3204E+02	.0000E+00	.0000E+00	.2342E+00
tetrachloroethene	.2005E+07	.4628E-01	.6519E+00	.1465E+05
trichloroethene	.2204E+06	.1614E+00	.2273E+01	.1610E+04
vinylacetate	.4113E+05	.5981E-01	.8425E+00	.3005E+03
vinylchloride	.1725E+02	.0000E+00	.0000E+00	.1260E+00
Ethylbenzene	.2734E+06	.2426E+00	.3417E+01	.1998E+04

RESULTS AT TIME (DAYS) 2923.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.2051E+02	.4859E+05	.4705E+02	.2268E+03
toluene	.1051E+04	.8586E+07	.2040E+04	.3569E+05
p-xylene	.1958E+03	.5392E+07	.4272E+03	.2155E+05
111-trichloroethane	.1480E+03	.2164E+07	.1033E+04	.1165E+05
1122-tetrachloroethane	.5247E+03	.1776E+08	.1304E+05	.1140E+06
112-trichloroethane	.4288E+02	.2540E+06	.3640E+03	.3834E+04
11-dichoroethane	.1012E+01	.9989E+03	.1283E+01	.2825E+01
11-dichoroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.2005E+02	.1980E+07	.7610E+02	.1081E+04
trichloroethene	.5033E+02	.1569E+06	.5580E+02	.4781E+03
vinylacetate	.1337E+02	.2112E+05	.2087E+02	.3725E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.7043E+02	.1814E+06	.1098E+02	.5526E+03

TOTAL MASS IN ALL PHASE = .3675E+05

TOTAL MASS IN GAS PHASE (kg)	= .2138E+01
TOTAL MASS IN FREE PHASE (kg)	= .3654E+05
TOTAL MASS IN WATER PHASE (kg)	= .1711E+02
TOTAL MASS IN SOIL PHASE (kg)	= .1891E+03

Stlbot.out

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S				
g	g	g/m3	g/m3	mg/k
benzene	.4888E+05	.5072E-01	.7144E+00	.3572E+03
toluene	.8625E+07	.2588E+01	.3645E+02	.6302E+05
p-xylene	.5415E+07	.4813E+00	.6780E+01	.3957E+05
111-trichloroethane	.2177E+07	.3640E+00	.5127E+01	.1591E+05
1122-tetrachloroethane	.1788E+08	.1290E+01	.1817E+02	.1307E+06
112-trichloroethane	.2582E+06	.1057E+00	.1488E+01	.1887E+04
11-dichloroethane	.1004E+04	.2525E-02	.3556E-01	.7337E+01
11-dichloroethene	.2665E+02	.0000E+00	.0000E+00	.1948E+00
methylenechloride	.3019E+02	.0000E+00	.0000E+00	.2206E+00
tetrachloroethene	.1981E+07	.4931E-01	.6945E+00	.1447E+05
trichloroethene	.1575E+06	.1243E+00	.1751E+01	.1151E+04
vinylacetate	.2115E+05	.3317E-01	.4672E+00	.1546E+03
vinylchloride	.1722E+02	.0000E+00	.0000E+00	.1259E+00
Ethylbenzene	.1820E+06	.1741E+00	.2452E+01	.1330E+04

RESULTS AT TIME (DAYS) 3288.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1375E+02	.3018E+05	.3155E+02	.1521E+03
toluene	.9871E+03	.7469E+07	.1916E+04	.3352E+05
p-xylene	.2025E+03	.5168E+07	.4420E+03	.2230E+05
111-trichloroethane	.1477E+03	.2000E+07	.1031E+04	.1163E+05
1122-tetrachloroethane	.5469E+03	.1714E+08	.1359E+05	.1189E+06
112-trichloroethane	.3828E+02	.2100E+06	.3250E+03	.3423E+04
11-dichloroethane	.3472E+00	.3174E+03	.4401E+00	.9693E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.2137E+02	.1954E+07	.8110E+02	.1152E+04
trichloroethene	.3780E+02	.1091E+06	.4192E+02	.3591E+03
vinylacetate	.7044E+01	.1031E+05	.1099E+02	.1962E+00
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.4901E+02	.1169E+06	.7640E+01	.3846E+03

TOTAL MASS IN ALL PHASE = .3442E+05

TOTAL MASS IN GAS PHASE (kg) = .2052E+01
TOTAL MASS IN FREE PHASE (kg) = .3421E+05
TOTAL MASS IN WATER PHASE (kg) = .1748E+02

Stlbot.out

TOTAL MASS IN SOIL PHASE (kg) = .1918E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.3038E+05	.3403E-01	.4793E+00	.2220E+03
toluene	.7506E+07	.2431E+01	.3424E+02	.5485E+05
p-xylene	.5191E+07	.4980E+00	.7015E+01	.3793E+05
111-trichloroethane	.2013E+07	.3633E+00	.5117E+01	.1471E+05
1122-tetrachloroethane	.1728E+08	.1345E+01	.1894E+02	.1262E+06
112-trichloroethane	.2138E+06	.9434E-01	.1329E+01	.1562E+04
11-dichloroethane	.3192E+03	.8673E-03	.1222E-01	.2333E+01
11-dichloroethene	.2525E+02	.0000E+00	.0000E+00	.1845E+00
methylenechloride	.2743E+02	.0000E+00	.0000E+00	.2004E+00
tetrachloroethene	.1955E+07	.5253E-01	.7398E+00	.1429E+05
trichloroethene	.1096E+06	.9339E-01	.1315E+01	.8008E+03
vinylacetate	.1032E+05	.1749E-01	.2463E+00	.7544E+02
vinylchloride	.1330E+02	.0000E+00	.0000E+00	.9718E-01
Ethylbenzene	.1174E+06	.1212E+00	.1707E+01	.8575E+03

RESULTS AT TIME (DAYS) 3653.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.8894E+01	.1804E+05	.2041E+02	.9834E+02
toluene	.9188E+03	.6426E+07	.1783E+04	.3120E+05
p-xylene	.2093E+03	.4936E+07	.4567E+03	.2304E+05
111-trichloroethane	.1468E+03	.1838E+07	.1025E+04	.1156E+05
1122-tetrachloroethane	.5697E+03	.1651E+08	.1416E+05	.1238E+06
112-trichloroethane	.3374E+02	.1711E+06	.2864E+03	.3016E+04
11-dichloroethane	.1088E+00	.9195E+02	.1379E+00	.3038E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.2280E+02	.1927E+07	.8652E+02	.1229E+04
trichloroethene	.2763E+02	.7375E+05	.3064E+02	.2625E+03
vinylacetate	.3509E+01	.4745E+04	.5477E+01	.9776E-01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.3299E+02	.7274E+05	.5143E+01	.2589E+03

TOTAL MASS IN ALL PHASE = .3219E+05

Stlbot.out

TOTAL MASS IN GAS PHASE (kg) = .1974E+01
 TOTAL MASS IN FREE PHASE (kg) = .3197E+05
 TOTAL MASS IN WATER PHASE (kg) = .1785E+02
 TOTAL MASS IN SOIL PHASE (kg) = .1945E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.1817E+05	.2202E-01	.3101E+00	.1328E+03
toluene	.6460E+07	.2263E+01	.3187E+02	.4720E+05
p-xylene	.4959E+07	.5147E+00	.7249E+01	.3624E+05
111-trichloroethane	.1850E+07	.3611E+00	.5086E+01	.1352E+05
1122-tetrachloroethane	.1664E+08	.1401E+01	.1973E+02	.1216E+06
112-trichloroethane	.1744E+06	.8315E-01	.1171E+01	.1274E+04
11-dichloroethane	.9251E+02	.2721E-03	.3833E-02	.6760E+00
11-dichloroethene	.2248E+02	.0000E+00	.0000E+00	.1643E+00
methylenechloride	.2558E+02	.0000E+00	.0000E+00	.1869E+00
tetrachloroethene	.1928E+07	.5604E-01	.7893E+00	.1409E+05
trichloroethene	.7407E+05	.6829E-01	.9619E+00	.5413E+03
vinylacetate	.4754E+04	.8720E-02	.1228E+00	.3474E+02
vinylchloride	.1328E+02	.0000E+00	.0000E+00	.9703E-01
Ethylbenzene	.7304E+05	.8163E-01	.1150E+01	.5337E+03

RESULTS AT TIME (DAYS) 4018.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.5526E+01	.1033E+05	.1268E+02	.6110E+02
toluene	.8466E+03	.5460E+07	.1643E+04	.2875E+05
p-xylene	.2159E+03	.4696E+07	.4712E+03	.2377E+05
111-trichloroethane	.1452E+03	.1676E+07	.1014E+04	.1144E+05
1122-tetrachloroethane	.5930E+03	.1584E+08	.1473E+05	.1289E+06
112-trichloroethane	.2930E+02	.1370E+06	.2488E+03	.2620E+04
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.2436E+02	.1898E+07	.9243E+02	.1313E+04
trichloroethene	.1960E+02	.4824E+05	.2173E+02	.1862E+03
vinylacetate	.1643E+01	.2048E+04	.2563E+01	.4576E-01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00

Stlbot.out

TOTAL MASS IN GAS PHASE (kg)	=	.1903E+01
TOTAL MASS IN FREE PHASE (kg)	=	.2981E+05
TOTAL MASS IN WATER PHASE (kg)	=	.1824E+02
TOTAL MASS IN SOIL PHASE (kg)	=	.1972E+03

S

g

SPECIES

	Stlbot.out			
tetrachloroethene	.2606E+02	.1867E+07	.9888E+02	.1405E+04
trichloroethene	.1344E+02	.3042E+05	.1491E+02	.1277E+03
vinylacetate	.7170E+00	.8220E+03	.1119E+01	.1997E-01
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.1332E+02	.2490E+05	.2076E+01	.1045E+03

TOTAL MASS IN ALL PHASE = .2795E+05

TOTAL MASS IN GAS PHASE (kg)	=	.1835E+01
TOTAL MASS IN FREE PHASE (kg)	=	.2773E+05
TOTAL MASS IN WATER PHASE (kg)	=	.1864E+02
TOTAL MASS IN SOIL PHASE (kg)	=	.1999E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S				
	g	g/m3	g/m3	mg/k
g				
benzene	.5691E+04	.8135E-02	.1146E+00	.4159E+02
toluene	.4603E+07	.1901E+01	.2677E+02	.3364E+05
p-xylene	.4474E+07	.5471E+00	.7706E+01	.3269E+05
111-trichloroethane	.1529E+07	.3517E+00	.4954E+01	.1118E+05
1122-tetrachloroethane	.1530E+08	.1517E+01	.2136E+02	.1118E+06
112-trichloroethane	.1102E+06	.6177E-01	.8701E+00	.8052E+03
11-dichloroethane	.3697E+02	.0000E+00	.0000E+00	.2701E+00
11-dichloroethene	.1967E+02	.0000E+00	.0000E+00	.1437E+00
methylenechloride	.2187E+02	.0000E+00	.0000E+00	.1598E+00
tetrachloroethene	.1869E+07	.6405E-01	.9022E+00	.1366E+05
trichloroethene	.3058E+05	.3325E-01	.4684E+00	.2234E+03
vinylacetate	.8239E+03	.1785E-02	.2514E-01	.6020E+01
vinylchloride	.9330E+01	.0000E+00	.0000E+00	.6818E-01
Ethylbenzene	.2502E+05	.3299E-01	.4647E+00	.1828E+03

RESULTS AT TIME (DAYS) 4748.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.1853E+01	.2921E+04	.4251E+01	.2049E+02
toluene	.6941E+03	.3773E+07	.1347E+04	.2357E+05
p-xylene	.2288E+03	.4195E+07	.4994E+03	.2519E+05
111-trichloroethane	.1399E+03	.1361E+07	.9764E+03	.1102E+05
1122-tetrachloroethane	.6410E+03	.1443E+08	.1593E+05	.1393E+06

	Stlbot.out			
112-trichloroethane	.2104E+02	.8290E+05	.1786E+03	.1881E+04
11-dichoroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichoroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.2792E+02	.1834E+07	.1060E+03	.1506E+04
trichloroethene	.8877E+01	.1841E+05	.9842E+01	.8433E+02
vinylacetate	.2893E+00	.3041E+03	.4515E+00	.8060E-02
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.7912E+01	.1356E+05	.1233E+01	.6208E+02

TOTAL MASS IN ALL PHASE = .2594E+05

TOTAL MASS IN GAS PHASE (kg)	= .1772E+01
TOTAL MASS IN FREE PHASE (kg)	= .2572E+05
TOTAL MASS IN WATER PHASE (kg)	= .1905E+02
TOTAL MASS IN SOIL PHASE (kg)	= .2026E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S				
	g	g/m3	g/m3	mg/k
benzene	.2948E+04	.4596E-02	.6473E-01	.2154E+02
toluene	.3799E+07	.1710E+01	.2409E+02	.2776E+05
p-xylene	.4221E+07	.5628E+00	.7927E+01	.3084E+05
111-trichloroethane	.1373E+07	.3442E+00	.4848E+01	.1003E+05
1122-tetrachloroethane	.1459E+08	.1576E+01	.2220E+02	.1066E+06
112-trichloroethane	.8499E+05	.5188E-01	.7308E+00	.6210E+03
11-dichoroethane	.3378E+02	.0000E+00	.0000E+00	.2469E+00
11-dichoroethene	.1827E+02	.0000E+00	.0000E+00	.1335E+00
methylenechloride	.2002E+02	.0000E+00	.0000E+00	.1463E+00
tetrachloroethene	.1836E+07	.6864E-01	.9667E+00	.1342E+05
trichloroethene	.1852E+05	.2197E-01	.3094E+00	.1353E+03
vinylacetate	.3048E+03	.7211E-03	.1016E-01	.2227E+01
vinylchloride	.9312E+01	.0000E+00	.0000E+00	.6805E-01
Ethylbenzene	.1363E+05	.1961E-01	.2762E+00	.9959E+02

RESULTS AT TIME (DAYS) 5113.606000

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.9883E+00	.1423E+04	.2267E+01	.1093E+02

	Stlbot.out			
toluene	.6159E+03	.3058E+07	.1195E+04	.2091E+05
p-xylene	.2350E+03	.3934E+07	.5128E+03	.2587E+05
111-trichloroethane	.1360E+03	.1209E+07	.9496E+03	.1071E+05
1122-tetrachloroethane	.6656E+03	.1369E+08	.1654E+05	.1447E+06
112-trichloroethane	.1731E+02	.6231E+05	.1470E+03	.1548E+04
11-dichoroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichoroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.2999E+02	.1799E+07	.1138E+03	.1617E+04
trichloroethene	.5617E+01	.1064E+05	.6228E+01	.5336E+02
vinylacetate	.1069E+00	.1026E+03	.1668E+00	.2977E-02
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.4460E+01	.6980E+04	.6952E+00	.3499E+02

TOTAL MASS IN ALL PHASE = .2400E+05

TOTAL MASS IN GAS PHASE (kg)	= .1711E+01
TOTAL MASS IN FREE PHASE (kg)	= .2377E+05
TOTAL MASS IN WATER PHASE (kg)	= .1947E+02
TOTAL MASS IN SOIL PHASE (kg)	= .2054E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
S	g	g/m3	g/m3	mg/k
benzene	.1437E+04	.2454E-02	.3457E-01	.1050E+02
toluene	.3080E+07	.1518E+01	.2138E+02	.2251E+05
p-xylene	.3960E+07	.5781E+00	.8142E+01	.2894E+05
111-trichloroethane	.1221E+07	.3348E+00	.4716E+01	.8919E+04
1122-tetrachloroethane	.1385E+08	.1637E+01	.2306E+02	.1012E+06
112-trichloroethane	.6403E+05	.4272E-01	.6017E+00	.4679E+03
11-dichoroethane	.3138E+02	.0000E+00	.0000E+00	.2293E+00
11-dichoroethene	.1550E+02	.0000E+00	.0000E+00	.1133E+00
methylenechloride	.1816E+02	.0000E+00	.0000E+00	.1327E+00
tetrachloroethene	.1801E+07	.7370E-01	.1038E+01	.1316E+05
trichloroethene	.1071E+05	.1391E-01	.1960E+00	.7823E+02
vinylacetate	.1029E+03	.2668E-03	.3758E-02	.7516E+00
vinylchloride	.9293E+01	.0000E+00	.0000E+00	.6790E-01
Ethylbenzene	.7020E+04	.1107E-01	.1559E+00	.5130E+02

RESULTS AT TIME (DAYS) 5478.606000

SPECIESMASS (g) IN PHASES

	Stlbot.out GAS	OIL	WATER	SOLID
benzene	.4943E+00	.6476E+03	.1134E+01	.5466E+01
toluene	.5375E+03	.2428E+07	.1043E+04	.1825E+05
p-xylene	.2407E+03	.3666E+07	.5252E+03	.2649E+05
111-trichloroethane	.1313E+03	.1061E+07	.9164E+03	.1034E+05
1122-tetrachloroethane	.6902E+03	.1292E+08	.1715E+05	.1500E+06
112-trichloroethane	.1392E+02	.4559E+05	.1182E+03	.1245E+04
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.3226E+02	.1761E+07	.1224E+03	.1739E+04
trichloroethene	.3385E+01	.5836E+04	.3754E+01	.3216E+02
vinylacetate	.3576E-01	.3123E+02	.5580E-01	.9961E-03
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.2369E+01	.3373E+04	.3692E+00	.1859E+02

TOTAL MASS IN ALL PHASE = .2212E+05

TOTAL MASS IN GAS PHASE (kg) = .1652E+01

TOTAL MASS IN FREE PHASE (kg) = .2189E+05

TOTAL MASS IN WATER PHASE (kg) = .1988E+02

TOTAL MASS IN SOIL PHASE (kg) = .2081E+03

SPECIES	MASS	CONC WELL GAS	CONC SOIL GAS	CONC SOIL MAS
	g	g/m3	g/m3	mg/k
benzene	.6547E+03	.1229E-02	.1731E-01	.4784E+01
toluene	.2448E+07	.1326E+01	.1868E+02	.1789E+05
p-xylene	.3694E+07	.5923E+00	.8342E+01	.2699E+05
111-trichloroethane	.1073E+07	.3233E+00	.4554E+01	.7840E+04
1122-tetrachloroethane	.1309E+08	.1698E+01	.2392E+02	.9562E+05
112-trichloroethane	.4698E+05	.3439E-01	.4843E+00	.3433E+03
11-dichloroethane	.2819E+02	.0000E+00	.0000E+00	.2060E+00
11-dichloroethene	.1410E+02	.0000E+00	.0000E+00	.1030E+00
methylenechloride	.1631E+02	.0000E+00	.0000E+00	.1192E+00
tetrachloroethene	.1763E+07	.7936E-01	.1118E+01	.1288E+05
trichloroethene	.5875E+04	.8396E-02	.1183E+00	.4293E+02
vinylacetate	.3132E+02	.8943E-04	.1260E-02	.2289E+00
vinylchloride	.9272E+01	.0000E+00	.0000E+00	.6775E-01
Ethylbenzene	.3395E+04	.5886E-02	.8290E-01	.2481E+02

RESULTS AT TIME (DAYS) 5478.606000

Stlbot.out

SPECIESMASS (g) IN PHASES			
	GAS	OIL	WATER	SOLID
benzene	.4943E+00	.6476E+03	.1134E+01	.5466E+01
toluene	.5375E+03	.2428E+07	.1043E+04	.1825E+05
p-xylene	.2407E+03	.3666E+07	.5252E+03	.2649E+05
111-trichloroethane	.1313E+03	.1061E+07	.9164E+03	.1034E+05
1122-tetrachloroethane	.6902E+03	.1292E+08	.1715E+05	.1500E+06
112-trichloroethane	.1392E+02	.4559E+05	.1182E+03	.1245E+04
11-dichloroethane	.0000E+00	.0000E+00	.0000E+00	.0000E+00
11-dichloroethene	.0000E+00	.0000E+00	.0000E+00	.0000E+00
methylenechloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
tetrachloroethene	.3226E+02	.1761E+07	.1224E+03	.1739E+04
trichloroethene	.3385E+01	.5836E+04	.3754E+01	.3216E+02
vinylacetate	.3576E-01	.3123E+02	.5580E-01	.9961E-03
vinylchloride	.0000E+00	.0000E+00	.0000E+00	.0000E+00
Ethylbenzene	.2369E+01	.3373E+04	.3692E+00	.1859E+02

TOTAL MASS IN ALL PHASE = .2212E+05

TOTAL MASS IN GAS PHASE (kg)	= .1652E+01
TOTAL MASS IN FREE PHASE (kg)	= .2189E+05
TOTAL MASS IN WATER PHASE (kg)	= .1988E+02
TOTAL MASS IN SOIL PHASE (kg)	= .2081E+03

SPECIES	MASS	CONC		CONC
		WELL GAS	SOIL GAS	
S				
g	g	g/m3	g/m3	mg/k
benzene	.6547E+03	.1229E-02	.1731E-01	.4784E+01
toluene	.2448E+07	.1326E+01	.1868E+02	.1789E+05
p-xylene	.3694E+07	.5923E+00	.8342E+01	.2699E+05
111-trichloroethane	.1073E+07	.3233E+00	.4554E+01	.7840E+04
1122-tetrachloroethane	.1309E+08	.1698E+01	.2392E+02	.9562E+05
112-trichloroethane	.4698E+05	.3439E-01	.4843E+00	.3433E+03
11-dichloroethane	.2819E+02	.0000E+00	.0000E+00	.2060E+00
11-dichloroethene	.1410E+02	.0000E+00	.0000E+00	.1030E+00
methylenechloride	.1631E+02	.0000E+00	.0000E+00	.1192E+00
tetrachloroethene	.1763E+07	.7936E-01	.1118E+01	.1288E+05
trichloroethene	.5875E+04	.8396E-02	.1183E+00	.4293E+02
vinylacetate	.3132E+02	.8943E-04	.1260E-02	.2289E+00

	Stlbot.out			
vinylchloride	.9272E+01	.0000E+00	.0000E+00	.6775E-01
Ethylbenzene	.3395E+04	.5886E-02	.8290E-01	.2481E+02



Appendix C – Dewatering Calculations

ACS: Dewatering Project

Cap design scenarios during dewatering:

Onsite Area, Scenario 1: Existing conditions

Onsite Area, Scenario 2: Regrade to drain

Onsite Area, Scenario 3: regrade and 1' clay cap

Onsite Area, Scenario 4: regrade, clay cap with paved areas

Offsite Area: Capped with 1' clay

Dewatering project design criteria:

1. Still bottoms area needs to be dewatered within one year.
2. System used to treat water removed during the dewatering operation can handle a maximum flow of 35 gpm.
3. Each pump within the trenches has a maximum pumping rate of 5 gpm.
4. 90% pump efficiency

Dewatering Options:

Option 1 = use existing trenches

Option 2 = use existing trenches, install separation barrier

Option 3 = use existing trenches, install separation barrier, put in place well point system

Option 4 = use existing trenches, install separation barrier, put in place well point system, surround well points with sheet pile

	<u>Onsite Area Scenario 1</u>	<u>Onsite Area Scenario 2</u>	<u>Onsite Area Scenario 3</u>	<u>Onsite Area Scenario 4</u>	<u>Capped Offsite Area</u>	<u>Area Enclosed in Sheetpile</u>
Option 1	1.1 yr / 35 gpm	1.1 yr / 35 gpm	1.0 yr / 35 gpm	1.0 yr / 35 gpm		
Option 2	0.55 yrs / 35 gpm	0.54 yrs / 35 gpm	0.50 yrs / 35 gpm	0.44 yrs / 35 gpm	0.63 yrs / 25gpm	
Option 3	1.0 yrs / 22.2 gpm	1.0 yrs / 21.7 gpm	1.0 yrs / 19.6 gpm	1.0 yrs / 17.5 gpm		
Option 4	1.2 yrs / 15 gpm	1.2 yrs / 15 gpm	1.1 yrs / 15 gpm	0.9 yrs / 15 gpm		1.0 yrs / 9.26 gpm

Summary of dewatering options:

Option 1: The entire site can be dewatered in one year if the Onsite Area is capped with clay beneath the gravel or if it is capped with clay and asphalt.

Option 2: By separating the offsite and onsite areas with a separation barrier, they can be dewatered separately. The offsite area can be dewatered in 0.63 years with the five trenches already in place. Then, the hydraulic capacity of the system can be devoted to dewatering the onsite area. The onsite area can be dewatered in approximately half a year under all scenarios.

Option 3: The dewatering of the Onsite Area under this option is achievable within a year under all four capping scenarios.

Option 4: The Still Bottoms Pond Area can be dewatered in one year with the well points operated at a pumping rate of 10.41 gpm. The area within the sheet pile could be dewatered faster than one year however the treatment system would not handle the flow hydraulically or chemically. The rest of the Onsite Area can only be dewatered within a year if capping scenario 4 is chosen.



BY APE DATE 6/22/98 CLIENT ACS SHEET 1 OF 1
CHKD. BY _____ DESCRIPTION _____ JOB NO. _____

Problem: Need to determine the infiltration to the ACS site and need to determine the time required to dewater the site by removing the current quantity of water existing at the site in addition to the infiltration.

Design Criteria: • Still bottoms area needs to be dewatered within a one year time period.
• the system which will be used to treat water removed during the dewatering operation can only handle a total flow of 35 gpm.

References: 1. Dodson, R.D., 1995. Stormwater Pollution Control: Industry and Construction NPDES Compliance, McGraw-Hill, Inc., New York.

- this reference was used to obtain the runoff coefficient for asphalt and the Rational Method in order to determine runoff from Coffey Rd.

2. Montgomery Watson, 1996. American Chemical Services, Inc. NPL Site Draft Perimeter Groundwater Containment System, 100 percent design submittal, February.

- this reference was used to obtain site specific hydrogeological parameters.

3. Environmental Laboratory, USAE Waterways Experiment Station, 1994. Hydrologic Evaluation of Landfill Performance (HELP) Model, version 3.01, 10 October.

- this computer model was used to obtain data on precipitation, evapotranspiration, temperature, solar radiation, and soil layer design. Based on synthetic weather data from the nearby location of Chicago, IL and on the soil layer design data average annual amounts of infiltration, evapotranspiration, and runoff were determined.

4. Holtz, R.D. and W.D. Kovacs, 1981. An Introduction to Geotechnical Engineering, Prentice-Hall Civil Engineering and Engineering Mechanics Series.

- this reference, in addition to consulting with T. Blair was used to determine the porosity of the water bearing layer.



BY APE

DATE 6/24/95 CLIENT ACS

SHEET 2

OF

CHKD. BY

DESCRIPTION

JOB NO.

Given: ACS site layout; Porosity data from reference #4 and interview of T. Blair; Water table data from June 1995 Quarterly Groundwater Measurements

Correct Depth of water table:	Depth to clay layer:	Porosity of water	Bearing layer:	Area:	Onsite Area	Sheetpile Area
10 ft	15 ft	0.35	13 acres	566,280 ft ²	15 acres	3.44 acres
5 ft	10 ft	0.3	15 acres	653,440 ft ²	3.3 acres	150,000 ft ²
5 ft	10 ft	0.3	3.3 acres	143,248 ft ²	3.44 acres	150,000 ft ²

Step 1: Determine existing volume of water in each area. This will be determined with the following formula: Volume of water = [Desired depth of water table - Current depth of water table] x Area x Porosity

So, for the offsite area, $V_{\text{offsite}} = [15 \text{ ft} - 10 \text{ ft}] \times 566,280 \text{ ft}^2 \times 0.35 = 990,990 \text{ ft}^3 = 7,412,600 \text{ gallons}$

$$V_{\text{onsite}} = [10' - 5'] \times 653,440 \text{ ft}^2 \times 0.30 = 480,160 \text{ ft}^3 = 7,331,600 \text{ gallons}$$

$$V_{\text{still bottoms}} = [10' - 5'] \times 143,248 \text{ ft}^2 \times 0.30 = 215,612 \text{ ft}^3 = 1,612,850 \text{ gallons}$$

$$V_{\text{sheetpile}} = [10' - 5'] \times 150,000 \text{ ft}^2 \times 0.30 = 225,000 \text{ ft}^3 = 1,683,000 \text{ gallons}$$

Step 2: Determine runoff from Colfax Road which drains into site. Use Rational Method from Reference #1

$$Q = CIA$$

Where: C = runoff coefficient, determined by land use
 $C_{\text{asphalt}} = 0.7 - 0.95$
assume $C = 0.80$

$$A = \text{drainage Area, ft}^2$$

$$I = \text{rainfall intensity, in/yr}$$


$$I = 34.15 \text{ inches/yr}$$

(Avg. Annual Precipitation) from reference 3.

$$Q = 18,213 \text{ ft}^3/\text{yr} = 136,136 \text{ gallons/yr}$$

EN 15 (10/78)

800 ft of road along onsite area and 800 ft of road along offsite area drain onto the respective areas.
 $A = (800 \text{ ft})(10 \text{ ft}) = 8000 \text{ ft}^2$





BY APR

DATE 6/29/98

CLIENT ACS

SHEET 3

OF

JOB NO.

DESCRIPTION

CHKD. BY

Step 3 Determine the quantity of infiltration to each of the areas in ACS. Primarily we are interested in infiltration to 3 areas:

- still bottoms area
- other onsite infiltration
- offsite area

The still bottoms area and the offsite area will both be capped with clay and so this will be the only soil design modeled using the HELP model. The remaining on-site area will be looked at under four different scenarios. These scenarios are listed below.

Scenario 1: remaining onsite area as it exists. 10% of surface allows runoff.

Scenario 2: remaining onsite area graded so the 12" gravel over top 15" siltysand surface allows 100% runoff.

Scenario 3: remaining onsite area graded so the 12" gravel over 12" clay over 18" siltysand surface allows 100% runoff and clay cap put beneath gravel.

Scenario 4: 70% of remaining onsite area is capped with topsoil over the cap that has a good stand of grass. Other 30% of area is paved with asphalt to allow for ACS operations.

- 70% 6" topsoil w/ grass
- 30% 6" asphalt
- 12" clay
- 12" gravel

The infiltration will be determined for the capped still bottoms area, then the 4 scenarios for the remaining onsite area, and then for the offsite area. All of the values presented are outputs from the HELP Model which is reference 3. The values generated by the HELP model for each run is written in parentheses along with the page.

$$\text{Infiltration} = 134 \text{ ft}^3/\text{yr} \times \frac{1 \text{ ft}^3}{7.48 \text{ gallons}} = 1,002 \text{ gallons}/\text{yr} = 1,002 \text{ gallons}/\text{yr} \times \frac{1 \text{ day}}{24 \text{ hours}} \times \frac{1 \text{ hour}}{60 \text{ min}} = 0.002 \text{ gallons}/\text{min}$$

Runoff from the capped still bottoms area will also be determined because this runoff will infiltrate into other areas within the onsite area.

$$\text{Runoff} = 301,729 \text{ ft}^3/\text{yr} = 2,256,933 \text{ gallons}/\text{yr}$$

Note: Contributions from the fire pond leakage into the subsurface will be neglected because the fire pond shall be emptied and filled with concrete.



BY ADE

DATE 6/29/98

CLIENT ACS

SHEET 4

OF

CHKD. BY

DESCRIPTION

JOB NO.

Remaining On-site Area : Scenario 1 : remaining onsite area as it exists. 12" gravel over top 18" silty sand. 70% of surface allows runoff.

(HELP model filename: Onsite.out, page 6)

The direct infiltration to the onsite area will be determined first with the HELP model output. Then the infiltration coming from runoff which drains onto the onsite area from Colfax Road and from the capped still bottoms area will be calculated. Of this runoff which drains to the site a certain percentage of it will evaporate and of the remaining quantity a certain percentage will be assumed to infiltrate. Based on the cap designs and on weather and evapotranspiration factors, these percentages are determined by the HELP model. First we will determine direct infiltration.

$$\text{Direct Infiltration} = \frac{390,795}{704,147 \text{ ft}^2/\text{yr}} = \frac{2,923,147 \text{ gallons/yr}}{5,267,393 \text{ gallons/yr}}$$

Now, the infiltration occurring due to runoff from other areas flowing into the onsite area will be determined.

$$\text{Runoff from Colfax Rd.} = 136,136 \text{ gallons/yr} \quad \text{from page 2.}$$

$$\text{Runoff from still bottoms area} = 2,256,933 \text{ gallons/yr} \quad \text{from page 3.}$$

$$\text{Total Runoff to onsite area} = 2,393,069 \text{ gallons/yr}$$

As can be seen in the HELP file - Onsite.out, page 6 - $\frac{63.1}{48.5}\%$ of the water entering the onsite area is lost to evapotranspiration. Therefore, $\frac{63.1}{48.5}\%$ of the total runoff to the onsite area will be lost to evapotranspiration and $\frac{36.9}{54.5}\%$ will remain behind. As can also be seen in the HELP file, $\frac{26.9}{48.5}\%$ of water on the site percolates through layer 2. It is therefore assumed that $\frac{26.9}{48.5}\%$ of the $\frac{36.9}{54.5}\%$ of the total runoff remaining will infiltrate.

$$\begin{aligned} \text{Additional runoff infiltration} &= \left[2,393,933 \text{ gallons/yr} - \left(\frac{63.1}{48.5}\% \right) (2,393,933 \text{ gal/yr}) \right] \left(\frac{26.9}{48.5}\% \right) \\ &= \frac{237,624.9 \text{ gal/yr}}{632,776 \text{ gallons/yr}} \end{aligned}$$

The total infiltration to the onsite area will be the sum of the direct infiltration and the additional runoff infiltration.

$$\text{Total Infiltration} = \frac{2,923,147 \text{ gal/yr}}{5,267,393 \text{ gal/yr}} + \frac{237,624 \text{ gal/yr}}{632,776 \text{ gal/yr}} = \frac{5,900,159 \text{ gal/yr}}{11.22 \text{ gal/min}}$$

$$3,160,771 \text{ gal/yr} = 6.01 \text{ gal/min}$$



BY APE

DATE 6/29/98

CLIENT ACS

SHEET 5

OF

Remaining On-site Area: Scenario 2 remaining on-site area segregated to allow 100% runoff.

(HELP Model File: Onsite3.out, page 6) First, find the infiltration
Direct Infiltration = $\frac{360,942}{2,699,846} \text{ gal/yr} = \frac{5,149,815}{2,699,846} \text{ gal/yr}$

From the summation of runoff contributions to the on-site area on page 4 we know the total runoff to the on-site area. - Total Runoff to on-site area: 2,393,064 gal/yr.

62.0% of the water entering the on-site area in scenario 2 is lost to evapotranspiration. Of the 55% remaining it is assumed that 47.5% will infiltrate, because the percentage of water infiltrating the site is 47.5%. 25.0% 62%
additional runoff infiltration = $[2,393,064 \text{ gal/yr} - (47.5\%)(2,393,064 \text{ gal/yr})](47.5\%)$
25.0

Total infiltration = $\frac{5,149,815}{2,699,846} \text{ gal/yr} + \frac{628,188}{227,341} \text{ gal/yr} = \frac{5,777,000}{2,927,187} \text{ gal/yr} = \frac{10.49}{5.57} \text{ gal/min}$

Remaining On-site Area: Scenario 3: remaining on-site area segregated to allow 100% runoff and with a 12" clay layer beneath 12" of gravel.

(HELP Model File: Onsite S.out, pg. 6)

Direct Infiltration: $\frac{241,392}{1,805,612} \text{ gal/yr} = \frac{1,965,512}{1,805,612} \text{ gal/yr}$

The summation of total runoff contributions to the on-site area on page for yields:

Total runoff to on-site area: 2,393,064 gal/yr.

64% of the water entering the on-site area in scenario 3 is lost to evapotranspiration. Of the 36% remaining it is assumed that 18% of it shall infiltrate because this is the percentage of water which infiltrates the soil. 17

additional runoff infiltration = $[2,393,064 \text{ gal/yr} - (2,393,064 \text{ gal/yr})(64\%)](18\%)$

= $\frac{155,070}{146,456} \text{ gal/yr}$

Total infiltration = $\frac{1,965,512}{1,805,612} \text{ gal/yr} + \frac{155,070}{146,456} \text{ gal/yr} = \frac{2,120,582}{1,952,068} \text{ gal/yr} = \frac{4.03}{3.71} \text{ gal/min}$



BY APR

DATE 6/29/98

CLIENT ACS

SHEET 6

OF

JOB NO.

DESCRIPTION

CHKD. BY

Remaining On Site Area: Scenario 4 : capping of 70% of the remaining onsite area with 12" clay beneath 6" topsoil with a good stand of grass and paving of the remaining 30% of the onsite area. 100% runoff allowed.

(HELP Model file: Cap on 2.out, pg. 6)
(HELP Model file: Asphalt.out, pg. 6)

The paved area was modeled as though it was 6" clay overlying 12" of gravel.

Direct infiltration through the paved area = $\frac{128 \text{ ft}^3}{1040 \text{ yr}} = 9.5 \text{ gal/yr}$

Runoff from paved area = $322,185 \text{ ft}^3/\text{yr} = 2,409,944 \text{ gal/yr}$

✓ This runoff goes into the capped grassy area

Direct infiltration through capped grassy area = $1588 \text{ ft}^3/\text{yr} = 11,878 \text{ gal/yr}$

Total Direct Infiltration = $12,835 \text{ gal/yr}$

The total runoff into the capped grassy area which contributes to the additional runoff infiltration will be runoff from Colfax Rd., runoff from the capped still bottoms area, and runoff from the paved area.

Total runoff to the onsite area = $2,393,064 \text{ gal/yr} + 2,409,944 \text{ gal/yr} = 4,803,000 \text{ gal/yr}$

Summation from page 4

Assume that all runoff ends up in the capped grassy area.

From HELP file: Cap on 2.out, page 6, Evapotranspiration accounts for 73% of the water lost from the site. Of the remaining 27% it will be assumed that only 0.15% infiltrates as that is the quantity of water shown to infiltrate in the HELP file.

additional runoff infiltration = $[4,803,000 \text{ gal/yr} - (73\%)(4,803,000 \text{ gal/yr})](0.15\%)$

= $1,945 \text{ gal/yr}$

14,863

Total infiltration = $\frac{12,835 \text{ gal/yr}}{12,918} + 1,945 \text{ gal/yr} = \frac{14,780 \text{ gal/yr}}{14,863} = 0.028 \text{ gal/yr}$



BY APC

DATE 6/29/78

CLIENT ATC

SHEET 7

OF

JOB NO.

DESCRIPTION

CHKD. BY

Conclusion: The infiltration rates, according to the HELL model, to the capped still bottoms area and the offsite area are acceptable with the intended cap design.

where: k = hydraulic conductivity in cm/sec.

12" clay $k = 5.0 \times 10^{-7}$ cm/sec

12" gravel $k = 0.3$ cm/sec

18" silty sand $k = 7.2 \times 10^{-2}$ cm/sec

Still bottoms Area (3 layers) cap =

evaporative zone depth is 18"

12" clay $k = 5.0 \times 10^{-7}$ cm/sec

18" silty sand $k = 7.2 \times 10^{-2}$

evaporative zone depth is 18"

Offsite area cap = (2 layers)

The infiltration rates to the remaining on-site areas are poor in scenarios 1 and 2. The reason for this is because of the high hydraulic conductivity of the gravel and silty sand and the fact that the evaporative zone depth is only 6". In scenario 3 the infiltration rate is fair because of the clay layer underlying the gravel. Scenario 4 is the best option because the clay on top with grass increases the evaporative zone depth to 18" and increases the quantity of water lost to evapotranspiration. Also, the asphalt and clay layers are both less permeable to water and help to reduce the quantity of infiltration.

depressions only allow 70% runoff

"other" on-site areas

Scenario 2

12" gravel $k = 0.3$ cm/sec

18" silty sand $k = 7.2 \times 10^{-2}$

12" gravel $k = 0.3$ cm/sec

18" silty sand $k = 7.2 \times 10^{-2}$


Scenario 4

12" gravel $k = 0.3$ cm/sec

12" clay $k = 5.0 \times 10^{-7}$ cm/sec

18" silty sand $k = 7.2 \times 10^{-2}$

Scenario 3





BY APE DATE 6/19/98 CLIENT ACS SHEET 8 OF
 CHKD. BY DESCRIPTION JOB NO.

Infiltration to Offsite Area : offsite area is capped with 12" clay over top of 18" siltysand.

(HELP Model file: Offsite 2.out, pg. 6)

$$\text{Direct Infiltration} = 293 \text{ ft}^3/\text{yr} = \boxed{2,192 \text{ gal/yr}}$$

Runoff from Colfax Road is the only other major contribution of water to the site.

$$\text{Total Runoff to site} = 136,136 \text{ gal/yr} \quad (\text{from page 2})$$

26% of the water entering the site is lost to evapotranspiration. 74% of the runoff from Colfax Road will come onto the site where 0.018 % of it shall infiltrate.

$$\begin{aligned} \text{additional runoff infiltration} &= \left[136,136 \text{ gal/yr} - (26\%)(136,136 \text{ gal/yr}) \right] (0.018\%) \\ &= \boxed{18 \text{ gal/yr}} \end{aligned}$$

This seems unrealistic

$$\text{Total infiltration} = \boxed{2,210 \text{ gal/yr} = 0.0042 \text{ gal/min}}$$

Step 4 Summarize infiltration rates. We are interested in the infiltration to:

- the capped still bottoms area
- the "other" onsite area (4 scenarios)
- offsite area

<u>Area</u>	<u>infiltration rate</u>
capped still bottoms area	1002 gal/yr = 0.002 gal/min
"other" onsite areas	
Scenario 1	5,900,159 gal/yr = 11.22 gal/min
Scenario 2	5,775,000 gal/yr = 10.99 gal/min
Scenario 3	2,120,582 gal/yr = 4.03 gal/min
Scenario 4	14,780 gal/yr = 0.028 gal/min
offsite	2,210 gal/yr = 0.0042 gal/min

* These infiltration rates also represent the pumping rate needed to offset infiltration.



BY APE

DATE 6/24/98

CLIENT ACS

SHEET 9 OF



CHKD. BY

DESCRIPTION

JOB NO.

Determine the infiltration to the sheet pile enclosed area.

The sheet pile enclosed area has the following basic dimensions:



As can be seen in the above sketch, the sections of sheet pile will project above the ground surface effectively preventing any runoff. A certain percentage of precipitation will be lost to evaporation. The rest shall be assumed to infiltrate.

(HELP Model literature: Stillbot. out, pg. 6)

Precipitation = 34.15 inches

Evapotranspiration = 8.95 inches

$$\text{Precipitation (inches)} - \text{Evapotranspiration (inches)} = \text{Infiltration (inches)}$$

$$\frac{\text{Infiltration (inches)}}{12} \times \text{Area of sheet pile enclosed area (ft}^2\text{)} = \text{ft}^3 \text{ of infiltrat}$$

$$\text{Infiltration} = 34.15'' - 8.95'' = 25.20'' \times \frac{1 \text{ ft}}{12''} = 2.1 \text{ ft}$$

$$\text{Infiltration} = 2.1 \text{ ft} \times 150,000 \text{ ft}^2 = 315,000 \text{ ft}^3 = 2,356,200 \text{ gallons/yr} = \boxed{4.48 \text{ gal/min}}$$

Assume 5% of water located outside of sheet pile enclosed area will leak through the sheetpile.

Volume of water outside sheetpile = Volume of water onsite - Volume of water inside sheetpile

Reference pg. 2 for
volumes

$$\text{Volume outside} = 7,331,600 \text{ gallons} - 1,683,000 \text{ gallons} = 5,648,600 \text{ gallons}$$

$$\text{Leakage} = (5\%)(5,648,000 \text{ gallons}) = 282,430 \text{ gallons/yr} = \boxed{0.54 \text{ gallons/min}}$$

Also, assume approximately 1% of precipitation which infiltrates the remaining on site area will leak through the sheetpile. At most this will be = $(11.22 \text{ gal/min})(1\%) = \boxed{0.11 \text{ gal/min}}$



BY APE DATE 6/29/98 CLIENT ACS SHEET 10 OF
CHKD. BY DESCRIPTION JOB NO.

Total infiltration to the sheetpile enclosed area = $4.48 \text{ gal/min} + 0.54 \text{ gal/min} + 0.11 \text{ gal/min}$

$$= \boxed{5.13 \text{ gal/min}} = 2,696,328 \text{ gal/yr}$$

This seems a bit high for an area capped mostly with clay. The infiltration rate to the capped still bottoms area was only 6002 gal/yr. Because the sheetpile prevents any runoff from escaping the entire quantity of water which is not lost to evaporation is assumed to infiltrate.

* Run the HELP Model for the sheetpile area assuming it is entirely capped with clay and that it allows 0% runoff.



Step 5: Determine time required to dewater ACS site.

There will be six different options for dewatering the ACS site which will be investigated. These options are described below.

Option 1: Use 8 existing trenches within the ACS site each pumping at 4.38 gpm to dewater the entire site at a design criteria rate of 35 gpm.

Option 2: Put in a separation barrier between the onsite and offsite areas and dewater each area separately using only their respective trenches operated at 5 gpm each.

Option 3: Put in a separation barrier and pump the onsite area with 3 trenches at 5 gpm each and place a well point system around the contaminated still bottoms area to increase the dewatering rate.

Option 4: Put in a separation barrier between onsite and offsite areas and install sheet pile to enclose the contaminated area. Then put in a well point system inside the sheet pile enclosed area and dewater the enclosed area with well points and the outside area with 3 trenches.

Option 5: Install the sheet pile with the well points inside and also operate the 8 trenches to dewater the entire site outside the sheet pile. Do not install a separation barrier.

Option 6: Dewater the entire ACS site using a well point system installed around the contaminated still bottoms area.

* Assume 80% efficiency for all trenches and well point systems.

Option 1 Use the 8 existing trenches operating at the design criteria flow of 35 gpm. First the entire volume of existing water on the site must be found.

Total Volume of preexisting water in entire site = $V_{\text{onsite}} + V_{\text{offsite}}$ (see page 2 for Volumes)

$$V_{\text{total}} = 7,331,600 \text{ gal} + 7,412,600 \text{ gal} = 14,744,200 \text{ gal}$$

$$\# + 80\% \text{ efficiency} = 35 \text{ gpm} \times 0.80 = 28 \text{ gpm}$$

The infiltration to the site will vary depending upon which on site capping scenario is chosen. Consult page 8 to see infiltration rates for the different options.

$$\text{Scenario 1 total infiltration to site} = 0.002 \text{ gal/min} + 11.22 \text{ gal/min} + 0.004 \text{ gal/min} = 11.22 \text{ gal/min}$$

$$= 11.22 \text{ gal/min} = 6.02 \text{ gal/min}$$



Option 1 (scenario 1, cont.)

total infiltration to site = 11.23 gal/min

This infiltration will try to fill the site with water as the dewatering project attempts to dewater the site. Since they oppose each other, the infiltration rate will be subtracted from the pumping rate to get the adjusted pumping rate.

Pumping Rate - Infiltration rate = adjusted pumping rate

$$\frac{V_{\text{total}}}{\text{time to dewater}} = \text{adjusted pumping rate}$$

to dewater site in 1 year pumping rate required would be:

$$14,744,200 \text{ gal/yr} = 28 \text{ gpm} + \text{infiltration rate}$$

$$= 39.23 \text{ gpm} \times 0.80 = 49.04 \text{ gpm}$$
 this exceeds the design criteria.

Scenario 2 12" gravel regressed to allow 100% runoff in the site area.

total infiltration to site = $0.002 \text{ gal/min} + 10.44 \text{ gal/min} + 0.004 \text{ gal/min}$ = 5.57

$$= \frac{5.58 \text{ gpm}}{11.00 \text{ gal/min}}$$

time to dewater = $\frac{14,744,200 \text{ gal}}{(28 \text{ gpm} - 11.23 \text{ gpm})} = \frac{14,744,200 \text{ gal}}{16.77 \text{ gpm}} = 1.65 \text{ years}$

design criteria.

Scenario 3 12" gravel regressed to allow 100% runoff and the installation of a 12" clay layer beneath the gravel.

total infiltration to site = $0.002 \text{ gpm} + 4.03 \text{ gpm} + 0.004 \text{ gpm}$ = 4.04 gpm

time to dewater = $\frac{14,744,200 \text{ gal}}{(28 \text{ gpm} - 4.04 \text{ gpm})} = \frac{14,744,200 \text{ gal}}{23.96 \text{ gpm}} = 1.17 \text{ years}$

Scenario 4 70% of remaining on site area cropped w/12" clay beneath 6" topsoil with a good stand of grass and the remaining 30% of the on site area paved with asphalt.

total infiltration to site = $0.002 \text{ gpm} + 0.028 \text{ gpm} + 0.004 \text{ gpm}$

$$= 0.034 \text{ gpm}$$

time to dewater = $\frac{14,744,200 \text{ gal}}{(28 \text{ gpm} - 0.034 \text{ gpm})} = 1.00 \text{ years}$



BY APE

DATE 6/29/99

CLIENT ACS

SHEET 13

OF

CHKD. BY

DESCRIPTION

JOB NO.

Option 1Conclusion:

It will be impossible to dewater the entire site within 1 year at a pumping rate that does not exceed 35 gpm in Scenario's one through three. In the fourth scenario the site can be dewatered in exactly one year.
 ↑ Costly, Not likely to be done in 1 yr.

∴ * Option 1 for dewatering the entire ACS site is not a viable option.

Option 2

Install a separation barrier between the onsite and offsite areas and dewater each separately using the trenches.

Onsite Area - the onsite area infiltration rate will vary depending upon the capping scenario chosen. Infiltration rate data on pg. 8.

Total volume preexisting water in onsite area = 7,331,600 gal.

3 trenches:

Max pumping rate = 15 gpm

Scenario 1 total infiltration to onsite area = 0.002 gpm + $\frac{11.22 \text{ gpm}}{6.01}$ (12" gravel w/70% allowing runoff.)

$(15 \text{ gpm}) \cdot 0.86 = 12.9 \text{ gpm}$
 $0.90 = 13.5 \text{ gpm}$

$= \frac{11.22 \text{ gpm}}{6.01}$

time to dewater = $\frac{7,331,600 \text{ gal.}}{\frac{12 \text{ gpm}}{13.5} - \frac{11.22 \text{ gpm}}{6.01}} =$

17.88 years

1.86 ~~years~~

Scenario 2 - regrading of gravel to allow 100% runoff.

total infiltration = 0.002 gpm + $\frac{10.99 \text{ gpm}}{5.57}$
 $= \frac{10.99 \text{ gpm}}{5.57}$

time to dewater = $\frac{7,331,600 \text{ gal.}}{\frac{12 \text{ gpm}}{13.5} - \frac{10.99 \text{ gpm}}{5.57}} =$

13.81 years

1.76 years

Scenario 3 - regrading of gravel to allow 100% runoff and place 12" clay layer beneath gravel.

total infiltration = 0.002 gpm + $\frac{4.03 \text{ gpm}}{3.71}$
 $= \frac{4.03 \text{ gpm}}{3.71}$

time to dewater = $\frac{7,331,600 \text{ gal.}}{\frac{12 \text{ gpm}}{13.5} - \frac{4.03 \text{ gpm}}{3.71}} =$

1.75 years

1.42 yrs



Option 2 (cont.)
Onsite Area

Scenario 4 - capping of 70% of onsite w/ clay and grass and paving of 30% of site.

$$\text{Total infiltration} = 0.002 \text{ gpm} + 0.028 \text{ gpm} = 0.03 \text{ gpm}$$

$$\text{Time to dewater} = \frac{7,331,600 \text{ gal}}{12 \text{ gpm} - 0.03 \text{ gpm}} = 1.16 \text{ years}$$

Offsite Area The offsite area is capped with 12" clay over top 18" silt/sand. There are 5 trenches which could pump at a maximum rate of 25 gpm.

$$25 \text{ gpm} \times 0.80 = 20 \text{ gpm}$$

Total volume preexisting water in offsite area = 7,412,600 gallons

$$\text{Total infiltration to offsite area} = 0.0042 \text{ gpm} \text{ — from pg. 8}$$

$$\text{Time to dewater} = \frac{7,412,600 \text{ gal}}{20 \text{ gpm} - 0.0042 \text{ gpm}} = 0.71 \text{ years}$$

pumping rate required to dewater offsite area in 1 yr.

$$7,412,600 \text{ gal/yr} = 14.10 \text{ gpm} \times 0.80 = 17.63 \text{ gpm} + \text{infiltration}$$

Option 2 Conclusion

The onsite area can not be dewatered within one year with only 3 trenches with a maximum pumping capacity of 15 gpm.

The offsite area can be dewatered in less than one year at the maximum pumping rate of 25 gpm. At a pumping rate of 17.63 gpm the offsite area can be dewatered in one year.



BY _____ DATE _____ CLIENT _____ SHEET 15 OF _____
 CHKD. BY _____ DESCRIPTION _____ JOB NO. _____

Option 3 dewater the onsite area with well point system around still bottoms area and 3 trenches within onsite area.

Total Volume to be removed within 1yr = existing water + 1 yr of infiltration.

existing volume of water in onsite area = 7,331,600 gallons (from pg. 2)

The infiltration to the capped still bottoms area is 1,002 gal/yr.

The infiltration to the remaining onsite areas varies with the capping scenario. The total infiltration will be equivalent to the infiltration to the capped still bottoms area added on to the infiltration rate to the remaining onsite area for the given scenario. The various infiltration rates are summarized in step 4.

Scenario 1 Total infiltration = $1,002 \text{ gal/yr} + \frac{5,900,159 \text{ gal}}{3,160,771} = \frac{5,901,161 \text{ gal}}{3,161,773}$

Total volume to be removed = $7,331,600 \text{ gal} + \frac{5,900,159 \text{ gal}}{3,161,773} = \frac{13,232,761 \text{ gallons}}{10,493,373}$
 $\frac{13,232,761 \text{ gal}}{1 \text{ yr}} = \frac{25.18 \text{ gpm}}{19.96} = \frac{31.50 \text{ gpm}}{22.20 \text{ gpm}}$ pumping rate needed w/ well points and 3 trenches to dewater w/in 1yr.

Assuming 3 trenches are operated at max of 15 gpm the pumping rate of the well point system will need to be $\frac{31.50 - 15}{22.2 - 13.5} = \frac{16.5 \text{ gpm}}{8.7 \text{ gpm}}$

Scenario 2 Total infiltration = $1,002 \text{ gal/yr} + \frac{5,775,000 \text{ gal}}{2,927,187} = \frac{5,786,000 \text{ gal}}{2,928,189}$

Total volume to be removed = $7,331,600 \text{ gal} + \frac{5,775,000 \text{ gal}}{2,928,189} = \frac{13,087,600 \text{ gal}}{10,259,789}$
 $\frac{13,087,600 \text{ gal}}{1 \text{ yr}} = \frac{19.52 \text{ gpm}}{24.90 \text{ gpm}} = \frac{31.12 \text{ gpm}}{21.70 \text{ gpm}}$ pumping rate needed w/ well points and 3 trenches to dewater area in 1yr.

Assuming 3 trenches are operated at max of 15 gpm the pumping rate of the well point system will need to be $\frac{31.12 - 15}{21.7 - 13.5} = \frac{16.12 \text{ gpm}}{8.2 \text{ gpm}}$

Scenario 3 Total infiltration = $1,002 \text{ gal/yr} + \frac{2,120,582 \text{ gal}}{1,952,058} = \frac{2,121,584 \text{ gal}}{1,953,060}$

Total volume to be removed = $7,331,600 \text{ gal} + \frac{2,120,582 \text{ gal}}{1,953,060} = \frac{9,453,184 \text{ gal}}{9,284,660}$
 $\frac{9,453,184 \text{ gal}}{1 \text{ yr}} = \frac{17.66 \text{ gpm}}{17.98 \text{ gpm}} = \frac{22.48 \text{ gpm}}{19.63}$ pumping rate needed w/ well points and 3 trenches to dewater area in 1 year.

Assuming 3 trenches are operated at max of 15 gpm the pumping rate of the well point system will need to be $\frac{22.48 - 15}{19.63 - 13.5} = \frac{6.13 \text{ gpm}}{7.48 \text{ gpm}}$



BY _____ DATE _____ CLIENT _____ SHEET 16 OF _____
 CHKD. BY _____ DESCRIPTION _____ JOB NO. _____

Scenario 4
 Total Infiltration = 1,002 gpy + 14,780 gpy = 15,782 gpy

Total volume to be removed = 7,331,600 gal + 15,782 gal = 7,347,382 gal

$7,347,382 \text{ gal} / 13.98 \text{ gpm} / 0.80 = 17,447 \text{ gpm}$
 pumping rate needed for whole system

with 3 traches operating at max of 15 gpm:

Pumping rate of well point system = 2,447 gpm

Option 3
Conclusion: With the onsite area isolated from the offsite area by a barrier wall, the dewatering

of the onsite area with a well point system and the three trenches is achievable within a year under all 4 scenarios. However, under the first two scenarios

the design criteria pumping rate is approached. This means there will likely be no pumping capacity available for dewatering the offsite area. Under the

third scenario there is a little more than 10 gpm pumping capacity left in the system.

The fourth scenario allows for the most flexibility. The well point system pumping ^{the onsite area} rate could be increased more to dewater less than a year or power could be

devoted to dewatering the offsite area simultaneously.



Option 4

CHKD BY

BY APE

DESCRIPTION

DATE 6/29/98

CLIENT

ACS

JOB NO.

SHEET

17

OF

Within 1 year the total volume which must be removed to effectively dewater a particular area

equals → Infiltration water + Existing water = total volume

total volume $\div 0.80 = 9.90$ Pumping rate required assuming 80% efficiency of pumps
Sheet pile enclosed area → Total Volume = 2,696,328 gal/yr + 1,683,000 gallons = 4,379,328 gallons

To dewater 4,379,328 gallons in 1 yr you need a pumping rate of:

$$4,379,328 \text{ gal/yr} \div 0.80 = 5,474,160 \text{ gal/yr}$$

The remaining area outside the sheetpile can be determined. Then add infiltration to the onsite area.

$$V_{\text{onsite}} - V_{\text{sheetpile}} = V_{\text{remaining}}$$

Remaining + V. Infiltration = Volume to be dewatered.

$$7,331,600 \text{ gallons} - 1,683,000 \text{ gallons} = 5,648,600 \text{ gallons}$$

This is the volume remaining in the rest of the onsite area.

The infiltration to the remaining on site area varies depending upon which cap is selected. Below the total volume remaining, which was calculated above, shall be added to the infiltration for each scenario and a corresponding pumping rate shall be developed in a manner similar as to what was done above.

Scenario 1: $5,900,159 \text{ gal/yr} + 5,648,600 \text{ gal} = 11,548,759 \text{ gallons}$
This is the volume to be dewatered

$$11,548,759 \text{ gallons/yr} \div 21.97 \text{ gal/min} = 16.76$$

This pumping rate is higher than can be achieved by the three trailers because they can only pump at 5 gpm.

Maximum pumping capacity of three trailers = 15 gpm.

At 15 gpm the time to dewater the area outside the sheetpile is equal to:

$$11,548,759 \text{ gal} \div 15 \text{ gal/min} = 769,917 \text{ minutes} = 1.24 \text{ years}$$

13.5 $\times 0.80 = 10.8$ gal/min ~ Maximum pumping of all 3 trailers at 80% efficiency - 90%

BY APE
CHKD. BY

DATE 6/20/98

CLIENT ACS

DESCRIPTION

Scenario 2: 2,927,187

$$5,755,000 \text{ gal/yr} + 5,648,600 \text{ gal} = 11,403,600 \text{ gal} = \text{Volume to be dewatered}$$

$$\frac{11,403,600 \text{ gal}}{16.32} = 704,632 \text{ gal/yr}$$

$$\frac{704,632 \text{ gal/yr}}{15 \text{ gpm}} = 1.21 \text{ years}$$

This pumping rate is higher than can be achieved by the three trenches.

Maximum pumping capacity of three trenches = 15 gpm

$$\text{time to dewater} = \frac{11,403,600 \text{ gal}}{15 \text{ gpm}} = 1.45 \text{ years}$$

Scenario 3: 1,952,068

$$2,120,582 \text{ gal/yr} + 5,648,600 \text{ gal} = 7,769,182 \text{ gal} = \text{Volume to be dewatered}$$

$$\frac{7,769,182 \text{ gal}}{14.46 \text{ gal/min}} = 537,979 \text{ gal/yr}$$

$$\frac{537,979 \text{ gal/yr}}{13.5 \text{ gpm}} = 1.07 \text{ yrs}$$

May be achievable with the three trenches.

Not achievable assuming trenches only 80% efficient.

7,600,668
13.5 gpm

Scenario 4: 14,780 gal/yr + 5,648,600 gal = 5,663,380 gal

$$\frac{5,663,380 \text{ gal}}{12.0 \text{ gpm}} = 471,948 \text{ gal/yr}$$

$$\frac{471,948 \text{ gal/yr}}{10.77 \text{ gal/min}} = 43,896 \text{ gal/yr}$$

$$\frac{43,896 \text{ gal/yr}}{0.80} = 54,870 \text{ gal/yr}$$

$$\frac{54,870 \text{ gal/yr}}{13.47 \text{ gal/min}} = 4.07 \text{ years}$$

achievable even with three trenches operating at only 80% efficiency.

Option 4
Conclusion:

The area enclosed within the sheetpile can be effectively dewatered in one year at a pumping rate of 10.41 gpm assuming the pumps are only 80% efficient.

In order to dewater the area outside of the sheet pile with only three trenches within one year it will be necessary to pave 30% of the area and cap the remaining 70% of the on-site area and seed it with grass. Even with the extensive capping plan of scenario 4 the 3 trenches will need to be operated at nearly maximum capacity in order to effectively dewater the remaining outside area.

BY APEDATE 6/24/98CLIENT ACS

SHEET _____

OF _____

CHKD. BY _____

DESCRIPTION Amendment to Option 4

JOB NO. _____

Option 4HELP filename:
sheet.out, pg 6

If we consider infiltration to the sheet pile using the HELP model the quantity of infiltration is equal to $1461 \text{ ft}^3/\text{yr} = 10,928 \text{ gal/yr}$. Most of the precipitation that falls in the sheetpile enclosed area evaporates (99.5%). This is because the rate of percolation into the packed clay is very slow. The majority of the water ponds on the surface and over time is lost to evaporation.

$$\begin{aligned} \text{Total volume within sheet pile area} &= \text{existing water} + \text{infiltrating water} \\ &= 1,683,000 \text{ gallons}^{\text{from pg. 2}} + 10,928 \text{ gal/yr} \end{aligned}$$

$$\text{Total volume} = 1,693,928 \text{ gallons}$$

To dewater 1,693,928 gallons in 1 year you need a pumping rate of:

$$1,693,928 \frac{\text{gal}}{\text{yr}} = 3.22 \text{ gpm} / 0.80 = \boxed{4.03 \text{ gpm}}$$



BY APE DATE 6/29/98 CLIENT ACS SHEET 19 OF
 CHKD. BY DESCRIPTION JOB NO.

Option 5 Install the sheetpile with the well points inside and operate the 8 trenches outside the sheet pile area. Do not install the separation barrier.

Volume of water existing in sheet pile area = 1,683,000 gallons

Volume of water in remaining on site area = 5,648,600 gallons

Volume of water in offsite area = 7,412,600 gallons

Total Volume to be removed from outside the sheetpile area = 5,648,600 gal + 7,412,600 gal = 13,061,200 gal

As determined in option 4 the pumping rate required to dewater the area inside the sheetpile

within one year is 10.41 gal/min

Remaining pumping capacity = 24.6 gpm $\times 0.80$

= 19.68 gpm

assuming 80% efficiency

The rest of the ACS site will be dewatered by the 8 trenches located around the site.

Volume to be dewatered within 1 year = 13,061,200 gallons + infiltration

The infiltration will vary depending upon which capping scenario is chosen.

total infiltration = "other" on-site infiltration + offsite area infiltration.

so small relative to on-site that it is negligible.

(see pg. 8 for infiltration data)

Scenario 1

total infiltration = 11.22 gpm

time to dewater = $\frac{\text{total volume outside sheetpile}}{(\text{remaining pumping capacity}) - (\text{infiltration})}$

time to dewater = $\frac{13,061,200 \text{ gal}}{19.68 \text{ gpm} - 11.22 \text{ gpm}} = \boxed{2.94 \text{ years}}$

Scenario 2

total infiltration = 10.99 gpm

time to dewater = $\frac{13,061,200 \text{ gal}}{19.68 \text{ gpm} - 10.99 \text{ gpm}} = \boxed{2.86 \text{ years}}$

Scenario 3

total infiltration = 4.03 gpm

time to dewater = $\frac{13,061,200 \text{ gal}}{(19.68 - 4.03) \text{ gpm}} = \boxed{1.59 \text{ years}}$

Scenario 4

total infiltration = 0.028 gpm + 0.004 gpm = 0.032 gpm

time to dewater = $\frac{13,061,200 \text{ gal}}{19.68 \text{ gpm} - 0.032 \text{ gpm}} = \boxed{1.26 \text{ years}}$



MONTGOMERY WATSON

BY APE DATE 6/29/98 CLIENT ACS SHEET 20 OF
CHKD. BY DESCRIPTION JOB NO.

Option 5 Conclusion

The area inside the sheetpile can be completely dewatered in one year at a pumping rate of 10.41 gpm. The rest of the ACS site cannot be dewatered in any time less than a year with the remaining pumping capacity and stay within the design criteria pumping rate of 35 gpm.



BY APF

CHKD. BY _____

DESCRIPTION _____

DATE 6/29/98

CLIENT ACS

SHEET 21

OF _____

JOB NO. _____

Option 6 De water the entire ACS site with well point system installed around contaminated still bottoms area.

Total Volume of existing water to be removed = 14,744,200 gallons. (see pg. 2 for volumes)

Infiltration rate to site depends upon the capping scenario selected.

Scenario 1

total infiltration to site = 11.23 gpm = 5,902,488 gal/yr (From option 1 notes)

total volume to be removed in 1 yr = 14,744,200 gal + 5,902,488 gal

= 20,646,688 gal

pumping rate required to remove total in 1 yr = $\frac{20,646,688 \text{ gal}}{\text{yr}} = 39,28 \text{ gpm} \times 0.80 = 49.10 \text{ gpm}$

Scenario 2

total infiltration rate = 11.00 gpm = 5,781,600 gpy

total to be removed in 1 yr = 14,744,200 gal + 5,781,600 gpy = 20,525,800 gal

pumping rate necessary = $\frac{20,525,800 \text{ gal}}{\text{yr}} = 39.05 \text{ gpm} \times 0.80 = 48.82 \text{ gpm}$

Scenario 3

total infiltration rate = 4.04 gpm = 2,123,424 gpy

total to be removed in 1 yr = 14,744,200 gal + 2,123,424 gal = 16,867,624 gal

pumping rate necessary = $\frac{16,867,624 \text{ gal}}{\text{yr}} = 32.10 \text{ gpm} \times 0.80 = 40.12 \text{ gpm}$

Scenario 4


total infiltration rate = 0.034 gpm = 17,870 gpy

total to be removed in 1 yr = 14,744,600 gal + 17,870 gal = 14,762,470 gal

pumping rate necessary = $\frac{14,762,470 \text{ gal}}{\text{yr}} = 28.10 \text{ gpm} \times 0.80 = 35.11 \text{ gpm}$

Option 6 Conclusion

The entire site cannot be dewatered in less than 1 year using a well point system and remaining within the design criteria pumping rate. Only in the fourth scenario can the entire site be dewatered in nearly as short a time as one year and remain at the design pumping rate of 35.0 gpm.



Appendix D – HELP Model results

Table 2. HELP4 Results for Modeled Scenarios
ACS NPL Site

Trial Cover Design Number and Description		Average Annual Totals			Peak Daily Values	
		inches	cubic feet	percent	inches	cubic feet
Offsite Cap Design						
Cap 1 - Standard RCRA Model Cap	(6"OL, 18"ML, 12"SP, FML, 24"CL)					
Precipitation		34.15	647,013	100	4.64	87,921
Runoff		2.86	62,407	8.39	2.06	44,851
Evapotranspiration		25.47	554,649	74.58	--	--
Percolation Through Cover		0.00021	4.65	0.00062	0.00046	10.11
Lateral Drainage Collected		5.8	126,345	16.99	0.03	651
Cap 2 - Alternative Cap	(6"OL, 18"ML, Geosynthetic, FML, GCL, 12"CL)					
Precipitation		34.15	647,013	100	4.64	87,921
Runoff		5.17	112,633	15.15	2.27	49,451
Evapotranspiration		28.97	630,898	84.83	--	--
Percolation Through Cover		0.0038	83.08	0.011	0.00022	4.71
Cap 3 - Alternative Cap	(6"OL, 12"ML, 0.2" FML, 12"CL)					
Precipitation		34.15	743,693	100	4.64	101,059
Runoff		5.17	112,659	15.15	2.27	49,439
Evapotranspiration		28.97	630,903	84.8	--	--
Percolation Through Cover		0.0034	73.6	0.0099	0.00026	5.68
Offsite Cover Design						
Offsite cover - Cover Area Limiting Rainfall Infiltration	(6" OL, 12"CL)					
Precipitation		34.15	867,642	100	4.64	117,902
Runoff		7.761	197,206	22.73	3.53	89,879
Evapotranspiration		25.07	636,995	73.42	--	--
Percolation Through Cover		1.32	33,441	3.85	0.01	259

Offcov2#.out

```
*****
*****
**
**
**
**      HYDROLOGIC EVALUATION OF LANDFILL PERFORMANCE
**      HELP MODEL VERSION 3.07 (1 NOVEMBER 1997)
**      DEVELOPED BY ENVIRONMENTAL LABORATORY
**      USAE WATERWAYS EXPERIMENT STATION
**      FOR USEPA RISK REDUCTION ENGINEERING LABORATORY
**
**
*****
*****
```

PRECIPITATION DATA FILE: C:\HELP4\ACSrain.D4
TEMPERATURE DATA FILE: C:\HELP4\ACStemp.D7
SOLAR RADIATION DATA FILE: C:\HELP4\ACSSun.D13
EVAPOTRANSPIRATION DATA: C:\HELP4\ACSevapo.D11
SOIL AND DESIGN DATA FILE: C:\HELP4\offcov2#.D10
OUTPUT DATA FILE: C:\HELP4\offcov2#.OUT

TIME: 11:43 DATE: 8/18/1998

TITLE: offsite cover

Offcay2#.out

NOTE: INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WERE
COMPUTED AS NEARLY STEADY-STATE VALUES BY THE PROGRAM.

LAYER 1

TYPE 1 - VERTICAL PERCOLATION LAYER

MATERIAL TEXTURE NUMBER 6

THICKNESS	=	6.00	INCHES
POROSITY	=	0.4530	VOL/VOL
FIELD CAPACITY	=	0.1900	VOL/VOL
WILTING POINT	=	0.0850	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.4530	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.720000011000E-03	CM/SEC

NOTE: SATURATED HYDRAULIC CONDUCTIVITY IS MULTIPLIED BY 4.63
FOR ROOT CHANNELS IN TOP HALF OF EVAPORATIVE ZONE.

LAYER 2

TYPE 1 - VERTICAL PERCOLATION LAYER

MATERIAL TEXTURE NUMBER 16

THICKNESS	=	6.00	INCHES
POROSITY	=	0.4270	VOL/VOL
FIELD CAPACITY	=	0.4180	VOL/VOL
WILTING POINT	=	0.3670	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.4240	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.100000001000E-06	CM/SEC

LAYER 3

Offcov2#.out

TYPE 3 - BARRIER SOIL LINER
MATERIAL TEXTURE NUMBER 16

THICKNESS	=	6.00	INCHES
POROSITY	=	0.4270	VOL/VOL
FIELD CAPACITY	=	0.4180	VOL/VOL
WILTING POINT	=	0.3670	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.4270	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.100000001000E-06	CM/SEC

GENERAL DESIGN AND EVAPORATIVE ZONE DATA

NOTE: SCS RUNOFF CURVE NUMBER WAS COMPUTED FROM DEFAULT
SOIL DATA BASE USING SOIL TEXTURE # 6 WITH A
GOOD STAND OF GRASS, A SURFACE SLOPE OF 2.8
AND A SLOPE LENGTH OF 800. FEET.

SCS RUNOFF CURVE NUMBER	=	57.80	
FRACTION OF AREA ALLOWING RUNOFF	=	100.0	PERCENT
AREA PROJECTED ON HORIZONTAL PLANE	=	7.000	ACRES
EVAPORATIVE ZONE DEPTH	=	12.0	INCHES
INITIAL WATER IN EVAPORATIVE ZONE	=	5.262	INCHES
UPPER LIMIT OF EVAPORATIVE STORAGE	=	5.280	INCHES
LOWER LIMIT OF EVAPORATIVE STORAGE	=	2.712	INCHES
INITIAL SNOW WATER	=	0.000	INCHES
INITIAL WATER IN LAYER MATERIALS	=	7.824	INCHES
TOTAL INITIAL WATER	=	7.824	INCHES
TOTAL SUBSURFACE INFLOW	=	0.00	INCHES/YEAR

EVAPOTRANSPIRATION AND WEATHER DATA

Offcov2#.out

NOTE: EVAPOTRANSPIRATION DATA WAS OBTAINED FROM
CHICAGO ILLINOIS

STATION LATITUDE	=	41.78 DEGREES
MAXIMUM LEAF AREA INDEX	=	3.50
START OF GROWING SEASON (JULIAN DATE)	=	117
END OF GROWING SEASON (JULIAN DATE)	=	290
EVAPORATIVE ZONE DEPTH	=	12.0 INCHES
AVERAGE ANNUAL WIND SPEED	=	10.30 MPH
AVERAGE 1ST QUARTER RELATIVE HUMIDITY	=	71.00 %
AVERAGE 2ND QUARTER RELATIVE HUMIDITY	=	65.00 %
AVERAGE 3RD QUARTER RELATIVE HUMIDITY	=	70.00 %
AVERAGE 4TH QUARTER RELATIVE HUMIDITY	=	72.00 %

NOTE: PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR CHICAGO ILLINOIS

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
1.60	1.31	2.59	3.66	3.15	4.08
3.63	3.53	3.35	2.28	2.06	2.10

NOTE: TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR CHICAGO ILLINOIS

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
21.40	26.00	36.00	48.80	59.10	68.60
73.00	71.90	64.70	53.50	39.80	27.70

Offcov2#.out

NOTE: SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR CHICAGO ILLINOIS
AND STATION LATITUDE = 41.78 DEGREES

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 100

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
PRECIPITATION						
TOTALS	1.51 4.02	1.36 3.61	2.62 3.26	3.62 2.35	3.12 2.23	4.39 2.07
STD. DEVIATIONS	0.65 1.99	0.69 1.85	1.12 1.76	1.58 1.34	1.43 1.21	2.05 1.03
RUNOFF						
TOTALS	0.397 0.209	1.146 0.164	2.538 0.286	1.294 0.259	0.159 0.512	0.218 0.581
STD. DEVIATIONS	0.600 0.590	0.874 0.556	1.644 0.735	1.364 0.699	0.467 0.853	0.596 0.794
EVAPOTRANSPIRATION						
TOTALS	0.532 3.855	0.437 3.396	0.766 2.323	2.960 1.421	3.494 1.027	4.257 0.602

			Offcov2#.out			
STD. DEVIATIONS	0.117	0.103	0.501	0.768	1.019	1.364
	1.545	1.484	0.985	0.333	0.208	0.179

PERCOLATION/LEAKAGE THROUGH LAYER 3

TOTALS	0.0073	0.0010	0.0531	0.2168	0.2107	0.0696
	0.0591	0.0606	0.0818	0.1817	0.2183	0.1561
STD. DEVIATIONS	0.0214	0.0038	0.0715	0.0604	0.0449	0.0583
	0.0589	0.0576	0.0813	0.1027	0.0981	0.0911

AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)

DAILY AVERAGE HEAD ON TOP OF LAYER 3

AVERAGES	0.1796	0.0182	1.8780	7.7384	6.4199	2.1551
	1.8326	1.8820	2.7254	6.1098	7.9177	5.2099
STD. DEVIATIONS	0.6463	0.1510	2.6144	2.2432	1.8395	1.9762
	1.9555	1.8959	2.9000	3.7935	3.8993	3.3575

AVERAGE ANNUAL TOTALS & (STD. DEVIATIONS) FOR YEARS 1 THROUGH 100

	INCHES		CU. FEET	PERCENT
PRECIPITATION	34.15 (5.545)		867642.2	100.00
RUNOFF	7.761 (2.9651)		197205.69	22.729

	Offcov2#.out		
EVAPOTRANSPIRATION	25.069 (3.3562)	636995.06	73.417
PERCOLATION/LEAKAGE THROUGH LAYER 3	1.31607 (0.33394)	33441.355	3.85428
AVERAGE HEAD ON TOP OF LAYER 3	3.672 (1.033)		
CHANGE IN WATER STORAGE	0.000 (1.4807)	0.00	0.000

PEAK DAILY VALUES FOR YEARS 1 THROUGH 100

	(INCHES)	(CU. FT.)
PRECIPITATION	4.64	117902.398
RUNOFF	3.537	89879.2812
PERCOLATION/LEAKAGE THROUGH LAYER 3	0.010205	259.30365
AVERAGE HEAD ON TOP OF LAYER 3	12.000	
SNOW WATER	7.00	177995.0000
MAXIMUM VEG. SOIL WATER (VOL/VOL)	0.4400	
MINIMUM VEG. SOIL WATER (VOL/VOL)	0.2260	

Offcov2#.out

FINAL WATER STORAGE AT END OF YEAR 100

LAYER	(INCHES)	(VOL/VOL)
1	2.7180	0.4530
2	2.5440	0.4240
3	2.5620	0.4270
SNOW WATER	0.000	

Capoff1.out

```
*****
*****
**
**
**
**      HYDROLOGIC EVALUATION OF LANDFILL PERFORMANCE      **
**      HELP MODEL VERSION 3.07  (1 NOVEMBER 1997)          **
**      DEVELOPED BY ENVIRONMENTAL LABORATORY                **
**      USAE WATERWAYS EXPERIMENT STATION                   **
**      FOR USEPA RISK REDUCTION ENGINEERING LABORATORY      **
**
**
*****
*****
```

PRECIPITATION DATA FILE: C:\HELP4\ACSrain.D4
TEMPERATURE DATA FILE: C:\HELP4\ACStemp.D7
SOLAR RADIATION DATA FILE: C:\HELP4\ACSSun.D13
EVAPOTRANSPIRATION DATA: C:\HELP4\ACSevapo.D11
SOIL AND DESIGN DATA FILE: C:\HELP4\capoff1.D10
OUTPUT DATA FILE: C:\HELP4\capoff1.OUT

TIME: 9:51 DATE: 7/30/1998

```
*****
```

TITLE: offsite cap #1 - standard RCRA cap

```
*****
```

Capoff1.out

NOTE: INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WERE
COMPUTED AS NEARLY STEADY-STATE VALUES BY THE PROGRAM.

LAYER 1

TYPE 1 - VERTICAL PERCOLATION LAYER

MATERIAL TEXTURE NUMBER 6

THICKNESS	=	6.00	INCHES
POROSITY	=	0.4530	VOL/VOL
FIELD CAPACITY	=	0.1900	VOL/VOL
WILTING POINT	=	0.0850	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.2901	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.720000011000E-03	CM/SEC

NOTE: SATURATED HYDRAULIC CONDUCTIVITY IS MULTIPLIED BY 4.63
FOR ROOT CHANNELS IN TOP HALF OF EVAPORATIVE ZONE.

LAYER 2

TYPE 1 - VERTICAL PERCOLATION LAYER

MATERIAL TEXTURE NUMBER 9

THICKNESS	=	18.00	INCHES
POROSITY	=	0.5010	VOL/VOL
FIELD CAPACITY	=	0.2840	VOL/VOL
WILTING POINT	=	0.1350	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.3304	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.190000006000E-03	CM/SEC

LAYER 3

Capoff1.out

TYPE 2 - LATERAL DRAINAGE LAYER

MATERIAL TEXTURE NUMBER 1

THICKNESS	=	12.00	INCHES
POROSITY	=	0.4170	VOL/VOL
FIELD CAPACITY	=	0.0450	VOL/VOL
WILTING POINT	=	0.0180	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.1944	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.999999978000E-02	CM/SEC
SLOPE	=	2.00	PERCENT
DRAINAGE LENGTH	=	550.0	FEET

LAYER 4

TYPE 3 - BARRIER SOIL LINER

MATERIAL TEXTURE NUMBER 36

THICKNESS	=	0.20	INCHES
POROSITY	=	0.0030	VOL/VOL
FIELD CAPACITY	=	0.0020	VOL/VOL
WILTING POINT	=	0.0010	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.0030	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.399999993000E-12	CM/SEC

LAYER 5

TYPE 1 - VERTICAL PERCOLATION LAYER

MATERIAL TEXTURE NUMBER 16

THICKNESS	=	24.00	INCHES
POROSITY	=	0.4270	VOL/VOL
FIELD CAPACITY	=	0.4180	VOL/VOL
WILTING POINT	=	0.3670	VOL/VOL

Capoff1.out

INITIAL SOIL WATER CONTENT = 0.4180 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 0.100000001000E-06 CM/SEC

GENERAL DESIGN AND EVAPORATIVE ZONE DATA

NOTE: SCS RUNOFF CURVE NUMBER WAS COMPUTED FROM DEFAULT
SOIL DATA BASE USING SOIL TEXTURE # 6 WITH A
GOOD STAND OF GRASS, A SURFACE SLOPE OF 2. %
AND A SLOPE LENGTH OF 550. FEET.

SCS RUNOFF CURVE NUMBER	=	58.90	
FRACTION OF AREA ALLOWING RUNOFF	=	100.0	PERCENT
AREA PROJECTED ON HORIZONTAL PLANE	=	6.000	ACRES
EVAPORATIVE ZONE DEPTH	=	18.0	INCHES
INITIAL WATER IN EVAPORATIVE ZONE	=	5.984	INCHES
UPPER LIMIT OF EVAPORATIVE STORAGE	=	8.730	INCHES
LOWER LIMIT OF EVAPORATIVE STORAGE	=	2.130	INCHES
INITIAL SNOW WATER	=	0.000	INCHES
INITIAL WATER IN LAYER MATERIALS	=	20.053	INCHES
TOTAL INITIAL WATER	=	20.053	INCHES
TOTAL SUBSURFACE INFLOW	=	0.00	INCHES/YEAR

EVAPOTRANSPIRATION AND WEATHER DATA

NOTE: EVAPOTRANSPIRATION DATA WAS OBTAINED FROM
CHICAGO ILLINOIS

STATION LATITUDE	=	41.78 DEGREES
MAXIMUM LEAF AREA INDEX	=	3.50
START OF GROWING SEASON (JULIAN DATE)	=	117

Capoff1.out

END OF GROWING SEASON (JULIAN DATE)	=	290
EVAPORATIVE ZONE DEPTH	=	18.0 INCHES
AVERAGE ANNUAL WIND SPEED	=	10.30 MPH
AVERAGE 1ST QUARTER RELATIVE HUMIDITY	=	71.00 %
AVERAGE 2ND QUARTER RELATIVE HUMIDITY	=	65.00 %
AVERAGE 3RD QUARTER RELATIVE HUMIDITY	=	70.00 %
AVERAGE 4TH QUARTER RELATIVE HUMIDITY	=	72.00 %

NOTE: PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR CHICAGO ILLINOIS

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
1.60	1.31	2.59	3.66	3.15	4.08
3.63	3.53	3.35	2.28	2.06	2.10

NOTE: TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR CHICAGO ILLINOIS

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
21.40	26.00	36.00	48.80	59.10	68.60
73.00	71.90	64.70	53.50	39.80	27.70

NOTE: SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR CHICAGO ILLINOIS
AND STATION LATITUDE = 41.78 DEGREES

Capoff1.out

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 100

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
	-----	-----	-----	-----	-----	-----
PRECIPITATION						

TOTALS	1.51 4.02	1.36 3.61	2.62 3.26	3.62 2.35	3.12 2.23	4.39 2.07
STD. DEVIATIONS	0.65 1.99	0.69 1.85	1.12 1.76	1.58 1.34	1.43 1.21	2.05 1.03
RUNOFF						

TOTALS	0.138 0.000	0.542 0.001	1.556 0.000	0.480 0.000	0.000 0.009	0.000 0.139
STD. DEVIATIONS	0.338 0.001	0.553 0.008	1.357 0.000	0.912 0.000	0.000 0.089	0.001 0.367
EVAPOTRANSPIRATION						

TOTALS	0.532 3.961	0.443 3.490	0.754 2.298	2.963 1.302	3.650 0.908	4.590 0.574
STD. DEVIATIONS	0.115 1.624	0.102 1.517	0.461 0.978	0.763 0.283	1.040 0.198	1.414 0.159
LATERAL DRAINAGE COLLECTED FROM LAYER 3						

TOTALS	0.4333 0.5613	0.3435 0.5087	0.3742 0.4434	0.5737 0.4287	0.6567 0.4185	0.5909 0.4681

Capoff1.out

STD. DEVIATIONS	0.1876	0.1605	0.1782	0.1514	0.1258	0.1274
	0.1466	0.1532	0.1493	0.1651	0.1728	0.1921

PERCOLATION/LEAKAGE THROUGH LAYER 4

TOTALS	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000

STD. DEVIATIONS	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000

PERCOLATION/LEAKAGE THROUGH LAYER 5

TOTALS	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000

STD. DEVIATIONS	0.0001	0.0000	0.0001	0.0001	0.0001	0.0001
	0.0001	0.0001	0.0001	0.0000	0.0001	0.0001

AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)

DAILY AVERAGE HEAD ON TOP OF LAYER 4

AVERAGES	7.0786	5.9349	6.1762	11.0068	12.3774	10.7538
	9.4674	8.2271	7.2930	7.1169	7.5908	8.2258

STD. DEVIATIONS	3.5528	2.8405	3.6069	4.9942	5.1907	4.0893
	3.5530	2.9483	2.6767	3.8080	5.5017	5.1575

Capoff1.out

AVERAGE ANNUAL TOTALS & (STD. DEVIATIONS) FOR YEARS 1 THROUGH 100

	INCHES	CU. FEET	PERCENT
PRECIPITATION	34.15 (5.545)	743693.3	100.00
RUNOFF	2.865 (1.7973)	62406.71	8.391
EVAPOTRANSPIRATION	25.466 (3.5820)	554648.81	74.580
LATERAL DRAINAGE COLLECTED FROM LAYER 3	5.80098 (1.37673)	126345.242	16.98889
PERCOLATION/LEAKAGE THROUGH LAYER 4	0.00021 (0.00007)	4.680	0.00063
AVERAGE HEAD ON TOP OF LAYER 4	8.437 (2.753)		
PERCOLATION/LEAKAGE THROUGH LAYER 5	0.00021 (0.00023)	4.647	0.00062
CHANGE IN WATER STORAGE	0.013 (3.0327)	287.96	0.039

PEAK DAILY VALUES FOR YEARS 1 THROUGH 100

	(INCHES)	(CU. FT.)
PRECIPITATION	4.64	101059.195
RUNOFF	2.059	44850.5625

Capoff1.out

DRAINAGE COLLECTED FROM LAYER 3	0.02987	650.55591
PERCOLATION/LEAKAGE THROUGH LAYER 4	0.000002	0.05352
AVERAGE HEAD ON TOP OF LAYER 4	35.919	
MAXIMUM HEAD ON TOP OF LAYER 4	45.921	
LOCATION OF MAXIMUM HEAD IN LAYER 3 (DISTANCE FROM DRAIN)	202.6 FEET	
PERCOLATION/LEAKAGE THROUGH LAYER 5	0.000464	10.10889
SNOW WATER	7.00	152567.1410
MAXIMUM VEG. SOIL WATER (VOL/VOL)	0.4850	
MINIMUM VEG. SOIL WATER (VOL/VOL)	0.1183	

*** Maximum heads are computed using McEnroe's equations. ***

Reference: Maximum Saturated Depth over Landfill Liner
by Bruce M. McEnroe, University of Kansas
ASCE Journal of Environmental Engineering
Vol. 119, No. 2, March 1993, pp. 262-270.

FINAL WATER STORAGE AT END OF YEAR 100

Capoff1.out

LAYER	(INCHES)	(VOL/VOL)
1	2.7180	0.4530
2	5.9650	0.3314
3	2.6598	0.2217
4	0.0006	0.0030
5	10.0317	0.4180
SNOW WATER	0.000	

Capoff2.out

```
*****
*****
**
**
**
**      HYDROLOGIC EVALUATION OF LANDFILL PERFORMANCE
**      HELP MODEL VERSION 3.07  (1 NOVEMBER 1997)
**      DEVELOPED BY ENVIRONMENTAL LABORATORY
**      USAE WATERWAYS EXPERIMENT STATION
**      FOR USEPA RISK REDUCTION ENGINEERING LABORATORY
**
**
*****
*****
```

PRECIPITATION DATA FILE: C:\HELP4\ACSrain.D4
TEMPERATURE DATA FILE: C:\HELP4\ACStemp.D7
SOLAR RADIATION DATA FILE: C:\HELP4\ACSSun.D13
EVAPOTRANSPIRATION DATA: C:\HELP4\ACSevapo.D11
SOIL AND DESIGN DATA FILE: C:\HELP4\capoff2.D10
OUTPUT DATA FILE: C:\HELP4\capoff2.OUT

TIME: 9:48 DATE: 7/30/1998

```
*****
TITLE:  offsite cap #2
*****
```

Capoff2.out

NOTE: INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WERE
COMPUTED AS NEARLY STEADY-STATE VALUES BY THE PROGRAM.

LAYER 1

TYPE 1 - VERTICAL PERCOLATION LAYER
MATERIAL TEXTURE NUMBER 6

THICKNESS	=	6.00	INCHES
POROSITY	=	0.4530	VOL/VOL
FIELD CAPACITY	=	0.1900	VOL/VOL
WILTING POINT	=	0.0850	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.2865	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.720000011000E-03	CM/SEC

NOTE: SATURATED HYDRAULIC CONDUCTIVITY IS MULTIPLIED BY 4.63
FOR ROOT CHANNELS IN TOP HALF OF EVAPORATIVE ZONE.

LAYER 2

TYPE 1 - VERTICAL PERCOLATION LAYER
MATERIAL TEXTURE NUMBER 9

THICKNESS	=	18.00	INCHES
POROSITY	=	0.5010	VOL/VOL
FIELD CAPACITY	=	0.2840	VOL/VOL
WILTING POINT	=	0.1350	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.4955	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.190000006000E-03	CM/SEC

LAYER 3

Capoff2.out

TYPE 3 - BARRIER SOIL LINER
MATERIAL TEXTURE NUMBER 36

THICKNESS	=	0.20	INCHES
POROSITY	=	0.0030	VOL/VOL
FIELD CAPACITY	=	0.0020	VOL/VOL
WILTING POINT	=	0.0010	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.0030	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.399999993000E-12	CM/SEC

LAYER 4

TYPE 1 - VERTICAL PERCOLATION LAYER
MATERIAL TEXTURE NUMBER 17

THICKNESS	=	0.25	INCHES
POROSITY	=	0.7500	VOL/VOL
FIELD CAPACITY	=	0.7470	VOL/VOL
WILTING POINT	=	0.4000	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.6560	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.300000003000E-08	CM/SEC

LAYER 5

TYPE 1 - VERTICAL PERCOLATION LAYER
MATERIAL TEXTURE NUMBER 16

THICKNESS	=	12.00	INCHES
POROSITY	=	0.4270	VOL/VOL
FIELD CAPACITY	=	0.4180	VOL/VOL
WILTING POINT	=	0.3670	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.4044	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.100000001000E-06	CM/SEC

GENERAL DESIGN AND EVAPORATIVE ZONE DATA

NOTE: SCS RUNOFF CURVE NUMBER WAS COMPUTED FROM DEFAULT
SOIL DATA BASE USING SOIL TEXTURE # 6 WITH A
GOOD STAND OF GRASS, A SURFACE SLOPE OF 2.%,
AND A SLOPE LENGTH OF 550. FEET.

SCS RUNOFF CURVE NUMBER	=	58.90	
FRACTION OF AREA ALLOWING RUNOFF	=	100.0	PERCENT
AREA PROJECTED ON HORIZONTAL PLANE	=	6.000	ACRES
EVAPORATIVE ZONE DEPTH	=	18.0	INCHES
INITIAL WATER IN EVAPORATIVE ZONE	=	7.633	INCHES
UPPER LIMIT OF EVAPORATIVE STORAGE	=	8.730	INCHES
LOWER LIMIT OF EVAPORATIVE STORAGE	=	2.130	INCHES
INITIAL SNOW WATER	=	0.000	INCHES
INITIAL WATER IN LAYER MATERIALS	=	15.656	INCHES
TOTAL INITIAL WATER	=	15.656	INCHES
TOTAL SUBSURFACE INFLOW	=	0.00	INCHES/YEAR

EVAPOTRANSPIRATION AND WEATHER DATA

NOTE: EVAPOTRANSPIRATION DATA WAS OBTAINED FROM
CHICAGO ILLINOIS

STATION LATITUDE	=	41.78	DEGREES
MAXIMUM LEAF AREA INDEX	=	3.50	
START OF GROWING SEASON (JULIAN DATE)	=	117	
END OF GROWING SEASON (JULIAN DATE)	=	290	
EVAPORATIVE ZONE DEPTH	=	18.0	INCHES

Capoff2.out

AVERAGE ANNUAL WIND SPEED = 10.30 MPH
 AVERAGE 1ST QUARTER RELATIVE HUMIDITY = 71.00 %
 AVERAGE 2ND QUARTER RELATIVE HUMIDITY = 65.00 %
 AVERAGE 3RD QUARTER RELATIVE HUMIDITY = 70.00 %
 AVERAGE 4TH QUARTER RELATIVE HUMIDITY = 72.00 %

NOTE: PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING
 COEFFICIENTS FOR CHICAGO ILLINOIS

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
1.60	1.31	2.59	3.66	3.15	4.08
3.63	3.53	3.35	2.28	2.06	2.10

NOTE: TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING
 COEFFICIENTS FOR CHICAGO ILLINOIS

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
21.40	26.00	36.00	48.80	59.10	68.60
73.00	71.90	64.70	53.50	39.80	27.70

NOTE: SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING
 COEFFICIENTS FOR CHICAGO ILLINOIS
 AND STATION LATITUDE = 41.78 DEGREES

Capoff2.out

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 100

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC

PRECIPITATION						

TOTALS	1.51 4.02	1.36 3.61	2.62 3.26	3.62 2.35	3.12 2.23	4.39 2.07
STD. DEVIATIONS	0.65 1.99	0.69 1.85	1.12 1.76	1.58 1.34	1.43 1.21	2.05 1.03
RUNOFF						

TOTALS	0.229 0.051	0.795 0.023	2.058 0.017	1.152 0.100	0.165 0.148	0.135 0.298
STD. DEVIATIONS	0.395 0.281	0.719 0.227	1.650 0.139	1.337 0.485	0.477 0.506	0.433 0.570
EVAPOTRANSPIRATION						

TOTALS	0.532 5.255	0.444 3.807	0.750 2.312	2.946 1.188	3.669 0.861	6.636 0.566
STD. DEVIATIONS	0.115 1.917	0.102 1.752	0.457 0.963	0.736 0.216	1.013 0.185	0.557 0.151
PERCOLATION/LEAKAGE THROUGH LAYER 3						

TOTALS	0.0000 0.0000	0.0000 0.0000	0.0000 0.0000	0.0000 0.0000	0.0000 0.0000	0.0000 0.0000
STD. DEVIATIONS	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000

	0.0000	Capoff2.out 0.0000	0.0000	0.0000	0.0000	0.0000
PERCOLATION/LEAKAGE THROUGH LAYER 5						
TOTALS	0.0004	0.0003	0.0003	0.0003	0.0003	0.0003
	0.0003	0.0003	0.0003	0.0003	0.0003	0.0003
STD. DEVIATIONS	0.0008	0.0007	0.0007	0.0007	0.0006	0.0006
	0.0006	0.0006	0.0005	0.0005	0.0005	0.0005

 AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)

DAILY AVERAGE HEAD ON TOP OF LAYER 3						
AVERAGES	6.8298	6.1278	8.7383	17.9848	18.8149	14.6068
	8.7411	6.9634	7.0319	8.5146	11.2893	12.4595
STD. DEVIATIONS	1.7171	0.7025	4.0064	3.9165	1.8539	2.7398
	3.7320	2.3759	2.9159	4.6419	5.7656	5.4093

AVERAGE ANNUAL TOTALS & (STD. DEVIATIONS) FOR YEARS 1 THROUGH 100

	INCHES		CU. FEET	PERCENT
PRECIPITATION	34.15	(5.545)	743693.3	100.00
RUNOFF	5.171	(2.6145)	112632.85	15.145
EVAPOTRANSPIRATION	28.967	(3.6084)	630898.50	84.833

Capoff2.out

PERCOLATION/LEAKAGE THROUGH LAYER 3	0.00027 (0.00004)	5.892	0.00079
AVERAGE HEAD ON TOP OF LAYER 3	10.675 (1.746)		
PERCOLATION/LEAKAGE THROUGH LAYER 5	0.00381 (0.00728)	83.079	0.01117
CHANGE IN WATER STORAGE	0.004 (2.6482)	78.80	0.011

PEAK DAILY VALUES FOR YEARS 1 THROUGH 100

	(INCHES)	(CU. FT.)
PRECIPITATION	4.64	101059.195
RUNOFF	2.270	49450.7578
PERCOLATION/LEAKAGE THROUGH LAYER 3	0.000002	0.03586
AVERAGE HEAD ON TOP OF LAYER 3	24.000	
PERCOLATION/LEAKAGE THROUGH LAYER 5	0.000216	4.70553
SNOW WATER	7.00	152567.1410
MAXIMUM VEG. SOIL WATER (VOL/VOL)		0.4850
MINIMUM VEG. SOIL WATER (VOL/VOL)		0.1183

Capoff2.out

FINAL WATER STORAGE AT END OF YEAR 100

LAYER	(INCHES)	(VOL/VOL)
1	2.7180	0.4530
2	8.6367	0.4798
3	0.0006	0.0030
4	0.1360	0.5441
5	4.5265	0.3772

SNOW WATER 0.000

Offcap2.out

```
*****
*****
**
**
**
**      HYDROLOGIC EVALUATION OF LANDFILL PERFORMANCE      **
**      HELP MODEL VERSION 3.07 (1 NOVEMBER 1997)          **
**      DEVELOPED BY ENVIRONMENTAL LABORATORY              **
**      USAE WATERWAYS EXPERIMENT STATION                 **
**      FOR USEPA RISK REDUCTION ENGINEERING LABORATORY    **
**
**
*****
*****
```

PRECIPITATION DATA FILE: C:\HELP4\ACSrain.D4
TEMPERATURE DATA FILE: C:\HELP4\ACStemp.D7
SOLAR RADIATION DATA FILE: C:\HELP4\ACSSun.D13
EVAPOTRANSPIRATION DATA: C:\HELP4\ACSevapo.D11
SOIL AND DESIGN DATA FILE: C:\HELP4\offcap2.D10
OUTPUT DATA FILE: C:\HELP4\offcap2.OUT

TIME: 9:11 DATE: 7/30/1998

```
*****
TITLE: offsite final cap #3
*****
```

Offcap2.out

NOTE: INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WERE
COMPUTED AS NEARLY STEADY-STATE VALUES BY THE PROGRAM.

LAYER 1

TYPE 1 - VERTICAL PERCOLATION LAYER
MATERIAL TEXTURE NUMBER 6

THICKNESS	=	6.00	INCHES
POROSITY	=	0.4530	VOL/VOL
FIELD CAPACITY	=	0.1900	VOL/VOL
WILTING POINT	=	0.0850	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.2916	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.720000011000E-03	CM/SEC

NOTE: SATURATED HYDRAULIC CONDUCTIVITY IS MULTIPLIED BY 4.63
FOR ROOT CHANNELS IN TOP HALF OF EVAPORATIVE ZONE.

LAYER 2

TYPE 1 - VERTICAL PERCOLATION LAYER
MATERIAL TEXTURE NUMBER 9

THICKNESS	=	12.00	INCHES
POROSITY	=	0.5010	VOL/VOL
FIELD CAPACITY	=	0.2840	VOL/VOL
WILTING POINT	=	0.1350	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.5010	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.190000006000E-03	CM/SEC

LAYER 3

Offcap2.out

TYPE 3 - BARRIER SOIL LINER
MATERIAL TEXTURE NUMBER 36

THICKNESS	=	0.20	INCHES
POROSITY	=	0.0030	VOL/VOL
FIELD CAPACITY	=	0.0020	VOL/VOL
WILTING POINT	=	0.0010	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.0030	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.399999993000E-12	CM/SEC

LAYER 4

TYPE 1 - VERTICAL PERCOLATION LAYER
MATERIAL TEXTURE NUMBER 16

THICKNESS	=	12.00	INCHES
POROSITY	=	0.4270	VOL/VOL
FIELD CAPACITY	=	0.4180	VOL/VOL
WILTING POINT	=	0.3670	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.4049	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.100000001000E-06	CM/SEC

GENERAL DESIGN AND EVAPORATIVE ZONE DATA

NOTE: SCS RUNOFF CURVE NUMBER WAS COMPUTED FROM DEFAULT
SOIL DATA BASE USING SOIL TEXTURE # 6 WITH A
GOOD STAND OF GRASS, A SURFACE SLOPE OF 2.8
AND A SLOPE LENGTH OF 550. FEET.

SCS RUNOFF CURVE NUMBER	=	58.90	
FRACTION OF AREA ALLOWING RUNOFF	=	100.0	PERCENT

Offcap2.out

AREA PROJECTED ON HORIZONTAL PLANE	=	6.000	ACRES
EVAPORATIVE ZONE DEPTH	=	18.0	INCHES
INITIAL WATER IN EVAPORATIVE ZONE	=	7.761	INCHES
UPPER LIMIT OF EVAPORATIVE STORAGE	=	8.730	INCHES
LOWER LIMIT OF EVAPORATIVE STORAGE	=	2.130	INCHES
INITIAL SNOW WATER	=	0.000	INCHES
INITIAL WATER IN LAYER MATERIALS	=	12.621	INCHES
TOTAL INITIAL WATER	=	12.621	INCHES
TOTAL SUBSURFACE INFLOW	=	0.00	INCHES/YEAR

EVAPOTRANSPIRATION AND WEATHER DATA

NOTE: EVAPOTRANSPIRATION DATA WAS OBTAINED FROM
CHICAGO ILLINOIS

STATION LATITUDE	=	41.78	DEGREES
MAXIMUM LEAF AREA INDEX	=	3.50	
START OF GROWING SEASON (JULIAN DATE)	=	117	
END OF GROWING SEASON (JULIAN DATE)	=	290	
EVAPORATIVE ZONE DEPTH	=	18.0	INCHES
AVERAGE ANNUAL WIND SPEED	=	10.30	MPH
AVERAGE 1ST QUARTER RELATIVE HUMIDITY	=	71.00	%
AVERAGE 2ND QUARTER RELATIVE HUMIDITY	=	65.00	%
AVERAGE 3RD QUARTER RELATIVE HUMIDITY	=	70.00	%
AVERAGE 4TH QUARTER RELATIVE HUMIDITY	=	72.00	%

NOTE: PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR CHICAGO ILLINOIS

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
-----	-----	-----	-----	-----	-----

Offcap2.out

1.60	1.31	2.59	3.66	3.15	4.08
3.63	3.53	3.35	2.28	2.06	2.10

NOTE: TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR CHICAGO ILLINOIS

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
21.40	26.00	36.00	48.80	59.10	68.60
73.00	71.90	64.70	53.50	39.80	27.70

NOTE: SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR CHICAGO ILLINOIS
AND STATION LATITUDE = 41.78 DEGREES

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 100

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
PRECIPITATION						
TOTALS	1.51 4.02	1.36 3.61	2.62 3.26	3.62 2.35	3.12 2.23	4.39 2.07
STD. DEVIATIONS	0.65	0.69	1.12	1.58	1.43	2.05

	1.99	1.85	Offcap2.out 1.76	1.34	1.21	1.03
RUNOFF						
TOTALS	0.229	0.795	2.059	1.152	0.165	0.135
	0.052	0.023	0.018	0.099	0.148	0.298
STD. DEVIATIONS	0.395	0.719	1.649	1.337	0.477	0.433
	0.283	0.227	0.142	0.482	0.506	0.570
EVAPOTRANSPIRATION						
TOTALS	0.532	0.444	0.750	2.946	3.669	6.636
	5.254	3.808	2.313	1.188	0.861	0.566
STD. DEVIATIONS	0.115	0.102	0.457	0.736	1.013	0.557
	1.918	1.752	0.963	0.216	0.185	0.151
PERCOLATION/LEAKAGE THROUGH LAYER 3						
TOTALS	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
STD. DEVIATIONS	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
PERCOLATION/LEAKAGE THROUGH LAYER 4						
TOTALS	0.0004	0.0003	0.0004	0.0004	0.0004	0.0004
	0.0002	0.0001	0.0001	0.0002	0.0003	0.0003
STD. DEVIATIONS	0.0009	0.0008	0.0008	0.0007	0.0007	0.0006
	0.0004	0.0002	0.0003	0.0005	0.0006	0.0006

AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)

Offcap2.out

DAILY AVERAGE HEAD ON TOP OF LAYER 3

AVERAGES	3.3923	2.5440	4.7938	12.4125	12.8149	8.6066
	2.7432	0.9631	1.0295	2.5138	5.2894	7.3420
STD. DEVIATIONS	2.3203	1.4015	3.7412	3.5002	1.8545	2.7432
	3.7349	2.3731	2.9070	4.6385	5.7646	5.5622

AVERAGE ANNUAL TOTALS & (STD. DEVIATIONS) FOR YEARS 1 THROUGH 100

	INCHES	CU. FEET	PERCENT
PRECIPITATION	34.15 (5.545)	743693.3	100.00
RUNOFF	5.173 (2.6122)	112659.52	15.149
EVAPOTRANSPIRATION	28.967 (3.6094)	630902.94	84.834
PERCOLATION/LEAKAGE THROUGH LAYER 3	0.00014 (0.00005)	2.986	0.00040
AVERAGE HEAD ON TOP OF LAYER 3	5.370 (1.804)		
PERCOLATION/LEAKAGE THROUGH LAYER 4	0.00338 (0.00664)	73.595	0.00990
CHANGE IN WATER STORAGE	0.003 (2.6475)	57.34	0.008

PEAK DAILY VALUES FOR YEARS 1 THROUGH 100

	(INCHES)	(CU. FT.)
PRECIPITATION	4.64	101059.195
RUNOFF	2.270	49438.8359
PERCOLATION/LEAKAGE THROUGH LAYER 3	0.000001	0.02699
AVERAGE HEAD ON TOP OF LAYER 3	18.000	
PERCOLATION/LEAKAGE THROUGH LAYER 4	0.000261	5.68639
SNOW WATER	7.00	152567.1410
MAXIMUM VEG. SOIL WATER (VOL/VOL)		0.4850
MINIMUM VEG. SOIL WATER (VOL/VOL)		0.1183

FINAL WATER STORAGE AT END OF YEAR 100

LAYER	(INCHES)	(VOL/VOL)
1	2.7180	0.4530

Offcap2.out
2 5.6308 0.4692
3 0.0006 0.0030
4 4.5345 0.3779

SNOW WATER 0.000

